





Appendix 1. – Plates



REV.	DATE	DESCRIPTION	BY	CHKD.	REV'D.	APP'D.
PANAMA CANAL COMMISSION						
ENGINEERING AND CONSTRUCTION BUREAU ENGINEERING DIVISION BALBOA HEIGHTS, REPUBLIC OF PANAMA						
MITER GATE STUDY						
GATUN LOCKS GATE LEAFS 13 - 20						
SCALE: 1:		DATE: XXX				
DESIGNED: R. A. ALLWES		SUBMITTED: _____				
DRAWN: COC		CHIEF STRUCTURAL BRANCH				
CHECKED: XXX		APPROVED: _____				
		CHIEF, ENGINEERING DIVISION				

ALL DIMENSIONS AND/OR DIMENSIONS SHOWN IN CALLOUTS/NOTES ARE IN METERS UNLESS OTHERWISE NOTED.

JOB SAFETY DEPENDS ON YOU

A

B

C

D

E

1

1

2

2

3



3

4

4

5


5




REV.	DATE	DESCRIPTION	BY	CHKD.	REVIS.	APPR.
PANAMA CANAL COMMISSION						
ENGINEERING AND CONSTRUCTION BUREAU ENGINEERING DIVISION BALBOA HEIGHTS, REPUBLIC OF PANAMA						
MITER GATE STUDY						
PEDRO MIGUEL LOCKS GATE LEAFS 50-57						
SCALE: 1"			DATE: XXX			
DESIGNED: R. A. ALLVES	SUBMITTED:			CHIEF STRUCTURAL BRANCH		
DRAWN: CDC	CHECKED: XXX			APPROVED: CHIEF ENGINEERING DIVISION		

ALL DIMENSIONS AND/OR DIMENSIONS SHOWN IN CALLOUTS/NOTES ARE IN METERS UNLESS OTHERWISE NOTED.

JOB SAFETY DEPENDS ON YOU



ELEVATION
SCALE: 1:1



PLAN
GATE LEAFS 58-61
SCALE: 1:1

ALL DIMENSIONS AND/OR DIMENSIONS SHOWN IN CALLOUTS/NOTES ARE IN METERS UNLESS OTHERWISE NOTED.

REV.	DATE	DESCRIPTION	BY	CHKD.	REVIS.	APPR.
PANAMA CANAL COMMISSION						
ENGINEERING AND CONSTRUCTION BUREAU ENGINEERING DIVISION BALBOA HEIGHTS, REPUBLIC OF PANAMA						
MITER GATE STUDY						
PEDRO MIGUEL LOCKS GATE LEAFS 58-61						
SCALE: 1:1			DATE: XXX			
DESIGNED: R. A. ALLVES			SUBMITTED: _____			
DRAWN: CDC			CHECKED: _____			
CHECKED: XXX			APPROVED: _____			

JOB SAFETY DEPENDS ON YOU

A

B

C

D

E

1

1

2

2

3

3


4

4


5

5

FLOW




ELEVATION
SCALE: 1:1



8.48 9.72 15.24 10.06 18.29 12.42 10.47

FLOW




PERIMETER = 84.8
SURFACE AREA = 118.8 SQ M

PERIMETER = 83.9
SURFACE AREA = 118.0 SQ M

PERIMETER = 100.1
SURFACE AREA = 243.0 SQ M

PERIMETER = 93.7
SURFACE AREA = 234.5 SQ M

PLAN
GATE LEAFS 62-69
SCALE: 1:1



A

ALL DIMENSIONS AND/OR DIMENSIONS SHOWN IN CALLOUTS/NOTES ARE IN METERS UNLESS OTHERWISE NOTED.

JOB SAFETY DEPENDS ON YOU


REV.	DATE	DESCRIPTION	BY	CHKD.	REVL.	APPR.
PANAMA CANAL COMMISSION						
ENGINEERING AND CONSTRUCTION BUREAU ENGINEERING DIVISION BALBOA HEIGHTS, REPUBLIC OF PANAMA						
MITER GATE STUDY						
PEDRO MIGUEL LOCKS GATE LEAFS 62-69						
SCALE: 1:1		DATE: XXX				
DESIGNED: R. A. ALLVES	SUBMITTED: _____		CHIEF STRUCTURAL ENGINEER			
DRAWN: EAT	CHECKED: XXX		APPROVED: _____			
		CHIEF ENGINEERING DIVISION				

A


B

C

D




NEW SEAL STEEL
DETAIL 1
 SCALE: 1"



SECTION A
 SCALE: 1"

*NOTE: ALL ANCHORS & DOWELS TO BE INSTALLED USING EPOXY-RESIN GROUT. HOLE DIA TO MANUFACTURERS RECOMMENDATION




PLAN
 SCALE: 1"


ALL DIMENSIONS AND/OR DIMENSIONS SHOWN IN CALLOUTS/NOTES ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.

JOB SAFETY DEPENDS ON YOU


NO.	DATE	DESCRIPTION	BY	CHKD.	APP.
PANAMA CANAL COMMISSION					
ENGINEERING AND CONSTRUCTION BUREAU					
ISLAND GENERAL SERVICES OF PANAMA					
MITER GATE STUDY					
CAST-IN-PLACE SILL					
610 REMOVAL OF EXISTING SILL					
SCALE: AS SHOWN			DATE: 2002		
DESIGNED: []	CHECKED: []	APPROVED: []	DATE: []	BY: []	APP. []
DRAWN: []	REV. []	DATE: []	BY: []	APP. []	
REVISION: []	DATE: []	BY: []	APP. []		



NEW SEAL STEEL
DETAIL
 SCALE: 1:1



SECTION
 SCALE: 1:1




PLAN
 SCALE: 1:1

ALL DIMENSIONS AND/OR DIMENSIONS SHOWN IN CALLOUTS/NOTES ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.


NO.	REV.	DESCRIPTION	BY	CHKD.	DATE
PANAMA CANAL COMMISSION					
ENGINEERING AND CONSTRUCTION BUREAU <small>REPUBLIC OF PANAMA</small>					
MITER GATE STUDY					
CAST-IN-PLACE SILL ALTERNATIVE 'W'					
SCALE: AS SHOWN			DATE: 2000		
DESIGNED BY	CHECKED BY	DATE	APPROVED BY	DATE	

JOB SAFETY DEPENDS ON YOU




*NOTE: ALL ANCHORS & DOWELS TO BE INSTALLED USING EPOXY-RESIN GROUT, HOLE DIA TO MANUFACTURERS RECOMMENDATION.


SECTION A
SCALE: 1:1




SECTION B
SCALE: 1:1



ELEVATION
SCALE: 1:1




PLAN
SCALE: 1:1



TYPICAL MITER SILL

PLAN
SCALE: 1:1




SPlice DETAIL 1
SCALE: 1:1


ALL DIMENSIONS AND/OR DIMENSIONS SHOWN IN CALLOUTS/NOTES ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.

JOB SAFETY DEPENDS ON YOU


NO.	REV.	DESCRIPTION	DATE	BY	CHK.
PANAMA CANAL COMMISSION					
ENGINEERING AND CONSTRUCTION BUREAU					
DR. JUAN RIVERA, DIRECTOR					
MITER GATE STUDY					
CAST-IN-PLACE ALTERNATIVE 1B					
SCALE: AS SHOWN			DATE: 2008		
DESIGNED: <u> </u>	DRAWN: <u> </u>		CHECKED: <u> </u>		
REVISED: <u> </u>	DATE: <u> </u>		APPROVED: <u> </u>		
ISSUED: <u> </u>	BY: <u> </u>		FOR: <u> </u>		




SECTION A
SCALE: 1:1




ANCHOR BOLT DETAIL 1
SCALE: 1:1



LEVELING/PICKING DEVICE DETAIL 2
SCALE: 1:1




TYPICAL "A" PANELS
A1 PANELS SHOWN, A2 PANELS OPPOSITE HAND




TYPICAL "B" PANELS
B1 PANELS SHOWN, B2 PANELS OPPOSITE HAND

PLAN
SCALE: 1:1



TYPICAL JOINT SECTION B
SCALE: 1:1




TYPICAL MITER SILL

PLAN
SCALE: 1:1

ALL DIMENSIONS AND/OR DIMENSIONS SHOWN IN CALLOUTS/NOTES ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.

NO.	REV.	DESCRIPTION	BY	CHKD.	DATE
PANAMA CANAL COMMISSION					
ENGINEERING AND CONSTRUCTION BUREAU BUILDING DIVISION P.O. BOX 10000, PANAMA, CANAL ZONE					
MITER GATE STUDY					
610 REMOVAL OF EXISTING SILL PRECAST PANEL NEW SILL					
SCALE: AS SHOWN			DATE: 10/11/11		
DESIGNED BY:	DRAWN BY:		CHECKED BY:		APPROVED BY:
DATE:	DATE:		DATE:		DATE:

JOB SAFETY DEPENDS ON YOU




MITER GATES TO BE MODIFIED

GATUN - M.G. NO'S 13-16 AND 17-20
 PEDRO MIGUEL - M.G. NO'S 54-69

TYPICAL MITER GATE EXTENSION

SCALE: 1:



DETAIL

SCALE: 1:

Table 1. - Miter Gate and Miter Gate Sill Information for Existing Condition

Lock	Miter Gates			Existing Condition					
	No.	Type	Height m	MG Sill EL m	Chamber Floor EL m	Low Water EL m	MG Sed EL m	Minimum Draft m	MG-Chamber FL Clearance mm
Gatun	13-16	Man	23.72	-4.14	-4.75	8.23	-4.32	12.37	216
	17-20	Intermediate	23.72	-4.14	-4.75	8.23	-4.32	12.37	216
Pedro Miguel	54-57	Man	24.08	3.96	3.35	16.31	3.79	12.34	216
	58-61	Intermediate	24.08	3.96	3.35	16.31	3.79	12.34	216
	62-65	Man	24.08	3.96	3.35	16.31	3.79	12.34	216
	66-69	Man	24.08	3.96	3.35	16.31	3.79	12.34	216

Table 2. - Miter Gate and Miter Gate Sill Information for Future Modification.

Lock	Miter Gates			Future Modification					
	No.	Type	Height m	MG Sill EL m	Chamber Floor EL m	Low Water EL m	MG Sed EL m	Minimum Draft m	MG-Chamber FL Clearance mm
Gatun	13-16	Man	23.81	-4.44	-4.75	8.23	-4.57	12.67	128
	17-20	Intermediate	23.81	-4.44	-4.75	8.23	-4.57	12.67	128
Pedro Miguel	54-57	Man	24.17	3.66	3.35	16.31	3.54	12.65	128
	58-61	Intermediate	24.17	3.66	3.35	16.31	3.54	12.65	128
	62-65	Man	24.17	3.66	3.35	16.31	3.54	12.65	128
	66-69	Man	24.17	3.66	3.35	16.31	3.54	12.65	128

GENERAL NOTES:

1. ALL STEEL ASTM A36.
2. RUBBER SEAL MODEL NO. 2990 FROM BUCKHORN RUBBER PRODUCTS, INC.
3. ALL BOLTS SHALL BE ASTM A325 TYPE 3.

ALL DIMENSIONS AND/OR DIMENSIONS SHOWN IN CALLOUTS/NOTES ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.

JOB SAFETY DEPENDS ON YOU

REV.	DATE	DESCRIPTION	BY	CHKD.	APPRD.
PANAMA CANAL COMMISSION					
ENGINEERING AND CONSTRUCTION BUREAU ENGINEERING DIVISION BALBOA HEIGHTS, REPUBLIC OF PANAMA					
MITER GATE STUDY					
MITER GATE EXTENSION SECTION AND DETAIL					
SCALE: AS SHOWN			DATE:		
DESIGNED: B. ALLVES			SUBMITTED:	DISAPPROVED:	
DRAWN: JET			CHECKED: XXX	APPROVED: _____	

Appendix 2. – Miter Gate Bottom Extension: Calculations



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 1 of Pages

Subject PANAMA CANAL MITER GATE STUDY

Computed by SRS Date 12/7/99

Computation LOWER SILL OPTION - ASSUMPTIONS

Checked by AAH Date 12/11/01

DESIGN ASSUMPTIONS

- 1.) LOWERING OF 37-40, 50-53, 62-69, 70-73, 100-103, AND 104-107 MITER GATES.

AFTER COMPARING THE LIFT HEIGHTS FOR ALL MITER GATES A LIFT OF 51.17 ft FOR 37-40 AND 50-53 AND A LIFT OF 44.17 ft FOR M.G. 70-73 AND 100-103 ARE CLOSE IN RANGE FOR DESIGN. I WILL DESIGN THE EXTENSION OF THE FOLLOWING MITER GATES FOR A HEAD OF 51.17 ft. THIS ANALYSIS CAN BE FOUND IN PAGE 5 TO 25.

THE DESIGN HEAD FOR M.G. 62-69 AND M.G. 104-107 ARE SIMILAR (75.5 ft AND 73.83 ft). THEREFORE DESIGN EXTENSION FOR A DESIGN HEAD OF 75.5 ft. THIS ANALYSIS CAN BE FOUND ON PAGE 16 OF 25.

- 2) THE DESIGN ARE BROKEN UP INTO 2 ANALYSIS.

- 1) 54'-8" GATE FOR A HEAD OF 51.17 ft.
- 2) 79'-0" GATE FOR A HEAD OF 75.5 ft.

- 3) SEE DRAWING FOR SEQUENCE OF WORK.

- 4) FOR EXTENSION OF THE MITER GATE I MOVED THE SEAL LOCATION 1'-0" LOWER FROM THE EXISTING LOCATION. I WILL PUT AN EXTENSION OF THE SKIN PLATE AND PROVIDE STIFFENERS TO SUPPORT THE NEW SKIN PLATE EXTENSION LOCATED AT EVERY EXISTING STIFFENER ON THE LOWER GIRDER OF THE MITER GATES. SEE ATTACHED FOR DRAWING OF BOTTOM GIRDER OF MITER GATE.

THE BOTTOM GIRDER OF MITER GATE WILL HAVE TO BE CHECKED FOR ADDITIONAL BIAXIAL BENDING DUE TO THE EXTENSION. THIS ANALYSIS WAS NOT DONE IN THIS STUDY.

- 5) THE ONLY LOAD CONDITION USED IN THIS ANALYSIS WAS NORMAL OPERATING. FOR FUTURE DESIGN SUCH AS PLANS & SPECS A FURTHER ANALYSIS OF EXISTING AND EXTREME CONDITION WILL NEED TO BE PERFORMED. EXTREME WOULD CONSIDER DEBRIS LOAD SUCH AS LOG OR MISC. STUCK BETWEEN SILL AND GATE WHICH WOULD INDUCE CONCENTRATED LOAD ON EXTENSION.



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 2 of Pages

Subject PANAMA CANAL MITER GATE STUDY

Computed by SRS Date 12/5/99

Computation LOWER SILL OPTION - ASSUMPTIONS

Checked by AH Date 12/11/01

6) THE QUIN END OF THE MITER GATE WILL NOT NEED TO BE MODIFIED. THE SEAL ON LEAF WILL NEED A PIECE OF RUBBER TO CONNECT THE QUIN SEAL WITH GATE SEAL. SEE DRAWING FOR DETAILS.

 US Army Corps of Engineers Ohio River Division Pittsburgh District	COMPUTATION SHEET	Computed by: SRS
		Date: 11/9/99
		Checked by: KJH
		Date: 11/9/99
		Page: 6
SUBJECT: Panama Canal Miter Gate Study		
COMPUTATION: Skin Plate Design		


Lake Elevation Seal Elevation Plate Elevation Design Head
 (Gatun Highest = 87.5) ft 35.717 ft 35.133 32.367 ft

Water Density = 62.5 pcf

WATER PRESSURE q = 22.73 psi conservative uniform

SKIN PLATE DESIGN

t = 0.6875 inch plate
 Steel Fy = 36000 psi
 Steel E = 29000000 psi
 PANEL a = 18.968 inch a/b = 0.7158
 PANEL b = 26.5 inch
 Difference = 0.0488



Three edges simple supported and one end free Case 2a

	A/B	0.5	0.667	1	1.5	2	4	
β		0.36	0.45	0.67	0.7700	0.79	0.8	0.4822 interpolate
α		0.08	0.106	0.14	0.1600	0.165	0.167	0.1110 interpolate

Max. Bending Stress = $\sigma = \frac{\beta * q * b^2}{t^2} = 16284 < 22410 \text{ psi}$ Type B Loading EM 1110-2-2105
Good allowable stress = .83*.75*Fy REFERENCE 1

Max. Deflection = $y = \frac{\alpha * q * b^4}{E * t^3} = 0.1320 \text{ inch}$

PANEL a = 26.5 inch a/b = 1.3971
 PANEL b = 18.968 inch
 Difference = 0.40

Three edges fixed and one edge free Case 10a:


	A/B	0.25	0.5	0.75	1	1.5	2	3	0.5
β_1		0.02	0.081	0.173	0.321	0.727	1.226	2.105	0.6434 interpolate
β_2		0.016	0.066	0.148	0.259	0.484	0.605	0.519	0.4377 interpolate
β_3		0.031	0.126	0.286	0.511	1.073	1.568	1.982	0.9373 interpolate
γ_1		0.114	0.23	0.341	0.457	0.673	0.845	1.012	0.6285 interpolate
γ_2		0.125	0.248	0.371	0.51	0.859	1.212	1.0627	0.7872 interpolate

At $x = a/2, z = b/2$:

Max. Bending Stress = $\sigma = \frac{\beta_3 * q * b^2}{t^2} = 16563 < 22410 \text{ psi}$ Type B Loading EM 1110-2-2105
Good allowable stress = .83*.75*Fy REFERENCE 1

R is the reaction force per unit length normal to the plate surface exerted by the boundary support on the edge of the plate

R at location Z = 0 and X = 0 $R = \gamma_1 * q * b = 270.97 \text{ lb/inch}$



11/16 inch Plate is Good

Job No		Sheet No	Rev
Part 54'-8" skin plate extension		1	
Ref			
By SRS		Date 10-Nov-99	Chd
File skin54.std		Date/Time	10-Nov-1999 13:49

Software licensed to US Army COE - Pittsburgh
 Job Title Panama Canal Miter Gate Study

Client PCC

Job Information

Engineer	Checked	Approved
Name: SRS	<i>MS</i>	
Date: 10-Nov-99	12-11-01	

Comments

Extension of skin plate due to the LOWER SILL OPTION - 1 ft FOR 54'-8" MITER GATE

Structure Type SPACE FRAME

Number of Nodes	121	Highest Node	121
Number of Plates	100	Highest Plate	100

Number of Basic Load Cases	1
Number of Combination Load Cases	0

Included in this printout are data for:

All	The Whole Structure
-----	---------------------

Included in this printout are results for load cases:

Type	L/C	Name
Primary	1	WATER LOAD



Software licensed to US Army COE - Pittsburgh

Job Title Panama Canal Miter Gate Study

Job No	Sheet No	Rev
	2	
Part 54'-8" skin plate extension		
Ref		
By: SRS	Date: 10-Nov-99	Chd
File: skin54.std	Date/Time: 10-Nov-1999 13:49	

Client PCC

Node Displacement Summary

Node	L/C	X (in)	Y (in)	Z (in)	Resultant (in)	rX (rad)	rY (rad)	rZ (rad)
Max X	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00001	-0.01653	0.00000
Min X	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00001	-0.01653	0.00000
Max Y	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00001	-0.01653	0.00000
Min Y	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00001	-0.01653	0.00000
Max Z	1:WATER LOA	0.000	0.000	0.138	0.138	-0.00739	0.00000	0.00000
Min Z	1:WATER LOA	0.000	0.000	-0.000	0.000	-0.00015	-0.00044	0.00000
Max rX	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00001	-0.01653	0.00000
Min rX	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00937	0.00000	0.00000
Max rY	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00001	0.01653	0.00000
Min rY	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00001	-0.01653	0.00000
Max rZ	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00001	-0.01653	0.00000
Min rZ	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00001	-0.01653	0.00000
Max Rst	1:WATER LOA	0.000	0.000	0.138	0.138	-0.00739	0.00000	0.00000

Plate Centre Stress Summary

Plate	L/C	Shear			Membrane			Bending		
		Qx (ksi)	Qy (ksi)	Fx (ksi)	Fy (ksi)	Fxy (ksi)	Mxx (kip in/in)	Myy (kip in/in)	Mxy (kip in/in)	
Max Qx	1:WATER LOA	0.692	0.208	0.000	0.000	0.000	0.367	0.093	0.396	
Max Qy	1:WATER LOA	-0.220	0.440	0.000	0.000	0.000	0.085	0.101	-0.614	
Max Fx	1:WATER LOA	0.692	0.208	0.000	0.000	0.000	0.367	0.093	0.396	
Max Fy	1:WATER LOA	0.692	0.208	0.000	0.000	0.000	0.367	0.093	0.396	
Max Fxy	1:WATER LOA	0.692	0.208	0.000	0.000	0.000	0.367	0.093	0.396	



Software licensed to US Army COE - Pittsburgh

Job Title Panama Canal Miter Gate Study

Job No	Sheet No	Rev
	3	
Part 54'-8" skin plate extension		
Ref		
By SRS	Date 10-Nov-99	Chd
File skin54.std	Date/Time 10-Nov-1999 13:49	

Client PCC

Plate Centre Stress Summary Cont..

Plate	L/C	Shear			Membrane			Bending			
		Qx (ksi)	Qy (ksi)	Fx (ksi)	Fy (ksi)	Fxy (ksi)	Mix (kip/in/in)	My (kip/in/in)	Mxy (kip/in/in)		
Max Mx	51	1:WATER LOA	-0.093	0.059	0.000	0.000	0.000	0.000	1.370	0.053	-0.059
Max My	56	1:WATER LOA	-0.020	-0.084	0.000	0.000	0.000	0.000	0.884	0.502	-0.076
Max Mxy	99	1:WATER LOA	-0.220	0.440	0.000	0.000	0.000	0.000	0.085	0.101	-0.614

Plate Centre Principal Stress Summary

Plate	L/C	Principal		Von Mis		
		Top (ksi)	Bottom (ksi)	Top (ksi)	Bottom (ksi)	
Max (t)	51	1:WATER LOA	17.424	17.424	17.111	17.111
Max (b)	51	1:WATER LOA	17.424	17.424	17.111	17.111
Max VM (t)	51	1:WATER LOA	17.424	17.424	17.111	17.111
Max VM (b)	51	1:WATER LOA	17.424	17.424	17.111	17.111

Reaction Summary

Node	L/C	Horizontal		Vertical		Horizontal		Moment	
		FX (kip)	FY (kip)	FZ (kip)	MX (kip'in)	MY (kip'in)	MZ (kip'in)		
Max FX	1	1:WATER LOA	0.000	0.000	-0.965	0.000	0.000	0.000	0.000
Min FX	1	1:WATER LOA	0.000	0.000	-0.965	0.000	0.000	0.000	0.000
Max FY	1	1:WATER LOA	0.000	0.000	-0.965	0.000	0.000	0.000	0.000
Min FY	1	1:WATER LOA	0.000	0.000	-0.965	0.000	0.000	0.000	0.000
Max FZ	11	1:WATER LOA	0.000	0.000	0.930	0.000	0.000	0.000	0.000



Software licensed to US Army COE - Pittsburgh

Job Title Panama Canal Miter Gate Study


Job No	Sheet No	Rev
	4	
Part 54'-8" skin plate extension		
Ref		
By	Date	Chd
SRS	10-Nov-99	
File	skin54.std	
Date/Time	10-Nov-1999 13:49	

Client PCC

Reaction Summary Cont...

	Node	L/C	Horizontal			Vertical			Horizontal			Moment		
			FX (kip)	FY (kip)	FZ (kip)	FX (kip)	FY (kip)	FZ (kip)	MX (kip.in)	MY (kip.in)	MZ (kip.in)			
Min FZ	1	1:WATER LOA	0.000	0.000	-0.965	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Max MX	1	1:WATER LOA	0.000	0.000	-0.965	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Min MX	1	1:WATER LOA	0.000	0.000	-0.965	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Max MY	1	1:WATER LOA	0.000	0.000	-0.965	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Min MY	1	1:WATER LOA	0.000	0.000	-0.965	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Max MZ	1	1:WATER LOA	0.000	0.000	-0.965	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Min MZ	1	1:WATER LOA	0.000	0.000	-0.965	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000

	Software licensed to US Army COE - Pittsburgh		Job No	Sheet No	Rev
	Job Title Panama Canal Miter Gate Study			5	
Client	PCC	By	SRS	Date	10-Nov-99
		File	skin54.std	Date/Time	10-Nov-1999 13:49



Whole Structure

STAAD SPACE 54'-8" MITER GATE EXTENSION

START JOB INFORMATION

JOB NAME Panama Canal Miter Gate Study

JOB CLIENT PCC

JOB PART 54'-8" skin plate extension

JOB COMMENT Extension of skin plate due to the LOWER SILL OPTION - 1 ft

ENGINEER NAME SRS

ENGINEER DATE 10-Nov-99

END JOB INFORMATION

INPUT WIDTH 79

UNIT FEET KIP

JOINT COORDINATES

1 0 0 0; 2 0 0.158 0; 3 0 0.316 0; 4 0 0.474 0; 5 0 0.632 0; 6 0 0.79 0;
7 0 0.948 0; 8 0 1.106 0; 9 0 1.264 0; 10 0 1.422 0; 11 0 1.58 0; 12 0.221 0 0;
13 0.221 0.158 0; 14 0.221 0.316 0; 15 0.221 0.474 0; 16 0.221 0.632 0;
17 0.221 0.79 0; 18 0.221 0.948 0; 19 0.221 1.106 0; 20 0.221 1.264 0;
21 0.221 1.422 0; 22 0.221 1.58 0; 23 0.442 0 0; 24 0.442 0.158 0;
25 0.442 0.316 0; 26 0.442 0.474 0; 27 0.442 0.632 0; 28 0.442 0.79 0;
29 0.442 0.948 0; 30 0.442 1.106 0; 31 0.442 1.264 0; 32 0.442 1.422 0;
33 0.442 1.58 0; 34 0.663 0 0; 35 0.663 0.158 0; 36 0.663 0.316 0;
37 0.663 0.474 0; 38 0.663 0.632 0; 39 0.663 0.79 0; 40 0.663 0.948 0;
41 0.663 1.106 0; 42 0.663 1.264 0; 43 0.663 1.422 0; 44 0.663 1.58 0;
45 0.884 0 0; 46 0.884 0.158 0; 47 0.884 0.316 0; 48 0.884 0.474 0;
49 0.884 0.632 0; 50 0.884 0.79 0; 51 0.884 0.948 0; 52 0.884 1.106 0;
53 0.884 1.264 0; 54 0.884 1.422 0; 55 0.884 1.58 0; 56 1.105 0 0;
57 1.105 0.158 0; 58 1.105 0.316 0; 59 1.105 0.474 0; 60 1.105 0.632 0;
61 1.105 0.79 0; 62 1.105 0.948 0; 63 1.105 1.106 0; 64 1.105 1.264 0;
65 1.105 1.422 0; 66 1.105 1.58 0; 67 1.326 0 0; 68 1.326 0.158 0;
69 1.326 0.316 0; 70 1.326 0.474 0; 71 1.326 0.632 0; 72 1.326 0.79 0;
73 1.326 0.948 0; 74 1.326 1.106 0; 75 1.326 1.264 0; 76 1.326 1.422 0;
77 1.326 1.58 0; 78 1.547 0 0; 79 1.547 0.158 0; 80 1.547 0.316 0;
81 1.547 0.474 0; 82 1.547 0.632 0; 83 1.547 0.79 0; 84 1.547 0.948 0;
85 1.547 1.106 0; 86 1.547 1.264 0; 87 1.547 1.422 0; 88 1.547 1.58 0;
89 1.768 0 0; 90 1.768 0.158 0; 91 1.768 0.316 0; 92 1.768 0.474 0;
93 1.768 0.632 0; 94 1.768 0.79 0; 95 1.768 0.948 0; 96 1.768 1.106 0;
97 1.768 1.264 0; 98 1.768 1.422 0; 99 1.768 1.58 0; 100 1.989 0 0;
101 1.989 0.158 0; 102 1.989 0.316 0; 103 1.989 0.474 0; 104 1.989 0.632 0;
105 1.989 0.79 0; 106 1.989 0.948 0; 107 1.989 1.106 0; 108 1.989 1.264 0;
109 1.989 1.422 0; 110 1.989 1.58 0; 111 2.21 0 0; 112 2.21 0.158 0;
113 2.21 0.316 0; 114 2.21 0.474 0; 115 2.21 0.632 0; 116 2.21 0.79 0;
117 2.21 0.948 0; 118 2.21 1.106 0; 119 2.21 1.264 0; 120 2.21 1.422 0;
121 2.21 1.58 0;

ELEMENT INCIDENCES SHELL

1 1 12 13 2; 2 2 13 14 3; 3 3 14 15 4; 4 4 15 16 5; 5 5 16 17 6; 6 6 17 18 7;
7 7 18 19 8; 8 8 19 20 9; 9 9 20 21 10; 10 10 21 22 11; 11 12 23 24 13;
12 13 24 25 14; 13 14 25 26 15; 14 15 26 27 16; 15 16 27 28 17; 16 17 28 29 18;
17 18 29 30 19; 18 19 30 31 20; 19 20 31 32 21; 20 21 32 33 22; 21 23 34 35 24;
22 24 35 36 25; 23 25 36 37 26; 24 26 37 38 27; 25 27 38 39 28; 26 28 39 40 29;
27 29 40 41 30; 28 30 41 42 31; 29 31 42 43 32; 30 32 43 44 33; 31 34 45 46 35;
32 35 46 47 36; 33 36 47 48 37; 34 37 48 49 38; 35 38 49 50 39; 36 39 50 51 40;
37 40 51 52 41; 38 41 52 53 42; 39 42 53 54 43; 40 43 54 55 44; 41 45 56 57 46;
42 46 57 58 47; 43 47 58 59 48; 44 48 59 60 49; 45 49 60 61 50; 46 50 61 62 51;
47 51 62 63 52; 48 52 63 64 53; 49 53 64 65 54; 50 54 65 66 55; 51 56 67 68 57;
52 57 68 69 58; 53 58 69 70 59; 54 59 70 71 60; 55 60 71 72 61; 56 61 72 73 62;
57 62 73 74 63; 58 63 74 75 64; 59 64 75 76 65; 60 65 76 77 66; 61 67 78 79 68;
62 68 79 80 69; 63 69 80 81 70; 64 70 81 82 71; 65 71 82 83 72; 66 72 83 84 73;
67 73 84 85 74; 68 74 85 86 75; 69 75 86 87 76; 70 76 87 88 77; 71 78 89 90 79;



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 12 of Pages

Computed by SRS Date 11/9/99

Checked by AH Date 12/1/01

Subject PANAMA CANAL MITER GATE STUDY



Computation LOWER SILL OPTION - 54'-8" MITER GATES

DESIGN STIFFENER

DESIGN STIFFENER FOR BOTTOM OF MITER GATE AS A SEATED BRACKET.

REFERENCE, DESIGN OF WELDED STRUCTURES BY OMER W. BLODGETT, PAGE 5.32

ASSUME $\frac{1}{16}$ " PLATE



AREA = 1.2066 FT²


DETAIL 1




A.) USE MAXIMUM FORCE AT (A)

$$\text{LOAD} = (51.783' + .5833') * 62.5 \text{ pcf} = 3272.89 \text{ lb/ft PER LINEAR FT}$$


$$\text{LOAD} = 3272.89 \text{ lb/ft} * 26.5' / 12 \text{ ft} = 7227 \text{ lbs} = 7.23 \text{ kip}$$





AREA = 1.2066 FT²

DETAIL 1



$$\cos \theta = \frac{F_y}{F} \quad \therefore \quad F_y = 7.23^k \cos 45^\circ$$

$$F_y = 5.11^k = F_x$$



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 14 of Pages

Computed by SRS Date 12/99

Checked by AH Date 12/91

Subject Panama Canal Gate Study

Computation

B.)

AXIAL COMPRESSION

$$f_c = \frac{F}{A} = \frac{5.11 \text{ K}}{.716''(7.849'')} = 9.476 \text{ ksi}$$

AISC, ASD PAGE 5-42 CHAPTER E

$$F_e = \left[1 - \frac{(Kl/r)^2}{2C_c^2} \right] F_y$$

$$\frac{5}{3} - \frac{3(Kl/r)}{8C_c} - \frac{(Kl/r)^3}{8C_c^3}$$

$$K=1$$

$$l = 19.16''$$

$$r = .577350 (.716'') = .397''$$

$$Kl/r = 48.27$$

$$C_c = \sqrt{\frac{2\pi^2 E}{F_y}} = \sqrt{\frac{2\pi^2 (29,000 \text{ ksi})}{36 \text{ ksi}}}$$

$$C_c = 126.1$$

$Kl/r < C_c$ USE EQUATION E2-1

$$F_e = \left[1 - \frac{48.27^2}{2(126.1)^2} \right] 36 \text{ ksi}$$

$$\frac{5}{3} - \frac{2(48.27)}{8(126.1)} - \frac{48.27^3}{8(126.1)^3}$$

$$= \frac{33.362 \text{ ksi}}{1.8032}$$

$$F_e = 18.50 \text{ ksi}$$

FROM EM 110-2-2105, PAGE 4-1, USE TYPE B STRUCTURE USE .83

$$F_a = .83 * 18.50 \text{ ksi}$$

$$= 15.36 \text{ ksi}$$

$$f_c < F_a \text{ GOOD}$$

$$9.476 \text{ ksi} < 15.36 \text{ ksi}$$



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 15 of Pages

Computed by SRS Date

Checked by *AS* Date 12/01


Subject

Computation

(c.)

MOMENT

ASSUME STIFFENER IS:



$$\begin{aligned} M &= PL \\ &= 5.11 \text{ K} (19.16 \text{ in}) \\ &= 97 \text{ K-IN} \end{aligned}$$

$$S = \frac{I}{c} = \frac{\frac{1}{12} (1\frac{1}{16} \text{ in}) (7.84 \text{ in})^3}{7.84 \text{ in} / 2} = \frac{27.651}{3.922} = 7.05 \text{ in}^3$$

$$f_b = \frac{M}{S} = \frac{97 \text{ K-IN}}{7.05 \text{ in}^3} = 13.76 \text{ ksi}$$

AISC, ASD PAGE 5-45 CHAPTER F

$$\begin{aligned} F_b &= .66 F_y \\ &= .66 (36 \text{ ksi}) \\ &= 23.76 \text{ ksi} \end{aligned}$$

FROM EM 1110-2-2105, PAGE 4-1, USE TYPE B STRUCTURE USE .83

$$\begin{aligned} F_b &= .83 \times 23.76 \text{ ksi} \\ &= 19.72 \text{ ksi} \end{aligned}$$

$$\begin{aligned} f_b &< F_b \quad \text{GOOD} \\ 13.76 \text{ ksi} &< 19.72 \end{aligned}$$

FOR COMBINED STRESSES USE AISC, ASD CHAPTER H.

SINCE $f_a / F_a < .15$ CAN USE EQUATION H1-3

$$\frac{f_c}{F_a} + \frac{f_b}{F_b} \leq 1.0$$

$$\frac{.9476}{15.36} + \frac{13.76}{19.72} \leq 1.0$$

$$.76 \leq 1.0 \quad \text{GOOD FOR COMBINED STRESSES}$$

1 1/16" PLATE IS SUFFICIENT.



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 16 of Pages

Subject PANAMA CANAL MITER GATE STUDY

Computed by SRS Date 12/99

Computation LOWER SILL OPTION - ANALYSIS AND DESIGN FOR 79' GATES

Checked by AH Date 12/01


1) THE ANALYSIS ON PAGES 10 ARE FOR THE 79' AND 77' GATES.

2) DESIGN HEAD

a) PEDRO M.G. 62-69
MIRAFLORES M.G. 104-107

b) EXISTING SILL EL. @ PEDRO = +13.00
WATER EL. = 87.5'

c) NEW SILL EL @ PEDRO = +12.00
WATER EL. = 87.5'




$$\text{PRESSURE} = 76.083' \times 62.5 \text{ pcf} = 4755 \text{ lb/ft}^2 = 33 \text{ psi}$$


$$= 4.8 \text{ ksf}$$

3) SKIN PLATE AND STIFFENERS

SPACING OF EXISTING STIFFENERS FOR THE BOTTOM GIRDER IS 2'-2 1/2". DRAWING S155 IS FOR 79' GATES IT REFERENCES S156 FOR TYPICAL GIRDER. I USED 2'-2 1/2" FROM DWG 5023 FOR 77' GATES.



a) SKIN PLATE





US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 17 of Pages

Computed by SRS Date 12/99

Checked by AH Date 12/01

Subject

Computation

FROM ROARK'S FORMULAS FOR STRESS AND STRAIN, SIXTH EDITION, PAGE 461 AND 469
USE CASE 2/A AND CASE 10/A TO ANALYZE SKIN PLATE

SEE SPREADSHEET FOR ROARK'S ANALYSIS AND SEE STAADPRO ANALYSIS
FOR VERIFICATION.



US Army Corps
of Engineers
Ohio River Division
Pittsburgh District

COMPUTATION SHEET

Computed by: SRS
Date: 11/9/99
Checked by: H.H.
Date: 1/6/00
Page: 18

SUBJECT: Panama Canal Mixer Gate Study
COMPUTATION: Skin Plate Design for 79' Mixer Gate


Lake Elevation 87.5 ft Seal Elevation 12.000 ft Plate Elevation 11.417 Design Head 76.083 ft
Gatun Highest =

Water Density = 62.5 pcf

WATER PRESSURE $q = 33.02$ Psi conservative uniform

SKIN PLATE DESIGN

$t = 0.8125$ inch plate
Steel $F_y = 36000$ psi
Steel $E = 29000000$ psi
PANEL $a = 18.968$ inch $a/b = 0.7158$
PANEL $b = 26.5$ inch
Difference = 0.0488



Three edges simple supported and one end free Case 2a

A/B	0.5	0.667	1	1.5	2	4	
β	0.36	0.45	0.67	0.7700	0.79	0.8	0.4822 interpolate
α	0.08	0.106	0.14	0.1600	0.165	0.167	0.1110 interpolate

Max. Bending Stress = $\sigma = \frac{\beta * q * b^2}{t^2} = 16939 < 22410$ psi Type B Loading EM 1110-2-2105 allowable stress = .83 * .75 * F_y
Good

Max. Deflection = $y = \frac{a * q * b^4}{E * t^3} = 0.1162$ inch

PANEL $a = 26.5$ inch $a/b = 1.3971$
PANEL $b = 18.968$ inch
Difference = 0.40

Three edges fixed and one edge free Case 10a:


A/B	0.25	0.5	0.75	1	1.5	2	3	0.5
β_1	0.02	0.081	0.173	0.321	0.727	1.226	2.105	0.6434 interpolate
β_2	0.016	0.066	0.148	0.259	0.484	0.605	0.519	0.4377 interpolate
β_3	0.031	0.126	0.286	0.511	1.073	1.568	1.982	0.9573 interpolate
γ_1	0.114	0.23	0.341	0.457	0.673	0.845	1.012	0.6285 interpolate
γ_2	0.125	0.248	0.371	0.51	0.859	1.212	1.0627	0.7872 interpolate

At $x = A/2, z = B$:

Max. Bending Stress = $\sigma = \frac{\beta_3 * q * b^2}{t^2} = 17229 < 22410$ psi Type B Loading EM 1110-2-2105 allowable stress = .83 * .75 * F_y
Good

R is the reaction force per unit length normal to the plate surface exerted by the boundary support on the edge of the plate

R at location $Z = 0$ and $X = 0$
 $R = \gamma_1 * q * b = 393.70$ lb/inch



13/16 inch Plate is Good



Software licensed to US Army COE - Pittsburgh

Job Title Panama Canal Miter Gate Study

Job No	Sheet No	Rev
	1	
Part 79' Miter Gate Skin Plate Extension		
Ref		
By	Date	Chd
SRS	10-Nov-99	
File	Date/Time	
skin79.std	09-Dec-1999 12:36	

Client PCC

Job Information

Engineer	Checked	Approved
Name: SRS		
Date: 10-Nov-99		

Comments

Extension of skin plate due to the LOWER SILL OPTION - 1 ft

Structure Type SPACE FRAME

Number of Nodes	121	Highest Node	121
Number of Plates	100	Highest Plate	100

Number of Basic Load Cases	1
Number of Combination Load Cases	0

Included in this printout are data for:

All	The Whole Structure
-----	---------------------

Included in this printout are results for load cases:

Type	L/C	Name
Primary	1	WATER LOAD



Software licensed to US Army COE - Pittsburgh

Job Title Panama Canal Miter Gate Study

Rev

Job No

Sheet No

2

Part 79 Miter Gate Skin Plate Extension

Ref

By SRS

Date 10-Nov-99

Chd

Date/Time 09-Dec-1999 12:36

File skin79.std

Client PCC

Node Displacement Summary

Node	L/C	X (in)	Y (in)	Z (in)	Resultant (in)	rX (rad)	rY (rad)	rZ (rad)
Max X	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00002	-0.01003	0.00000
Min X	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00002	-0.01003	0.00000
Max Y	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00002	-0.01003	0.00000
Min Y	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00002	-0.01003	0.00000
Max Z	1:WATER LOA	0.000	0.000	0.084	0.084	-0.00449	-0.00000	0.00000
Min Z	1:WATER LOA	0.000	0.000	-0.000	0.000	-0.00011	-0.00028	0.00000
Max rX	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00002	-0.01003	0.00000
Min rX	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00569	0.00000	0.00000
Max rY	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00002	0.01003	0.00000
Min rY	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00002	-0.01003	0.00000
Max rZ	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00002	-0.01003	0.00000
Min rZ	1:WATER LOA	0.000	0.000	0.000	0.000	-0.00002	-0.01003	0.00000
Max Rst	1:WATER LOA	0.000	0.000	0.084	0.084	-0.00449	-0.00000	0.00000

Plate Centre Stress Summary

Plate	L/C	Shear			Membrane			Bending		
		Qx (ksi)	Qy (ksi)	Fx (ksi)	Fy (ksi)	Fxy (ksi)	Mix (kip-in/in)	My (kip-in/in)	Mxy (kip-in/in)	
Max Qx	1:WATER LOA	-0.586	0.177	0.000	0.000	0.000	0.369	0.093	-0.391	
Max Qy	1:WATER LOA	-0.182	0.368	0.000	0.000	0.000	0.085	0.100	-0.610	
Max Fx	1:WATER LOA	0.586	0.177	0.000	0.000	0.000	0.369	0.093	0.391	
Max Fy	1:WATER LOA	0.586	0.177	0.000	0.000	0.000	0.369	0.093	0.391	
Max Fxy	1:WATER LOA	0.586	0.177	0.000	0.000	0.000	0.369	0.093	0.391	



Software licensed to US Army COE - Pittsburgh

Job Title Panama Canal Miter Gate Study

Job No	Sheet No	Rev
	3	
Part79 Miter Gate Skin Plate Extension		
Ref		
By	Date	Chd
SRS	10-Nov-99	
File	Date/Time	
skin79.std	09-Dec-1999 12:36	

Client PCC

Plate Centre Stress Summary Cont...

Plate	L/C	Shear			Membrane			Bending			
		Qx (ksi)	Qy (ksi)	Qz (ksi)	Fx (ksi)	Fy (ksi)	Fz (ksi)	Mx (kip·in/in)	My (kip·in/in)	Mxy (kip·in/in)	
Max Mx	41	1:WATER LOA	0.078	0.049	0.000	0.000	0.000	0.000	1.371	0.053	0.058
Max My	46	1:WATER LOA	0.017	-0.071	0.000	0.000	0.000	0.000	0.885	0.502	0.076
Max Mxy	99	1:WATER LOA	-0.182	0.368	0.000	0.000	0.000	0.000	0.085	0.100	-0.610

Plate Centre Principal Stress Summary

Plate	L/C	Principal		Von Mis		
		Top (ksi)	Bottom (ksi)	Top (ksi)	Bottom (ksi)	
Max (t)	41	1:WATER LOA	12.486	12.486	12.264	12.264
Max (b)	41	1:WATER LOA	12.486	12.486	12.264	12.264
Max VM (t)	41	1:WATER LOA	12.486	12.486	12.264	12.264
Max VM (b)	41	1:WATER LOA	12.486	12.486	12.264	12.264

Reaction Summary

Node	L/C	Horizontal		Vertical		Horizontal		Moment	
		FX (kip)	FY (kip)	FZ (kip)	FY (kip)	MX (kip·in)	MY (kip·in)	MZ (kip·in)	
Max FX	1	1:WATER LOA	0.000	0.000	-0.959	0.000	0.000	0.000	0.000
Min FX	1	1:WATER LOA	0.000	0.000	-0.959	0.000	0.000	0.000	0.000
Max FY	1	1:WATER LOA	0.000	0.000	-0.959	0.000	0.000	0.000	0.000
Min FY	1	1:WATER LOA	0.000	0.000	-0.959	0.000	0.000	0.000	0.000
Max FZ	11	1:WATER LOA	0.000	0.000	0.916	0.000	0.000	0.000	0.000



Software licensed to US Army COE - Pittsburgh

Job Title Panama Canal Miter Gate Study

Job No	Sheet No	Rev
	4	
Part 79 Miter Gate Skin Plate Extension		
Ref		
By	Date	Chd
SRS	10-Nov-99	
File	Date/Time	
skin79.std	09-Dec-1999 12:36	

Client PCC

Reaction Summary Cont...


	Node	L/C	Horizontal			Vertical			Horizontal			Moment		
			FX (kip)	FY (kip)	FZ (kip)	FX (kip)	FY (kip)	FZ (kip)	MX (kip'in)	MY (kip'in)	MZ (kip'in)			
Min FZ	111	1:WATER LOA	0.000	0.000	-0.959	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Max MX	1	1:WATER LOA	0.000	0.000	-0.959	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Min MX	1	1:WATER LOA	0.000	0.000	-0.959	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Max MY	1	1:WATER LOA	0.000	0.000	-0.959	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Min MY	1	1:WATER LOA	0.000	0.000	-0.959	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Max MZ	1	1:WATER LOA	0.000	0.000	-0.959	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Min MZ	1	1:WATER LOA	0.000	0.000	-0.959	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000

Job No		Sheet No	Rev
		5	
Part 79: Miter Gate Skin Plate Extension			
Ref			
By	Date	Chd	
SRS	10-Nov-99		
File		Date/Time	
skin79.std		09-Dec-1999 12:36	

Software licensed to US Army COE - Pittsburgh

Job Title Panama Canal Miter Gate Study

Client PCC



Max Von Mis

- 1.85
- 2.51
- 3.16
- 3.81
- 4.46
- 5.11
- 5.76
- 6.41
- 7.06
- 7.71
- 8.36
- 9.01
- 9.66
- 10.3
- 11
- 11.6
- 12.3



Whole Structure

STAAD SPACE 79' MITER GATE EXTENSION

START JOB INFORMATION

JOB NAME Panama Canal Miter Gate Study

JOB CLIENT PCC

JOB PART 79' Miter Gate Skin Plate Extension

JOB COMMENT Extension of skin plate due to the LOWER SILL OPTION - 1 ft

ENGINEER NAME SRS

ENGINEER DATE 10-Nov-99

END JOB INFORMATION

INPUT WIDTH 79

UNIT FEET KIP

JOINT COORDINATES

1 0 0 0; 2 0 0.158 0; 3 0 0.316 0; 4 0 0.474 0; 5 0 0.632 0; 6 0 0.79 0;
7 0 0.948 0; 8 0 1.106 0; 9 0 1.264 0; 10 0 1.422 0; 11 0 1.58 0; 12 0.221 0 0;
13 0.221 0.158 0; 14 0.221 0.316 0; 15 0.221 0.474 0; 16 0.221 0.632 0;
17 0.221 0.79 0; 18 0.221 0.948 0; 19 0.221 1.106 0; 20 0.221 1.264 0;
21 0.221 1.422 0; 22 0.221 1.58 0; 23 0.442 0 0; 24 0.442 0.158 0;
25 0.442 0.316 0; 26 0.442 0.474 0; 27 0.442 0.632 0; 28 0.442 0.79 0;
29 0.442 0.948 0; 30 0.442 1.106 0; 31 0.442 1.264 0; 32 0.442 1.422 0;
33 0.442 1.58 0; 34 0.663 0 0; 35 0.663 0.158 0; 36 0.663 0.316 0;
37 0.663 0.474 0; 38 0.663 0.632 0; 39 0.663 0.79 0; 40 0.663 0.948 0;
41 0.663 1.106 0; 42 0.663 1.264 0; 43 0.663 1.422 0; 44 0.663 1.58 0;
45 0.884 0 0; 46 0.884 0.158 0; 47 0.884 0.316 0; 48 0.884 0.474 0;
49 0.884 0.632 0; 50 0.884 0.79 0; 51 0.884 0.948 0; 52 0.884 1.106 0;
53 0.884 1.264 0; 54 0.884 1.422 0; 55 0.884 1.58 0; 56 1.105 0 0;
57 1.105 0.158 0; 58 1.105 0.316 0; 59 1.105 0.474 0; 60 1.105 0.632 0;
61 1.105 0.79 0; 62 1.105 0.948 0; 63 1.105 1.106 0; 64 1.105 1.264 0;
65 1.105 1.422 0; 66 1.105 1.58 0; 67 1.326 0 0; 68 1.326 0.158 0;
69 1.326 0.316 0; 70 1.326 0.474 0; 71 1.326 0.632 0; 72 1.326 0.79 0;
73 1.326 0.948 0; 74 1.326 1.106 0; 75 1.326 1.264 0; 76 1.326 1.422 0;
77 1.326 1.58 0; 78 1.547 0 0; 79 1.547 0.158 0; 80 1.547 0.316 0;
81 1.547 0.474 0; 82 1.547 0.632 0; 83 1.547 0.79 0; 84 1.547 0.948 0;
85 1.547 1.106 0; 86 1.547 1.264 0; 87 1.547 1.422 0; 88 1.547 1.58 0;
89 1.768 0 0; 90 1.768 0.158 0; 91 1.768 0.316 0; 92 1.768 0.474 0;
93 1.768 0.632 0; 94 1.768 0.79 0; 95 1.768 0.948 0; 96 1.768 1.106 0;
97 1.768 1.264 0; 98 1.768 1.422 0; 99 1.768 1.58 0; 100 1.989 0 0;
101 1.989 0.158 0; 102 1.989 0.316 0; 103 1.989 0.474 0; 104 1.989 0.632 0;
105 1.989 0.79 0; 106 1.989 0.948 0; 107 1.989 1.106 0; 108 1.989 1.264 0;
109 1.989 1.422 0; 110 1.989 1.58 0; 111 2.21 0 0; 112 2.21 0.158 0;
113 2.21 0.316 0; 114 2.21 0.474 0; 115 2.21 0.632 0; 116 2.21 0.79 0;
117 2.21 0.948 0; 118 2.21 1.106 0; 119 2.21 1.264 0; 120 2.21 1.422 0;
121 2.21 1.58 0;

ELEMENT INCIDENCES SHELL

1 1 12 13 2; 2 2 13 14 3; 3 3 14 15 4; 4 4 15 16 5; 5 5 16 17 6; 6 6 17 18 7;
7 7 18 19 8; 8 8 19 20 9; 9 9 20 21 10; 10 10 21 22 11; 11 12 23 24 13;
12 13 24 25 14; 13 14 25 26 15; 14 15 26 27 16; 15 16 27 28 17; 16 17 28 29 18;
17 18 29 30 19; 18 19 30 31 20; 19 20 31 32 21; 20 21 32 33 22; 21 23 34 35 24;
22 24 35 36 25; 23 25 36 37 26; 24 26 37 38 27; 25 27 38 39 28; 26 28 39 40 29;
27 29 40 41 30; 28 30 41 42 31; 29 31 42 43 32; 30 32 43 44 33; 31 34 45 46 35;
32 35 46 47 36; 33 36 47 48 37; 34 37 48 49 38; 35 38 49 50 39; 36 39 50 51 40;
37 40 51 52 41; 38 41 52 53 42; 39 42 53 54 43; 40 43 54 55 44; 41 45 56 57 46;
42 46 57 58 47; 43 47 58 59 48; 44 48 59 60 49; 45 49 60 61 50; 46 50 61 62 51;
47 51 62 63 52; 48 52 63 64 53; 49 53 64 65 54; 50 54 65 66 55; 51 56 67 68 57;
52 57 68 69 58; 53 58 69 70 59; 54 59 70 71 60; 55 60 71 72 61; 56 61 72 73 62;
57 62 73 74 63; 58 63 74 75 64; 59 64 75 76 65; 60 65 76 77 66; 61 67 78 79 68;
62 68 79 80 69; 63 69 80 81 70; 64 70 81 82 71; 65 71 82 83 72; 66 72 83 84 73;
67 73 84 85 74; 68 74 85 86 75; 69 75 86 87 76; 70 76 87 88 77; 71 78 89 90 79;



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 25 of 25 Pages

Subject

PANAMA CANAL MITER GATE STUDY

Computed by

SRS

Date

Checked by

AH

Date 12/01

Computation

LOWER SILL OPTION - ANALYSIS AND DESIGN FOR 79' GATES.

b) STIFFENERS

FOR SAVINGS IN TIME I ASSUMED THE SAME
GEOMETRY FOR THE 54'-8" STIFFENER
BUT MADE IT 13/16" THICK PLATE.

Appendix 3. – Miter Gate Sill: Precast Panel & CIP Panel and Recess – Calculations



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 1 of Pages 26

Subject PANAMA CANAL

Computed by ZAA Date 11/26/01

Checked by WAT Date 12/11/01

Computation MITER GATE SILL MODIFICATION

1) PRELIMINARY PRECAST PANEL DESIGN

A) SINCE THE MITER GATES NOS. 13-20 AT GATUN LOCKS AND NOS. 54-69 AT PARRA MIGUEL ARE HORIZONTALLY FRAMED, THE LATERAL LOAD ON THE SILL IS DUE TO HYDROSTATIC PRESSURE. THE RUBBER SEAL OF THE MITER GATE DOES NOT TRANSFER LOAD TO THE SEAL.

B) TO DESIGN THE ANCHOR BOLTS, THE FOLLOWING DESIGN ASSUMPTIONS ARE MADE:

1) THE UPPER CHAMBER IS AT HIGHEST POOL ELEVATION AND THE LOWER CHAMBER OR OUTSIDE THE CHAMBER IS AT LOWEST POOL ELEVATION OR DEWATERED.

2) THE PRECAST PANEL IS SUBJECT TO FULL UPLIFT

Low Pool OR DEWATERED	}	HIGHEST CHAMBER POOL
-----------------------------	---	----------------------------

3) THE LOWEST GIRDER TRANSFERS ALL OF ITS LOAD INTO THE SILL SEGMENT. THE MAGNITUDE OF THE LOAD IS EQUAL ON THE TRIBUTARY AREA OF THE HORIZONTAL GIRDER AND THE M.G. EXTENSION FOR THE SEAL.

C) CALCULATE SIZE AND SPACING OF 1-IN DIA THREABAR

1) 1-IN DIA THREABAR - $A = 0.85 \text{ in}^2$ NYWIRAG¹
 $f_{ULT} = 150 \text{ ksi}$
 $f_y = 0.8 f_{ULT}$ ASTM A722-98 SEC. 2.2

2) ASSUME LATERAL LOAD APPLIED TO SILL IS EQUAL TO HYDROSTATIC PRESSURE APPLIED TO TRIBUTARY AREA OF LOWEST HORIZONTAL GIRDER. THE HORIZONTAL GIRDERS ARE SPACED ON 3'-8" CENTERS FOR GATUN MG NOS. 13-20 (HEIGHT - 77'-10") AND PARRA MIGUEL MG NOS. 54-69 (HEIGHT - 79').^{2,3} THE SEAL EXTENSION IS 1'-0".

3) THE THREABAR SIZE AND SPACING WILL BE BASED ON HIGHEST CHAMBER POOL ELEVATION AND ADJACENT CHAMBER AT LOWEST POOL ELEVATION OR DEWATERED.

¹ NYWIRAG THREABAR, ROCK AND SOIL ANCHORS, BROCHURE 4M 4-90, P. 3.

² ACP, MASTER MG AND VALVE OVERHAUL SCHEDULE, 25 JAN 1994

³ ACP, DWGS 5154 & 5155, 25 MAR 1994



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 2 of Pages 26

Subject SAWAMA CANAL

Computed by ZAA Date 11/26/01

Computation WETER GATE SILL MODIFICATION


Checked by WAH Date 12/11/01

4) USING HIGHEST CHANGED POOL ELEVATION FOR ADVANCED CHANGED SEWATERED:

Location	UPPER POOL EL (ft)	NEW M.G. SILL EL (ft)	M.G. EXTENSION PAST NEW SILL (ft)	MAX. HEAD (ft)
GATUN	+59	-14.58	0.58	74.16
PEARO MIGUEL	+81.5	+12.0	0.58	70.08

∴ GATUN CONTROLS

5) CALCULATE HYDROSTATIC FORCES & PRESSURES FOR LOWER HORIZONTAL GIRDER



PROPOSED SILL EL

NOTE: PRECAST PANEL NOT SHOWN - PURPOSE OF ILLUSTRATION ONLY TO SHOW DESIGN ELEVATIONS

NOTE: 1/2 M.G. HORIZONTAL GIRDER SPACING = 1'-10" (3'8" / 2)

• HYDROSTATIC PRESSURE:

$$\text{@ EL } -12.32 : 4.46 \text{ k/ft}^2 = (59' + 12.32') (0.0625 \text{ k/ft}^2)$$

$$4.64 \text{ k/ft}^2 = (59' + 14.16') (0.0625 \text{ k/ft}^2)$$

• FORCE : $H_w = \frac{(4.46 \text{ k/ft}^2 + 4.64 \text{ k/ft}^2)}{2} (2.83 \text{ ft})$

$$H_w = 12.89 \text{ k/ft}$$



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 3 of Pages 26

Computed by RAA Date 11/26/01

Checked by WAH Date 12/11/01

Subject PAJAMA CAWAL

Computation MITER GATE SILL MODIFICATION

• LOCATION

$$\bar{y} h_w = \sum \bar{y} h_w$$

$$\bar{y} = \frac{(4.46)(2.83)^2/2 + 1/2(4.64 - 4.46)(2.83)^2/3}{12.89}$$


$$\bar{y} = 1.40 \text{ ft}$$

1) PRECAST PANEL SIZE & DESIGN DATA (SEE PRECAST PANEL DWG)

1) ASSUMPTIONS / DESIGN DATA

- a) PANELS ARE 5'0" WIDE X 9" THICKNESS X 20'0" & 21'9" LENGTH
- b) $f'_c = 5 \text{ ksi}$
- c) 1" DIA THREADED ACTS AS SHEAR-FRICTION STEEL TO RESIST LATERAL THRUST OF LOWER HORIZONTAL GIRDER AND RESISTS FULL HYDROSTATIC UPLIFT ON PANEL

2) LOADINGS & U/S-R/S ANCHOR LAYOUT (PER UNIT LENGTH OF SLAB)



• PROBLEM IS INDETERMINANT TO 1 DEGREE ∴ USE STAAD/PRO 1/4 TO FIND REACTIONS:

- USED HYDROSTATIC PRESSURE = 4.66 k/ft², NOT 4.64 k/ft²
∴ STAAD/PRO RESULTS OFF BY 0.4% (INSIGNIFICANT)

- STAAD PRO RESULTS: $V_1 = 1.32 \text{ k/ft}$
 $V_2 = 2.53 \text{ k/ft}$
 $V_3 = 7.80 \text{ k/ft}$

4/ STAAD/PRO, RELEASE 2001, RESEARCH ENGINEERS CORP.



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 3 of Pages

Subject PANAMA CANAL MITER GATE STUDY

Computed by SRS Date 12/17/99

Computation LOWER SILL OPTION - DESIGN CRITERIA

Checked by AH Date 12/11/01

REFERENCES:

- 1) EM 1110-2-2105 DESIGN OF HYDRAULIC STEEL STRUCTURES
- 2) EM 1110-2-2703
- 3) AISC ASD MANUAL

DESIGN LOADS

- HYDROSTATIC
- DEBRIS (LOG OR SOME SORT OF OBSTRUCTION)

STEEL DESIGN CRITERIA

DESIGNED USING THE ALLOWABLE STRESS DESIGN METHOD
IN ACCORDANCE WITH THE AISC (ASD) AS MODIFIED
BY EM 1110-2-2105.

MATERIAL PROPERTIES:

PLATES & SHAPES: ASTM A36 WITH $F_y = 36,000 \text{ psi}$
BOLTS: ASTM A325 TYPE 3



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 4 of Pages

Subject PANAMA CANAL MITER GATE STUDY

Computed by SRS Date

Checked by AH Date 2/1/01

Computation LOWER SILL OPTION - ANALYSIS DESIGN FOR 54'-8" MITER GATES.

1) THE ANALYSIS ON PAGES _ TO _ ARE FOR THE 54'-8" AND 47'-4" MITER GATES.

USED DESIGN HEAD OF 54'-8" GATES FOR 47'-4" GATES.



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 5 of Pages

Subject PANAMA CANAL MITER GATE STUDY

Computed by SRS Date 11/8/99

Checked by A4 Date 12/11/01

Computation LOWER SILL OPTION - 54'-8" MITER GATES.

GATUN & PEDRO MIGUEL & MIRAFLORES LOCKS

- MITER GATES 37-40 FOR GATUN LOCKS

- MITER GATES 50-53 FOR PEDRO MIGUEL


GIVEN: " " 70-73 " " AND 100-103 FOR MIRAFLORES

HIGHEST LAKE ELEVATION = 87.5 ft

DESIGN HEAD


SILL ELEVATION AT GATUN & PEDRO = 27.3 ft (EXISTING)

" " = 36.3 ft (FUTURE)



FROM DWG 5025, SECTION A-A, THE GIRDERS ARE SPACED @ 2'-2 1/2"

∴ TRY PLACING STIFFENERS AT SAME LOCATION. SEE PAGE 4 FOR DWG



FROM ROARK'S FORMULAS FOR STRESS AND STRAIN, SIXTH EDITION, PAGE 461 AND 469.

USE CASE 2A AND CASE 10A TO ANALYZE SKIN PLATE

SEE SPREADSHEET FOR CALCULATIONS OF SKIN PLATE. (NEXT PAGE)

PAGES 7 TO 11 ARE "STAAD PRO" ANALYSIS OF THE SKIN PLATE TO VERIFY SPREADSHEET.



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 1 of Pages

Subject PANAMA CANAL MITER GATE STUDY

Computed by SRS Date 12/7/99

Computation LOWER SILL OPTION - ASSUMPTIONS

Checked by AA Date 12/11/01

DESIGN ASSUMPTIONS

- 1.) LOWERING OF 37-40, 50-53, 62-69, 70-73, 100-103, AND 104-107 MITER GATES.

AFTER COMPARING THE LIFT HEIGHTS FOR ALL MITER GATES.

A LIFT OF 51.17ft FOR 37-40 AND 50-53 AND A LIFT OF 44.17ft FOR M.G. 70-73 AND 100-103 ARE CLOSE IN RANGE FOR DESIGN. I WILL DESIGN THE EXTENSION OF THE FOLLOWING MITER GATES FOR A HEAD OF 51.17ft. THIS ANALYSIS CAN BE FOUND IN PAGE 5 TO 25.

THE DESIGN HEAD FOR M.G. 62-69 AND M.G. 104-107 ARE SIMILAR (75.5ft AND 73.83ft). THEREFORE DESIGN EXTENSION FOR A DESIGN HEAD OF 75.5ft. THIS ANALYSIS CAN BE FOUND ON PAGE 16 OF 25.

- 2) THE DESIGN ARE BROKEN UP INTO 2 ANALYSIS.

- 1) 54'-8" GATE FOR A HEAD OF 51.17ft.
- 2) 79'-0" GATE FOR A HEAD OF 75.5ft.

- 3) SEE DRAWING FOR SEQUENCE OF WORK.

- 4) FOR EXTENSION OF THE MITER GATE I MOVED THE SEAL LOCATION 1'-0" LOWER FROM THE EXISTING LOCATION. I WILL PUT AN EXTENSION OF THE SKIN PLATE AND PROVIDE STIFFENERS TO SUPPORT THE NEW SKIN PLATE EXTENSION LOCATED AT EVERY EXISTING STIFFENER ON THE LOWER GIRDER OF THE MITER GATES. SEE ATTACHED FOR DRAWING OF BOTTOM GIRDER OF MITER GATE.

THE BOTTOM GIRDER OF MITER GATE WILL HAVE TO BE CHECKED FOR ADDITIONAL BIAXIAL BENDING DUE TO THE EXTENSION. THIS ANALYSIS WAS NOT DONE IN THIS STUDY.

- 5) THE ONLY LOAD CONDITION USED IN THIS ANALYSIS WAS NORMAL OPERATING. FOR FUTURE DESIGN SUCH AS PLANS & SPECS A FURTHER ANALYSIS OF EXISTING AND EXTREME CONDITION WILL NEED TO BE PERFORMED. EXTREME WOULD CONSIDER DEBRIS LOAD SUCH AS LOG OR MISC. STUCK BETWEEN SILL AND GATE WHICH WOULD INDUCE CONCENTRATED LOAD ON EXTENSION.



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 4 of Pages 26

Computed by RAA Date 11/20/01

Checked by WJA Date 12/11/01

Subject PANAMA CANAL

Computation WATER GATE FILL MODIFICATION

- CHECK STAAD/PRO RESULTS

$$U_1 + U_2 + U_3 = 11.65 \text{ K/ft} \quad (\text{OPER PRESSURE} = 4.66 \text{ K/ft}^2)$$

$$U_{\text{WGT}} = \frac{1}{2} (4.66 \text{ K/ft}^2) (5 \text{ ft}) = 11.60 \text{ K/ft} \quad \text{OK}$$

NOTE - DIFFERENCE IS 0.050 ^{OK}

3) CHECK TYPICAL BAR SPACING (LONGITUDINAL AXIS)

a) CODE REQUIREMENTS FOR HYDRAULIC CONCRETE STRUCTURES:

$$U_w = 1.7 H_f (A + L) \quad \text{EM 2104 EQ (3-2)} \quad \text{15}$$

WHERE $H_f = 1.3$ FOR HYDRAULIC STRUCTURES

$H_f = 1.65$ FOR HYDRAULIC MEMBERS (DIRECT TENSION)

$A = \text{DEAD LOAD}$

$L = \text{LIVE LOAD}$

1.7 = SINGLE LOAD FACTOR - REPLACES ALL

ACI 318-99 LOAD FACTOR: 1.6

b) SHEAR:

$$\phi V_c = 1.3 (V_u - \phi V_c) \quad \text{EM 2104, P. 3-2}$$

WHERE $V_c = \text{STRAIN STRENGTH}$

$V_u = \text{ULTIMATE LOAD}$

$V_c = \text{CONCRETE STRENGTH}$

$\phi = \text{APPROXIMATE ACI STRENGTH REDUCTION}$

c) REBAR ACTS AS SHEAR-RESISTING STEEL FOR LATERAL THRUST

$$V_u = A_{vs} f_y \mu \quad \text{ACI (11-25)}$$

$A_{vs} = \text{AREA, IN}^2 \quad \text{ACI 11.7.9.3}$

$f_y = \text{YIELD STRESS, KSI}$

$\mu = 1.0 \lambda \quad (\text{CONCRETE INTERNATIONALLY ROUGHENED})$

$\lambda = 1.0 \quad (\text{NORMAL WEIGHT CONCRETE})$

5/ EM 1110-2-2104, STRENGTH DESIGN FOR REINFORCED-CONCRETE HYDRAULIC STRUCTURES, 30 JUNE 1992

6/ ACI 318-99, BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE, AMERICAN CONCRETE INSTITUTE, 1999



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 5 of Pages 26

Subject RAWAMA CANAL

Computed by DAA Date 10/23/01

Computation WATER GATE SILL MODIFICATION

Checked by WAT Date 12/1/01

d) THREAD BAR RESISTS HYDROSTATIC UPLIFT (LEAK ROW - HIGHEST):

$$\text{AXIAL TENSION: } \phi P_n \geq P_u \quad \text{ACI}$$

P_n = AXIAL STRENGTH
 P_u = FACTORED AXIAL LOAD

e) Combining ACI & CODES EQUATIONS

TENSION: $0.9 (f_y A_s) \geq 1.65 (1.7) (P_T)$

SHEAR FRICTION: $0.85 (f_y A_{sv}) \geq 1.3 (1.7) (V_u)$

- LOADS ON LEAD ANCHOR: TENSION: $P_T = U_2 = 7.80 \text{ K/FT}$
SHEAR: $P_u = 12.89 \text{ K/FT} / 3 = 4.30 \text{ K/FT}$
↳ 3 ROWS

- 1-IN THREAD BAR: $A_s = 0.85 \text{ in}^2$
 $F_{UT} = 150 \text{ KSI}$
 $f_y = 0.8 (150 \text{ KSI})$
 $f_y = 120 \text{ KSI}$

f) THREAD BAR SPACING

$$(0.9 + 0.85) (f_y A_s) \geq [1.65 (1.7) (P_T) + 1.3 (1.7) V_u] \cdot S$$

WHERE S = LONGITUDINAL SPACING SINCE LOADS ARE EXPRESSED IN TERMS OF LINEAR LENGTH

$$S = \frac{1.75 (120 \text{ KSI}) (0.85 \text{ in}^2)}{1.65 (1.7) (7.80 \text{ K/FT}) + 1.3 (1.7) (4.30 \text{ K/FT})}$$

ALLOWABLE DESIGN
LOAD
1" THREAD BAR = 76.5 K

S = 5.70 FT

USE S = 4'-9 1/4" OK
NOTE: 2ND ROW ONLY HAS 4 ANCHORS, SEE PRE-CAST DWG.

OK

NOTE: THE ACTUAL MAXIMUM LOAD IN LEAD ANCHORS IS
 $57.7 \text{ K} = \left(\frac{4.77 \text{ FT}}{S \text{ SPACING}} \times [7.8 \text{ K/FT} + 4.3 \text{ K/FT}] \right)$
↳ UPLIFT ↳ SHEAR



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 5A of Pages 26

Computed by DAA Date 11/25/01

Checked by WAT Date 12/11/01

Subject PIER AND CHUTE

Computation MITER GATE SILL MODIFICATION

g) THREADBAR EMBEDMENT

1) ASSUME MINIMUM CONCRETE STRENGTH EQUAL TO 4,000 PSI.

2) THREADBAR: $F_y = 120 \text{ KSI}$
 $A_s = 0.55 \text{ in}^2$

3) DRILL $1\frac{1}{2}$ " DIA AIR HOLE 1 GA

4) DEVELOPMENT LENGTH - CONSERVATIVE - BASED ON YIELD

$$l_{d0} = \text{MAX} \left\{ \frac{f_y d_b^{3/2}}{2500}; \frac{f_y d_b^2}{43 \gamma_c A} \right\} \text{ in}$$

where $A = \text{AREA DIA, in}^2$

$d_b = \text{REBAR DIA, in}$

$f_y = \text{SPECIFIED MIN YIELD STRENGTH, PSI}$

$\gamma_c = \text{SPECIFIED COMPRESSIVE STRENGTH OF CONCRETE, PSI}$

$$l_{d0} \geq \left\{ \begin{aligned} \frac{f_y d_b^{3/2}}{2500} &= \frac{(120,000 \text{ PSI})(1 \text{ in})^{3/2}}{2500} \left(\frac{\text{ft}}{12 \text{ in}} \right) = 3.50 \text{ FT} \\ \frac{f_y d_b^2}{43 \gamma_c A} &= \frac{(120,000 \text{ PSI})(1 \text{ in})^2}{43 (4000 \text{ PSI} \cdot 1.125 \text{ in})^{1/2}} \times \left(\frac{\text{ft}}{12 \text{ in}} \right) \\ &= 3.50 \text{ FT} \end{aligned} \right.$$

$$\therefore \text{TOTAL LENGTH} = \underline{3.5 \text{ FT}} + \underline{3 \text{ in}} = \underline{4 \text{ FT } 3 \text{ in}}$$

← EMBEDMENT L REBAR PANEL

SUBBEARING

k) EMBEDDED ANCHOR BASE PLATE - $6 \frac{3}{4} \text{ in} \times 6 \frac{3}{4} \text{ in} \times 1 \frac{1}{2} \text{ in}$

l) ANCHOR BASE PLATE WITH SPHERICAL SEAT
 $5 \text{ in} \times 5 \text{ in} \times 1 \frac{1}{4} \text{ in}$

GA/ HILTI REBAR FASTENING GUIDE, FASTENING TECHNOLOGY MANUAL



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 5 B of Pages 26

Subject PANAMA CANAL

Computed by RAA Date 11/30/01

Checked by WAF Date 12/11/01



Computation WATER GATE SILL MODIFICATION

1) CHECK FOR PUNCHING SHEAR STEEL REQUIREMENTS

• 1" THREADED BAR: $F_y = 120 \text{ ksi}$
 $A_c = 0.85 \text{ in}^2$
 $P_{UCT} = 102 \text{ K}$

• EVALUATE FOR MAXIMUM ANCHOR FORCE: $P_{ULT} = 102 \text{ E}$

NOTE: FROM PAGE 5, THE MAXIMUM ANCHOR LOAD IS 57.7 E. THIS IS A CONSERVATIVE APPROACH.



ANCHOR BOLT

• CHECK BEARING

$$P_u = 1.3(1.07)(102) = 225.4 \text{ E}$$

EM 2109, SEC 3.3.2

$$\phi (0.85 f'_c A_1) \sqrt{A_2} \geq P_u$$

ACI 10.17

$$\phi = 0.7$$

ACI 9.3.2.4

$$\sqrt{A_1/A_2} \geq 2 \therefore \text{USE 2}$$

$$A_1 \geq P_u / [2\phi (0.85 f'_c)]$$

$$= 225.4 / [2(0.7)(0.85)(5 \text{ ksi})]$$

$$A_1 \geq 37.9 \text{ in}^2$$

USE ANCHOR INREA BEARING PLATE: 12" X 12" X 1/2"



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 50 of Pages 26

Computed by RAA Date 11/30/01

Checked by WAH Date 12/11/01

Subject PAWAMA CANAL

Computation MITER GATE SILL MODIFICATION


Punching Shear

ACI 11.12

- $d =$ DISTANCE FROM INSET BEARING PLATE TO PRIMARY REINFORCEMENT

$$d = 9'' - \underbrace{1/2''}_{\substack{\text{COVER} \\ \text{PLATE THICKNESS}}} - \underbrace{1/2''}_{\substack{\text{COVER} \\ \text{PLATE THICKNESS}}} - \underbrace{3/4''}_{\substack{\text{COVER} \\ \text{PLATE THICKNESS}}}$$

$$d = 6.25 \text{ in}$$



PERIMETER

$$- b_o = 4(12 + 6.25 \text{ in}) = 73 \text{ in}$$

- ALLOWABLE SHEAR IN CONCRETE

$$V_c \leq (2 + 4/b_o) \sqrt{f'_c} b_o d \quad \text{ACI (11-35)}$$

$$\leq \left(\frac{K_S d + 2}{b_o} \right) \sqrt{f'_c} b_o d \quad \text{ACI (11-36)}$$

$$\leq 4 \sqrt{f'_c} b_o d \quad \text{ACI (11-37)}$$

$$K_S = 40 \quad \left\{ \text{LOADED AREA CONSIDERED AS CENTER COLUMN} \right\}$$

$$b_o = \frac{\text{LONG SIDE OF LOADED AREA}}{\text{SHORT SIDE OF LOADED AREA}} = 1.0$$

- DETERMINE CONTROLLING FACTORS

$$(2 + 4/b_o) = (2 + 4(1)) = 6$$

$$\left(\frac{K_S d + 2}{b_o} \right) = \left(\frac{40(6.25) + 2}{73} \right) = 5.42$$

\therefore EQ ACI (11-37) CONTROLS

$$V_c \leq 4 \sqrt{f'_c} b_o d$$

$$\leq 4 \sqrt{5000} (73 \text{ in}) (6.25 \text{ in}) / (1000 \text{ lb/k})$$

$$V_c \leq 129.0 \text{ k} \quad \text{NG, NEED}$$

\therefore DESIGN SHEAR STEEL BASED ON ACI 11.7.4



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 50 of Pages 26

Computed by RAA Date 11/30/01

Checked by WAH Date 12/11/01

Subject PANAMA CANAL

Computation MITER GATE SILL MODIFICATION

- SIZE SHEAR-FRICTION STEEL

$$V_u = A_v f_y \mu \quad \left\{ \begin{array}{l} \text{According to ACI 11.7.4.2, USE} \\ \text{EQ (11-25) SHEAR FRICTION IN COMPRESSION} \end{array} \right.$$

$$\phi V_s \geq 1.3 (V_u - \phi V_c) \quad \text{EM 2109, p. 3-2}$$

$$V_c = 2 \sqrt{f_c} b_o d \quad \text{ACI 11.12.3.1}$$

$$\phi = 0.95 \quad \text{ACI 9.3.2.3}$$

$$b_o = 4(12 \text{ in}) = 48 \text{ in}$$

$$d \approx 6.25 \text{ in}$$

$$V_c = 2 \sqrt{5000} (48 \text{ in})(6.25 \text{ in}) / (1000 \text{ lbs/ft}^2)$$

$$V_c = 42.4 \text{ K}$$

$$V_u = 1.7 P_{act}$$

$$= 1.7 (102 \text{ K})$$

$$V_u = 173.4 \text{ K}$$

$$V_s \geq 1.3 (V_u - \phi V_c) / \phi$$

$$\geq 1.3 (173.4 \text{ K} - 0.95(42.4 \text{ K})) / 0.95$$

$$V_s \geq 210.1 \text{ K}$$

$$V_u = A_v f_y \mu \geq V_c \quad \text{ACI 11.7.4.3}$$

$$A_v \geq V_c / (f_y \mu)$$

$\mu = 1.4$ CONCRETE PLACED MONOLITHICALLY

$\lambda = 1.0$ FOR NORMAL WT. CONCRETE

$$A_v \geq 210.1 \text{ K} / (60 \text{ KSI} \times 1.4)$$

$$A_v \geq 2.5 \text{ in}^2$$

∴ USE 6 - NO. 6 AS SHEAR FRICTION
FOR PUNCHING SHEAR



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 5E of Pages 20

Computed by PAA Date 11/20/01

Checked by WAH Date 12/11/01

Subject PANAMA CANAL

Computation WATER GATE CILL MODIFICATION

- Length of #6

• DEVELOPMENT

$$l_d = \frac{f_y \times d}{25 \sqrt{f_c}}$$

ACE 10.2.2

$\alpha = 1.0$ 1/2" LAYER

ACE 10.2.4

$\beta = 1.0$ NO EPOXY

$\lambda = 1.0$ NORMAL WT CONCRETE

$d_b = 3/4"$ AIA

$$l_d = \frac{(60,000 \text{ PSI}) (0.75")}{25 \sqrt{5,000 \text{ PSI}}}$$

$$= 25.5"$$

$$l_d = 2'-3"$$

$$\therefore \text{TOTAL LENGTH} = 1' + 2(2'-3")$$

$$= 4'-6"$$

\therefore USE 6 - No. 6 REBAR @ 4'-6" FOR ANCHOR IN BEAC



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 6 of Pages 26

Computed by RAA Date 11/30/01


Checked by WAH Date 12/11/01

Subject PANAMA CANAL

Computation WATER GATE SILL MODIFICATION

4) DETERMINING PICK AND LEVELING POINTS FOR PRECAST PANELS

- a) FOUR (4) PICK POINTS AND LEVELING POINTS WILL BE USED (SEE PRECAST PANEL DWG). THE LEVELING / PICKING DEVICE PERFORMS BOTH FUNCTIONS.
- b) ACCORDING TO PCI ⁷, THE PICK POINTS REQUIRED TO BALANCE POSITIVE AND NEGATIVE BENDING MOMENTS ARE AS FOLLOWS:



- THE PICK/LEVELING POINTS ARE LOCATED 0.207 * EDGE LENGTH FROM EDGES.

	EDGE DISTANCES	DL
• FOR PANELS 20' X 5'	1.04' & 4.14'	DL
• FOR PANELS 21'-4" X 5'	1.04' & 4.42'	DL

5) ESTIMATE FLEXURAL REINFORCEMENT REQUIREMENTS

a) DUE TO PICK & LEVELING LOADS

BOTH FACES:

$$+M_x = -M_x = 0.0107 w a^2 b$$

$$+M_y = -M_y = 0.0107 w a b^2$$

7/ PCI DESIGN HANDBOOK, PRECAST/PRESTRESSED CONCRETE INSTITUTE, 4TH ED., 1992.



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 7 of Pages 26

Computed by RAA Date 12/3/01

Checked by WAT Date 12/11/01



Subject PANAMA CANAL

Computation WATER GATE SILL MODIFICATION

6) MOMENTS DUE TO ECCENTRIC LIFT

- FOR LIFTS, THE CENTRAL LIFT POINT SHOULD BE DIRECTLY LOCATED OVER THE CENTER OF GRAVITY OF THE ENTIRE PANEL (PLAN VIEW). THE TYPICAL ANGLES OF LIFT (θ) ARE GREATER THAN 60° TO "MINIMIZE" THE LATERAL FORCE P_H AND THE SUBSEQUENT BENDING MOMENT.

- FOR MAXIMUM ECCENTRIC HORIZONTAL FORCE P_H , ASSUME 1 CENTRAL LIFT POINT WHERE THE ANGLE IS 60° . AS A RESULT, THERE ARE 1 VERTICAL AND 2 ORTHOGONAL HORIZONTAL REACTIONS.



$$M_x = P_H y_c$$



$$M_x = \frac{P y_c}{\tan \theta}$$

$$M_z = P_v e$$

$$M_z = P e \tan \theta$$

PCI, p. 5-9

FIG 1





US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 8 of Pages 20

Computed by RAA Date 12/3/01

Checked by WAT Date 12/11/01

Subject PALAWA CANAL

Computation WATER GATE SILL MODIFICATION

- FROM SECTION A, THE CENTRAL PICK POINT W, IS:

$$h = 6.42 \tan 60^\circ$$

$$h = 11.11 \text{ FT}$$

- PT W IS $dx = -1.97'$ $dy = 6.25'$ $dz = 11.11'$
FROM PT 1 (FIG 1).

- FIND P_H , P_V , P_z , & T [FIG 2]

• FIND PANEL WEIGHT W :

$$W = (5') (0.75') (21.33') (0.165 \text{ k/ft}^2)$$

$$W = 13.2 \text{ K}$$

• FIND CABLE TENSILE FORCE T :

$$4T \sin 60^\circ = W$$

$$T = \frac{(13.2 \text{ K})}{(4 \sin 60^\circ)}$$

$$T = 3.81 \text{ K}$$

• COMPONENTS OF FORCE HAVE THE SAME COMPONENTS AS DIRECTION

$$dx = -1.97' \quad dy = 6.25' \quad dz = 11.11'$$

$$d = \sqrt{dx^2 + dy^2 + dz^2} = 12.83'$$

$$\text{CHECK SECTION A-A} \rightarrow \frac{1}{d} W = \sqrt{6.42^2 + 11.11^2} = 12.83' \quad \text{OK}$$

$$P = \frac{T}{d} [-1.97' \mathbf{i} + 6.25' \mathbf{j} + 11.11' \mathbf{k}]$$

$$P = \frac{3.81 \text{ K}}{12.83'} [-1.97' \mathbf{i} + 6.25' \mathbf{j} + 11.11' \mathbf{k}]$$

$$P = -(0.99 \text{ K}) \mathbf{i} + (1.86 \text{ K}) \mathbf{j} + (3.30 \text{ K}) \mathbf{k}$$



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 9 of Pages 26

Computed by PAA Date 12/3/01

Checked by WAH Date 12/11/01

Subject PANAMA CANAL

Computation WATER GATE SILL MODIFICATION

• COMPONENTS :

CHECK

$$P_{H1} = 0.44 \text{ K} \rightarrow$$

$$P_{H2} = 1.86 \text{ K} \rightarrow$$

$$P_V = 3.20 \text{ K} \uparrow$$

$$\sqrt{(0.44)^2 + (1.86)^2 + (3.20)^2} = 3.81$$

c) PICK / LEVELING MOMENTS :

$$W = \gamma_c \cdot t \quad \left| \quad \begin{array}{l} \gamma_c = 0.165 \text{ K/ft}^3 \text{ UNIT WT OF CONCRETE} \\ t = 0.75 \text{ ft} \text{ PANEL THICKNESS} \end{array} \right.$$

$$W = 0.124 \text{ K/ft}^2$$

$$+M_x = -M_x = 0.0107 W a^2 b \quad \left| \quad \begin{array}{l} a = 5' \\ b = 21.33' \end{array} \right.$$


$$= 0.0107 (0.124 \text{ K/ft}^2) (5')^2 (21.33')$$

$$+M_x = 0.71 \text{ K-ft}$$

$$+M_y = -M_y = 0.0107 W a b^2$$

$$= 0.0107 (0.124 \text{ K/ft}^2) (5') (21.33')^2$$

$$+M_y = 3.02 \text{ K-ft}$$



d) ECCENTRIC PICK LOADS

$$+M_x = P_{H1} (7.5 \text{ in}) / (12 \text{ in/ft})$$

$$= (0.44 \text{ K}) (7.5 \text{ in}) / (12 \text{ in/ft})$$

$$+M_x = 0.28 \text{ K-ft}$$

$$+M_y = P_{H2} (7.5 \text{ in}) / (12 \text{ in/ft})$$

$$= (1.86 \text{ K}) (7.5 \text{ in}) / (12 \text{ in/ft})$$

$$+M_y = 1.16 \text{ K-ft}$$

e) SUM PICK / LEVELING & ECCENTRIC

$$+M_x = (0.71 + 0.28) \text{ K-ft} = 1.0 \text{ K-ft}$$

$$+M_y = (3.02 + 1.16) \text{ K-ft} = 4.18 \text{ K-ft}$$



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 10 of Pages 26
 Computed by RAA Date 12/3/01
 Checked by WAH Date 12/12/01

Subject PANAMA CANAL
 Computation WATER GATE RISE MODIFICATION


$-M_x = 9.71 \text{ K-FT}$

$-M_y = 3.02 \text{ K-FT}$

5) DETERMINE GROUT MOMENTS:

a) GROUT AT 10 PSL WILL BE USED TO FILL THE JOINTS AND JOINTS BETWEEN THE PRECAST PANELS AND EXISTING CONCRETE

b) CALCULATE MOMENTS:



FOR UPLIFT ON GATE, 2 LOAD CASES WILL BE INVESTIGATED:

- 1) TRANSVERSE SECTION - UPLIFT WITH 2 SUPPORTS
- 2) LONGITUDINAL SECTION - UPLIFT WITH 4 SUPPORTS

- MAXIMUM MOMENTS WILL BE CALCULATED FOR EACH SECTION.

1) TRANSVERSE SECTION


$$W = 10 \text{ PSL} \times (1.65 \text{ sq ft}) \times K$$

$W = 1.44 \text{ KSF}$

$$+M_y = \frac{WL^2}{2}$$

$$= 1.44 \text{ KSF} (5.6 \text{ FT}/2)^2 / 2$$

$+M_x = 5.65 \text{ K-FT/FT}$



AISC, LOAD CASE 2
 P. 2-302

S/ AISC, MANUAL OF STEEL CONSTRUCTION, ALLOWABLE STRESS DESIGN, 1989



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 11 of Pages 26

Computed by RAA Date 12/4/01

Checked by WAH Date 12/11/01

Subject PANAMA CANAL

Computation MITER GATE SILL MODIFICATION

- REDUCE MOMENT $\approx 20\%$ TO ACCOUNT FOR STIFFNESS OF LONGITUDINAL REINFORCEMENT

$$+M_x = 5.65 \text{ K-FT/FT (0.8)}$$

$$+M_x = \underline{\underline{4.52 \text{ K-FT/FT}}}$$

2) LONGITUDINAL SECTION

FOR LONGITUDINAL SECTION, ESTIMATE MOMENTS FROM LOAD CASE 39, AISC P. 2-309. THE TRANSVERSE REINFORCEMENT AT THE PANEL ENDS ACT AS "EFFECTIVE" SUPPORTS. FOR LONG SPAN WITH CONTINUOUS SUPPORTS UNDER UNIFORM LOAD, THE MAXIMUM MOMENTS ARE:

$$+M_y = 0.0714 w l^2 \quad l = \text{SUPPORT SPACING, FT}$$

$$-M_y = 0.0772 w l^2$$

NOTE: $+M_y$ & $-M_y$ ACT IN OPPOSITE DIRECTION FROM THE VALUE PROVIDED IN AISC DUE TO UPLIFT. DUE TO GROUTING SEQUENCE FROM ONE END TO THE OTHER END, CONSERVATIVELY INCREASE MOMENTS BY 50% TO ACCOUNT FOR NON-UNIFORM SPAN LOAD - REVIEW ANALYSIS REQUIRED TO MODEL GROUT ON SLAB WITH ANCHORS

$$\begin{aligned} \therefore +M_y &= 1.5 (0.0714 w l^2) \\ &= 0.1071 w l^2 \quad \text{--- Anchor Spacing} \\ &= 0.1071 (1.44 \text{ KSF}) (4.77 \text{ FT})^2 \end{aligned}$$

$$+M_y = \underline{\underline{3.51 \text{ K-FT/FT}}}$$

$$-M_y = 1.5 (0.0772) (1.44 \text{ KSF}) (4.77 \text{ FT})^2$$

$$-M_y = \underline{\underline{3.79 \text{ K-FT/FT}}}$$

6) MAXIMUM DESIGN MOMENTS

FROM A REVIEW OF THE MOMENTS DUE TO HANDLING AND GROUTING ARECAST PANELS, THE MOMENTS DUE TO GROUTING WILL CONTROL. THE MOMENTS DUE TO STRIPPING FORMS WAS NOT INVESTIGATED SINCE THE STRIPPING SUCTION PRESSURE $124 \text{ PSF} (1.4 \times 16 \text{ LB/FT}^2 \times 0.75 \text{ FT})$



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 12 of Pages 26

Computed by RAA Date 12/2/01

Checked by WAH Date 12/11/01

Subject NAWAMA CANAL

Computation WATER GATE SILL MODIFICATION

IS SIGNIFICANT (LFC THAN) THE GROUT PRESSURE 1,440 PCF
(10 PCF X 144 IN²/FT²)

MAXIMUM DESIGN MOMENTS

$$+M_x = 4.52 \text{ K-FT/FT} \quad \left\{ \begin{array}{l} \text{LET } -M_x = 4.52 \text{ K-FT/FT} \end{array} \right.$$

$$+M_y = 3.51 \text{ K-FT/FT}$$

$$-M_y = 3.79 \text{ K-FT/FT}$$

7) SIZE REINFORCEMENT

a) REINFORCEMENT MAT WILL BE USED FOR BOTH FACES

b) FIND SUFFICIENT STEEL CONDITION:

$$\rho_b = \frac{0.85 f'_c \beta_1}{f_y} \left(\frac{E_c}{E_c + f_y/E} \right)$$

SEE ATTACHMENT
CONCRETE EQ
DERIVATION

$$E_c = 0.003 \quad \text{ACI 10.2.3}$$

$$f_y = 60 \text{ ksi}$$

$$E = 29,000 \text{ ksi}$$

$$\beta_1 = 0.85 \quad \text{ACI 10.2.7.3}$$

$$f'_c = 5 \text{ ksi} \quad \text{CONCRETE STRENGTH}$$

$$\rho_b = 0.0356$$

c) MAXIMUM ALLOWABLE STEEL RATIO:

$$\rho \leq 0.375 \rho_b$$

$$\leq 0.375 (0.0356)$$

$$\rho \leq 0.0134$$

EM 2109, SEC 3-5(2)

d) REINFORCEMENT REQUIRED

$$M_{ELX} = 1.7 M_x (\text{MAX})$$

$$= 1.7 (4.52 \text{ K-FT/FT})$$

$$M_{MAX} = 7.68 \text{ K-FT/FT}$$

$$M_{ELY} = 1.7 (3.79 \text{ K-FT/FT})$$

$$M_{MAX} = 6.44 \text{ K-FT/FT}$$

NOTE: CORRS HYDRAULIC
LOAD FACTOR NOT USED
SINCE GROUTING OPERATION
CONDUCTED PRIOR TO USE
OF PANELS AS HYDRAULIC
STRUCTURE. H_g NOT FOR
CONSTRUCTION CORRS.



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 13 of Pages 26
 Computed by RAA Date 12/4/01
 Checked by WAH Date 12/11/01

Subject PANAMA CANAL
 Computation WATER GATE SILL MODIFICATION

$\phi M_u \geq M_u$ CONCRETE STRENGTH REQUIREMENT

$M_u \geq M_u / \phi$ $\phi = 0.9$ ACT 9.3.2.1

• $M_{u,x} \geq (7.69 \text{ K-FT/FT}) / 0.9$
 $M_{u,x} \geq 8.53 \text{ K-FT/FT}$

• $M_{u,y} \geq (6.44 \text{ K-FT/FT}) / 0.9$
 $M_{u,y} \geq 7.16 \text{ K-FT/FT}$

• DETERMINE REINFORCEMENT AREA & SPACING REQUIRED


SEE ATTACHMENT
FOR DERIVATION
OF EQ

$\frac{f_y^2 A_s^2}{1.7 f_c b} - f_y \rho A_c + M_u = 0$

$f_y = 60 \text{ KSI}$
 $b = 12 \text{ in}$ (1-FT STRIP)

FIND d :

COVER = 1/2 IN $A_c = 7.72$
 ASSUME #6 REBAR



$d = 9 - 1/2 - 3/8 = 7.125 \text{ in}$

$\frac{(60)^2 A_s^2}{1.7(5)(12)} - (60)(7.125) A_c + (8.53)(12 \text{ in/ft}) = 0$

$35.29 A_s^2 - 427.5 A_c + 102.36 = 0$

$A_c \text{ REQUIRED} = 0.22 \text{ in}^2 / \text{ft}$

e) SHRINKAGE & TEMPERATURE

$A_{SET} = 0.0028 A_g$

ENR 2109 SEC 2-5

$= 0.0028 (12 \text{ in})(9 \text{ in})$

$A_{SET} = 0.30 \text{ in}^2 / \text{ft}$ TOTAL

$A_{SET} = 0.15 \text{ in}^2 / \text{ft}$ EACH FACE



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 14 of Pages 26

Computed by RAA Date 12/4/01

Checked by WAT Date 12/11/01

Subject PANAMA CANAL

Computation WATER GATE SILL MODIFICATION

§) FOR $A_{REQUIRED} = 0.22 \text{ in}^2/\text{FT}$ EACH FACE, BOTH WAYS

$\#6 @ 18\text{-IN} = 0.29 \text{ in}^2/\text{FT}$

TO BE CONSERVATIVE AND ACCOUNT FOR GROUT PRESSURE
GREATER THAN 10 PSI, WILL USE $\#6 @ 12\text{ IN}$

USE $\#6 @ 12\text{ IN}$ BOTH FACES & BOTH WAYS




US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 15 of Pages 20
 Computed by EAA Date 12/4/01
 Checked by WAH Date 12/11/01

Subject MAWAMA CANAL
 Computation WATER GATE SILL MODIFICATION

2) PRELIMINARY CID DESIGN



SECTION A
 SCALE: 1/2" = 1'-0"

A) THREADED BAR ANCHORS

1) THE LOADING ON THE CID SEGMENT IS IDENTICAL TO THE LOADINGS ON THE PRECAST PANEL SEGMENT, AS PRESENTED IN THE DESIGN CALCULATIONS, PAGES 1 THROUGH 3. AS A RESULT, THE 1-IN DIA THREADED BAR ANCHORS ARE ADEQUATE SINCE THEIR SPACING IS 2'0" C-C, AND THE SPACING FOR THE ANCHORS FOR THE PRECAST PANEL WAS 4'-9 1/4". THE EMBEDMENT FOR THE ANCHORS IS 3'-6", AS SHOWN ON PAGE 5A.

USE 1-IN DIA THREADED BAR, 2'0" C-C STAGGERED, 4'-0" LENGTH

B) DOWELS

1) NO. 6 DOWELS ARE PLACED ON 2'-0" C-C & STAGGERED

2) FOR NO. 6 DOWELS, GIVEN THE MAXIMUM LOADING FOR THE SILL, PAGE 5, SECTION F; THE SPACING REQUIREMENT IS:



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 16 of Pages 26
 Computed by RAA Date 12/4/01
 Checked by WAH Date 12/11/01

Subject PAWAMA CANAL
 Computation MITER GATE SILL MODIFICATION

$$(0.9 + 0.85) (f_y A_c) \geq \left[\overset{\text{LOAD} \approx \text{K/FT}}{1.65(1.7) P_T} + \overset{\text{SPACING}}{1.3(1.7) V_u} \right] \times S$$

$$A_c = 0.44 \text{ in}^2 \quad \text{See Page 3}$$

$$f_y = 60 \text{ KSI}$$

$$P_T \approx \frac{(7.80 \text{ K/FT} + 2.53 \text{ K/FT})}{2} = 5.17 \text{ K/FT}$$

NOTE: THIS IS APPROXIMATE LOAD ON LEAD
 DOWELS, CONSIDERING THE FACT THAT
 THE 2 LEAD ROW ANCHORS CARRY A
 MAJOR % OF THE UPLIFT.

$$V_u = 2.57 \text{ K/FT} \quad \left\{ \begin{array}{l} \text{LATERAL THRUST - PAGE 3} \\ 12.89 \text{ K/FT} / 5 \text{ DOWELS \& ANCHORS} \end{array} \right.$$

$$S = \frac{1.75 (60 \text{ KSI}) (0.44 \text{ in}^2)}{1.65(1.7)(5.17 \text{ K/FT}) + 1.3(1.7)(2.57 \text{ K/FT})}$$

$$S = 2.29 \text{ FT}$$

USE #6 DOWELS @ 2'-0" C-C

3) EMBEUREMENT INTO EXISTING CONCRETE (SEE PAGE 5A)

DEVELOPMENT: $l_{d_b} = \text{MAX} \left\{ \frac{f_y d_b^{3/2}}{2880}; \frac{f_y d_b^2}{437 \sqrt{f'_c D}} \right\} \leq 12$

$$l_{d_b} \geq \left\{ \begin{array}{l} \frac{f_y d_b^{3/2}}{2880} = \frac{(60000)(0.75)^{3/2}}{2880} = 13.5 \text{ in} \\ \frac{f_y d_b^2}{437 \sqrt{f'_c D}} = \frac{(60000)(0.75)^2}{437 \sqrt{(4000)(7/8)}} = 13.3 \text{ in} \end{array} \right. \quad \leftarrow \text{CONTRACT}$$

USE 2'-2" TO ACCOUNT FOR CONCRETE DAMAGE
 & TO BE CONSERVATIVE

DOWELS = #6 @ 2'-0" C-C, STAGGERED, 2'-2" EMBEUREMENT

USE CERAMIC EPOXY



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 17 of Pages 26

Computed by _____ Date 12/4/01

Subject PAWANA CANAL

Checked by WAT Date 12/11/01

Computation MITFA GATE SILL MODIFICATION

c) SHRINKAGE & TEMPERATURE STEEL

$$A_{ST} \geq 0.0028 A_g$$
$$\geq 0.0028 (12 \text{ in})(12 \text{ in})$$
$$A_{ST} \geq 0.40 \text{ in}^2$$

∴ USE #6 @ 12" EACH WAY, ONE FACE



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 18 of Pages 26


Computed by EAA Date 11/5/01

Checked by WJH Date 12/11/01

Subject PANAMA CANAL

Computation WATER GATE SILL MODIFICATION

3) PRELIMINARY ALTERNATIVE "B" DESIGN



SECTION

SCALE: 1/2" = 1'-0"

(A)

A) 1-IN THREAD BAR AND NO. 10 DOWELS

1) ASSUME FULL HYDROSTATIC UPLIFT ON BASE.

$$U = (4.64 \text{ K/FT}^2) (1.17 \text{ FT}) = 5.43 \text{ K/FT}$$

2) THRUST: ASSUME THRUST APPLIED TO SILL IS EQUAL TO HYDROSTATIC PRESSURE APPLIED TO TRIANGULAR AREA OF LOWEST MAG HORIZONTAL GIRDER. THE LOAD IS 12.89 K/FT

3) ASSUME THE THREAD BAR AND NO. 10 DOWELS CARRY LOADS EQUALLY.



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 19 of Pages 26

Computed by PAA Date 12/6/91

Checked by WAF Date 12/11/91

Subject PANAMA CANAL

Computation WATER GATE SILL MODIFICATION

a) DETERMINE SPACING: (SEE PAGE 5)

$$(2.9 + 0.85)(f_y A_s) \geq [1.65(1.7)P_T + 1.3(1.7)V_u] + S$$

b) 1-IN THREADED: $A_s = 0.85 \text{ in}^2$
 $f_y = 120 \text{ KSI}$

$$P_T = 5.98 \text{ K/FT} / 2 = 2.72 \text{ K/FT}$$

Σ THREADED & ADWEL

$$V_u = 12.89 \text{ K/FT} / 2 = 6.45 \text{ K/FT}$$

$$S = \frac{1.75 (120 \text{ KSI}) (0.85 \text{ in}^2)}{1.65(1.7)(2.72 \text{ K/FT}) + 1.3(1.7)(6.45 \text{ K/FT})} = 5.2 \text{ FT}$$

b) NO. 10 REBAR: $A_s = 1.27 \text{ in}^2$
 $f_y = 60 \text{ KSI}$

$$P_T = 2.72 \text{ K/FT}$$

$$V_u = 6.45 \text{ K/FT}$$

$$S = \frac{1.75 (60 \text{ KSI}) (1.27 \text{ in}^2)}{1.65(1.7)(2.72 \text{ K/FT}) + 1.3(1.7)(6.45 \text{ K/FT})} = 6.09 \text{ FT}$$

c) 1-IN THREADED AND NO. 10 ADWEL ON 2 FT C-C AND STAGGERED 1 FT IS CONSERVATIVE.

d) DEVELOPMENT - USE EPOXY

1) 1-IN THREADED - USE 3'-6" (SEE PAGE 5A)

2) NO. 10 ADWEL (SEE PAGE 16)

$$l_{d_b} = \frac{f_y d_b^{3/2}}{2880} = \frac{(60000)(1.27'')^{3/2}}{2880} = 29.8 \text{ in}$$

$$\left(\frac{f_y d_b^2}{43140} = \frac{(60000)(1.27'')^2}{43140(1.40)} = 25.5 \text{ in} \right)$$



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 20 of Pages 26

Computed by RAA Date 12/6/01

Checked by WAT Date 12/11/01

Subject PANAMA CANAL

Computation MITER GATE SILL MODIFICATION

a) No. 10 90° Hook:

$$l_{db} = l_{db} + \frac{0.7 \times (A_{sREQ} / A_{sPROVIDED})}{\text{ACI 12.5.2.2}} \text{ ACI 12.5.1}$$

$$= 0.7 \times 1200 d_b / \sqrt{f_c} \times (A_{sREQ} / A_{sPROVIDED})$$

According to SEC 4(c) OF PAGE 19, USING A SPACING OF 2'-0", $A_{sREQ} = 0.42 \text{ in}^2$

$$\therefore l_{db} = 0.7 (0.42 / 1.27) (1200) (1.27) / \sqrt{4000}$$

$$l_{db} = 5.6 \text{ in}$$

$$\text{HOOK} = 12 d_b = 12 (1.27) = 15.24 \text{ in}$$

USE 12"

b) NO. 10 HOOKS LENGTH:

$$L = \frac{30 \text{ in} + 6 \text{ in} + 12 \text{ in}}{2 \text{ EMBRANCHMENT}}$$

$$L = \underline{\underline{4'-0 \text{ in}}}$$



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page of Pages



Computed by RAA Date 12/7/61

Checked by Date


Subject MANANA CANAL

Computation MITER GATE SILL MODIFICATION


REFERENCE MATERIAL




SECTION
SCALE: 1/2" = 1'-0"




TYPICAL JOINT
SCALE: 3" = 1'-0"




DETAIL
SCALE: 1" = 1'-0"



DETAIL
SCALE: 1" = 1'-0"




TYPICAL "A" PANELS
SCALE: 3" = 1'-0"




TYPICAL "B" PANELS
SCALE: 3" = 1'-0"

PLAN
SCALE: 1/2" = 1'-0"



PLAN
SCALE: 1/4" = 1'-0"



PANAMA CANAL COMMISSION INTERNATIONAL AND CONSTRUCTION MARKING DRAWING NUMBER: 34/36	
MITER GATE STUDY	
2'-0" REMOVAL OF EXISTING SILL PRECAST PANEL NEW SILL	
SCALE AND DATE	DATE: 1958
DESIGNED BY	DESIGNED: [Signature]
CHECKED BY	CHECKED: [Signature]
APPROVED BY	APPROVED: [Signature]

JOB SAFETY DEPENDS ON YOU

XXXX-XXXX


```
*****  
*  
*          STAAD.Pro          *  
*      Version 2001    Build 1005      *  
*      Proprietary Program of          *  
*      RESEARCH ENGINEERS, Intl.      *  
*      Date=    DEC  7, 2001          *  
*      Time=    15:31:57              *  
*  
*      USER ID: US Army COE - Pittsburgh  *  
*****
```

1. STAAD PLANE
2. START JOB INFORMATION
3. ENGINEER DATE 07-DEC-01
4. END JOB INFORMATION
5. INPUT WIDTH 79
6. UNIT FEET KIP
7. JOINT COORDINATES
8. 1 0 0 0; 2 1 0 0; 3 2.5 0 0; 4 4 0 0; 5 5 0 0
9. MEMBER INCIDENCES
10. 1 1 2; 2 2 3; 3 3 4; 4 4 5
11. MEMBER PROPERTY AMERICAN
12. 1 TO 4 TABLE ST W6X15
13. SUPPORTS
14. 2 TO 4 PINNED
15. UNIT INCHES KIP
16. CONSTANTS
17. E 29000 MEMB 1 TO 4
18. POISSON 0.3 MEMB 1 TO 4
19. DENSITY 0.000283 MEMB 1 TO 4
20. ALPHA 6E-006 MEMB 1 TO 4
21. UNIT FEET KIP
22. LOAD 1
23. MEMBER LOAD
24. 1 TRAP Y 0 -0.932 0 1
25. 2 TRAP Y -0.932 -2.33 0 1.5
26. 3 TRAP Y -2.33 -3.73 0 1.5
27. 4 TRAP Y -3.73 -4.66 0 1
28. PERFORM ANALYSIS

P R O B L E M S T A T I S T I C S

NUMBER OF JOINTS/MEMBER+ELEMENTS/SUPPORTS = 5/ 4/ 3
ORIGINAL/FINAL BAND-WIDTH= 1/ 1/ 4 DOF
TOTAL PRIMARY LOAD CASES = 1, TOTAL DEGREES OF FREEDOM = 9
SIZE OF STIFFNESS MATRIX = 1 DOUBLE KILO-WORDS
REQRD/AVAIL. DISK SPACE = 12.0/ >2000 MB, EXMEM = 464.0 MB

++ Processing Element Stiffness Matrix. 15:31:57
++ Processing Global Stiffness Matrix. 15:31:57
++ Processing Triangular Factorization. 15:31:57
++ Calculating Joint Displacements. 15:31:57
++ Calculating Member Forces. 15:31:57

29. PRINT SUPPORT REACTION ALL

SUPPORT REACTIONS -UNIT KIP FEET STRUCTURE TYPE = PLANE

JOINT	LOAD	FORCE-X	FORCE-Y	FORCE-Z	MOM-X	MOM-Y	MOM Z
2	1	0.00	1.32	0.00	0.00	0.00	0.00
3	1	0.00	2.53	0.00	0.00	0.00	0.00
4	1	0.00	7.80	0.00	0.00	0.00	0.00

***** END OF LATEST ANALYSIS RESULT *****

30. PERFORM ANALYSIS

++ Processing Element Stiffness Matrix. 15:31:57
 ++ Processing Global Stiffness Matrix. 15:31:57
 ++ Processing Triangular Factorization. 15:31:57
 ++ Calculating Joint Displacements. 15:31:57
 ++ Calculating Member Forces. 15:31:57

31. FINISH

***** END OF THE STAAD.Pro RUN *****

**** DATE= DEC 7,2001 TIME= 15:31:57 ****

 * For questions on STAAD.Pro, please contact : *
 * By Email - North America : support@ca.reiusa.com *
 * By Email - International : support@reiusa.com *
 * Tel. (USA) : 714-974-2500 ; Fax (USA) : 714-974-4771 *



Software licensed to US Army COE - Pittsburgh

Job No

Sheet No

1

Rev

Part

Ref

By

Date 07-Dec-01


Chd

Job Title

Client

File Rich.std


Date/Time 07-Dec-2001 15:31



Whole Structure



DYWIDAG Threadbar Rock and Soil Anchors



The Dywidag Threadbar System is manufactured in the United States exclusively by Dywidag Systems International. Used worldwide since 1965, the threadbar system provides a simple, rugged method of efficiently applying prestress force to a wide variety of structural systems including posttensioned concrete, rock and soil anchor systems.

Available in $\frac{5}{8}$ " , 1" , $1\frac{1}{4}$ " and $1\frac{3}{8}$ " nominal diameter, Dywidag Threadbars are hot rolled and proof stressed alloy steel conforming to ASTM A 722.

The Dywidag Threadbar has a continuous rolled-in pattern of threadlike deformations along its entire length. More durable than machine threads, the deformations allow anchorages and couplers to thread onto the threadbar at any point.

The strength of the Dywidag Threadbar anchorages and couplers exceeds the requirements of ACI 318. Test reports are available for the main components of the system.

Conforming to the requirements of ASTM A 615, the threadbar deformations


develop an effective bond with cement or resin grout. The continuous thread simplifies stressing. Lift off readings may be taken at any time, and the prestress force increased or decreased as required.

The anchor plate need not be perpendicular to the Dywidag Threadbar. The curved surface of the anchor nut accommodates up to 5° misalignment. As much as a 25° misalignment of the threadbar with the bearing plate can be corrected by using a set of wedge washers with the anchor nut.


Available in mill lengths to 60', threadbars may be cut to specified lengths before shipment to the job site. Or where circumstances warrant, the threadbars may be shipped to the job site in mill lengths for field cutting with a portable friction or band saw. Threadbars may be coupled for ease of handling or to extend a previously stressed bar.

The Dywidag Threadbar System is used extensively in rock and soil anchor construction because of its versatility, strength, performance characteristics and off-the-shelf availability of most components.

Anchorage



Coupling



Threadbar Rock and Soil Anchors

Prestressing steel properties

Nominal Threadbar Diameter (inches)	Ultimate Stress (f_{pu} -ksi)	Cross Section Area (A_{ps} -inches ²)	Ultimate Strength ($f_{pu} A_{ps}$)	Prestressing Force — (kips)			Weight (lbs./ft.)	Minimum** Elastic Bending Radius (ft.)	Maximum Threadbar Diameter (inches)
				$0.80f_{pu} A_{ps}$	$0.70f_{pu} A_{ps}$	$0.60f_{pu} A_{ps}$			
5/8	157	0.28	43.5	34.8	30.5	26.1	0.98	26	0.693
1	150	0.85	127.5	102.0	89.3	76.5	3.01	52	1.201
1	160*	0.85	136.0	108.8	95.2	81.6	3.01	49	1.201
1 1/4	150	1.25	187.5	150.0	131.3	112.5	4.39	64	1.457
1 1/4	160*	1.25	200.0	160.0	140.0	120.0	4.39	60	1.457
1 3/8	150	1.58	237.0	189.6	165.9	142.2	5.56	72	1.630
1 3/8	160*	1.58	252.8	202.3	177.0	151.7	5.56	67	1.630

*Grade 160 Dywidag Threadbars available on special order when lead time permits.

**Prebent bars are required for radii less than the minimum elastic radius.

Steel stress levels

Dywidag Threadbars may be stressed to the allowable limits of ACI 318. The maximum working stress (temporary) may not exceed $0.80 f_{pu}$, and the transfer stress (lockoff) may not exceed $0.70 f_{pu}$.


The final effective (working) prestress level depends on the specific application, installation procedure, stressing sequence, and the rigidity of the structural system. In the absence of a detailed analysis of the

structural system, $0.60f_{pu}$ may be used as an approximation of the effective (working) prestress level.

Dywidag Threadbars may be used individually or in multiples depending upon the magnitude of force requirements or upon drilling considerations.

Actual loss calculations require structural design information not normally present on contract documents.

Wedge Washer Assembly




Anchorage Details

Threadbar Diameter (inches)	5/8	1	1 1/4	1 3/8
Anchor Plate Size (inches)	2 x 5 x 1 3 x 3 x 3/4	4 x 6 1/2 x 1 1/4 5 x 5 x 1 1/4	5 x 8 x 1 1/2 6 1/4 x 6 1/4 x 1 1/2	5 x 9 1/2 x 1 3/4 7 x 7 1/2 x 1 3/4
Nut Extension (inches) a	1 1/16**	1 7/8	2 1/2	2 3/4
Min. Bar Protrusion (inches) b	2 1/2	3	3 1/2	4



Coupler Details

Threadbar Diameter (inches)	5/8	1	1 1/4	1 3/8
Length (inches) c	4 1/2	5 1/2	6 3/4*	8 5/8
Diameter (inches) d	1 1/4	2	2 3/8	2 5/8

*7 1/2" long coupler available on special order.



1 1/4" Dywidag Threadbar soil anchors installed in a dry sand and gravel to tieback H-beam and concrete underpinning wall in 40 ft. deep excavation. Anchor design and installation by Richard Goettle Inc., Cincinnati, Ohio.



1 3/8" Dywidag Threadbar soil anchors installed in wet sand to tieback H-beam and timber lagging system in 40 ft. excavation. Anchor design and installation by Schnabel Foundation Co., Washington, D. C.

DYWIDAG SYSTEMS INTERNATIONAL, USA, INC.



Systems and Ideas

Corporate Office: 301 Marmon Drive, Lemont, IL 60439-9006 (708) 739-1100

07 Beaver Brook Road, Lincoln Park, NJ 07035 (201) 628-8700
 624 Belle Vista Drive East, St. Petersburg Beach, FL 33706 (813) 360-5648
 Suite H-1, 1341 Canton Road, NE, Marietta, GA 30066 (404) 421-9872
 17 Joppa Road, Baltimore, MD 21234 (301) 882-6111
 14 Elm Tree Place, 360-1002, Route 101, Bedford, NH 03102 (603) 472-7050

01 Marmon Drive, Lemont, IL 60439 (708) 739-1100
 5421 Trail Bend Drive, Florissant, MO 63033 (314) 741-5044
 1474 Grandview Avenue, Suite 1, Columbus, OH 43212 (614) 486-8793
 76 Creekside Drive, Avon Lake, OH 44012 (216) 933-7965
 169 Ruggles Drive, Grand Prairie, TX 75050 (214) 647-8152

39059 Guardino Drive, Suite 107, Fremont, CA 94538 (415) 792-4315
 2154 South Street, Long Beach, CA 90805 (213) 531-6161
 483 1/2 Anjou Drive, Grand Junction, CO 81504 (303) 434-9194
 P.O. Box 422, Parker, CO 80134 (303) 841-6879
 7225 S.W. 86th Street, Portland, OR 97223 (503) 245-8917

Dywidag Systems International, Canada LTD.
 65 Bowes Road, Unit 5, Concord, Ontario L4K 1H5, Canada (416) 669-4952
 100 Alexis Nihon Boulevard, Suite 216, St. Laurent, Quebec H4M 2N7, Canada (514) 744-6429
 2702 Ware Street, Suite 204, Abbotsford, BC V2S 5E6, Canada (604) 852-6466
 3701 19th Street, N.E., Calgary, Alberta T2E 6S8, Canada (403) 291-4414



Standard Specification for Uncoated High-Strength Steel Bars for Prestressing Concrete¹

This standard is issued under the fixed designation A 722/A 722M; the number immediately following the designation indicates the year of original adoption or, in the case of revision, the year of last revision. A number in parentheses indicates the year of last reapproval. A superscript epsilon (ϵ) indicates an editorial change since the last revision or reapproval.

1. Scope

1.1 This specification covers uncoated high-strength steel bars intended for use in pretensioned and post-tensioned prestressed concrete construction or in prestressed ground anchors. Bars are of a minimum ultimate tensile strength level of 1035 MPa (150 000 psi).

1.2 Two types of bars are provided: Type I bar has a plain surface and Type II bar has surface deformations.

1.3 Supplementary requirements of an optional nature are provided. They shall apply only when specified by the purchaser.

1.4 The values stated in SI units are to be regarded as the standard. The values given in parentheses are for information only.

2. Referenced Documents

2.1 ASTM Standards:

A 370 Test Methods and Definitions for Mechanical Testing of Steel Products²

A 700 Practices for Packaging, Marking, and Loading Methods for Steel Products for Domestic Shipment³

E 30 Test Methods for Chemical Analysis of Steel, Cast Iron, Open-Hearth Iron, and Wrought Iron⁴

3. Ordering Information

3.1 Orders for material under this specification should include the following information:

3.1.1 Quantity,

3.1.2 Name of material (uncoated high-strength bars for prestressing concrete),

3.1.3 ASTM designation and year of issue,

3.1.4 Size and length,

3.1.5 Type,

3.1.6 Special inspection requirements, if desired (see Section 12),

3.1.7 Special preparation for delivery, if desired (see Section 11), and

3.1.8 Supplementary requirements, if desired.

NOTE 1—A typical ordering description is as follows: 50 uncoated high-strength steel bars for prestressing concrete to ASTM-A-722/A 722M - ; 26 mm diameter, 12.20 m long, Type II; packed in accordance with A 700; meeting supplementary bending properties.

4. Materials and Manufacture

4.1 The bars shall be rolled from properly identified heats of ingot cast or strand cast steel. The standard sizes and dimensions of Type I and II bars shall be those listed in Table 1 and Table 2, respectively.

4.2 The bars shall be subjected to cold-stressing to not less than 80 % of the minimum ultimate strength, and then shall be stress relieved, to produce the prescribed mechanical properties.

5. Chemical Composition

5.1 An analysis of each heat of steel shall be made by the manufacturer from test samples taken during the pouring of each heat.

5.1.1 Choice and use of chemical composition and alloying elements, to produce the mechanical properties of the finished bar prescribed in 6.2, shall be made by the manufacturer, subject to the limitations in 5.1.2.

5.1.2 On heat analysis, phosphorus and sulfur shall not exceed the following:

Phosphorus	0.040 %
Sulfur	0.050 %

5.2 A product analysis may be made by the purchaser from the finished bar representing each cast or heat of steel. The phosphorus and sulfur contents thus determined shall not exceed the limits specified in 5.1.2 by 0.008 %.

5.3 Method E 30 shall be used for referee purposes.

6. Mechanical Properties

6.1 All testing for mechanical properties shall be performed in accordance with the requirements of Methods and Definitions A 370.

6.2 Tensile Properties:

6.2.1 Finished bars shall have a minimum ultimate tensile strength of 1035 MPa (150 000 psi).

¹ This specification is under the jurisdiction of ASTM Committee A-1 on Steel, Stainless Steel, and Related Alloys and is the direct responsibility of Subcommittee A01.05 on Steel Reinforcement.

Current edition approved April 10, 1998. Published December 1998. Originally published as A 722 - 75. Last previous edition A 722/A 722M - 97a.

² Annual Book of ASTM Standards, Vol 01.03.

³ Annual Book of ASTM Standards, Vol 01.05.

⁴ Annual Book of ASTM Standards, Vol 03.05.

TABLE 1 Dimensions for Type I (Plain) Bar

Nominal Diameter		Nominal Mass (Weight)		Nominal Area ^A	
mm	in.	kg/m	lb/ft	mm ²	in. ²
19	¾	2.23	1.50	284	0.44
22	⅞	3.04	2.04	387	0.60
25	1	3.97	2.67	503	0.78
29	1⅛	5.03	3.38	639	0.99
32	1¼	6.21	4.17	794	1.23
35	1⅜	7.52	5.05	955	1.48

^AThe nominal area is determined from the nominal diameter in inches. Values have been converted from inch-pound units to metric units.

TABLE 2 Dimensions for Type II (Deformed) Bar

Nominal Diameter ^A		Nominal Mass (Weight)		Nominal Area ^B	
mm	in.	kg/m	lb/ft	mm ²	in. ²
15	⅝	1.46	0.98	181	0.28
20	¾	2.22	1.49	271	0.42
26	1	4.48	3.01	548	0.85
32	1¼	6.54	4.39	806	1.25
36	1⅜	8.28	5.56	1019	1.58
46	1⅞	13.54	9.10	1664	2.58
65	2½	27.10	18.20	3331	5.16

^ANominal diameters are for identification only. Values have been converted from metric to inch-pound units.

^BThe nominal area is determined from the bar weight less 3.5 % for the ineffective weight of the deformations.

6.2.2 The minimum yield strength of Type I and Type II bars shall be 85 % and 80 %, respectively, of the minimum ultimate tensile strength of the bars. The yield strength shall be determined by either of the methods described in Test Methods and Definitions A 370; however, in the extension under load method, the total strain shall be 0.7 %, and in the offset method the offset shall be 0.2 %.

6.2.3 The minimum elongation after rupture shall be 4.0 % in a gage length equal to 20 bar diameters, or 7.0 % in a gage length equal to 10 bar diameters.

6.3 Test Specimens—Tension tests shall be made using full-size bar test specimens. Machined reduced section test specimens are not permitted. All unit stress determinations shall be based on the nominal area shown in Table 1 or the effective area shown in Table 2.

6.4 Number of Tests—The number of tensile specimens tested shall be one from each 36 Mg (39 tons) or fraction thereof, of each size of bar rolled from each heat but not less than two from each heat. The specimens shall be randomly selected following the final processing operation.

6.5 Retests:

6.5.1 If any tensile property of any tension test specimen is less than that specified, and any part of the fracture is outside the middle third of the gage length, as indicated by scribe scratches marked on the specimen before testing, a retest shall be allowed.

6.5.2 If the results of an original tension test fail to meet specified requirements, two additional tests shall be made on samples of bar from the same heat and bar size, and if failure occurs in either of these tests, the bar size from that heat shall be rejected.

6.5.3 If any test specimen fails because of mechanical reasons such as failure of testing equipment, it shall be discarded and another specimen taken.

6.5.4 If any test specimen develops flaws, it shall be

discarded and another specimen of the same size bar from the same heat substituted.

7. Requirements for Deformations

7.1 Material furnished as Type II bar shall have deformations spaced uniformly along the length of the bar. The deformations on opposite sides of the bar shall be similar in size and shape. The average spacing or distance between deformations on both sides of the bar shall not exceed seven tenths of the nominal diameter of the bar.

7.2 The minimum height and minimum projected area of the deformations shall conform to the requirements shown in Table 3.

7.3 Mechanical Coupling—For those bars having deformations arranged in a manner to permit coupling of the bars with a screw-on type coupler, it shall be the responsibility of the finished-bar manufacturer to demonstrate that a bar cut at any point along its length may be coupled to any other length of bar and that a coupled joint supports the minimum specified ultimate tensile strength of the coupled bars. The coupler type shall be provided or designed by the finished-bar manufacturer.

8. Measurements of Deformations

8.1 The average spacing of deformations shall be determined by dividing a measured length of the bar specimen by the number of individual deformations and fractional parts of deformations on any one side of the bar specimen. A measured length of the bar specimen shall be considered the distance from a point on a deformation to a corresponding point on any other deformation on the same side of the bar.

8.2 The average height of deformations shall be determined from measurements made on not less than two typical deformations. Determinations shall be based on three measurements per deformation: one at the center of the overall length, and the other two at the quarter points of the overall length.

8.3 To indicate adequately the conformity to the dimensional requirements, measurements shall be taken at random from one bar from each 30 Mg (33 tons) of each lot or fraction thereof.

8.4 Insufficient height, insufficient projected area, or excessive spacing of deformations shall not constitute cause for rejection unless it has been clearly established by determinations on each lot that typical deformation height or spacing

TABLE 3 Deformation Dimensions for Type II Bar

Nominal Diameter	Deformation Dimensions						
	Maximum Average Spacing		Minimum Average Height		Minimum Projected Area ^A		
	mm	in.	mm	in.	mm ² /mm	in. ² /in.	
15	⅝	11.1	0.44	0.7	0.03	2.4	0.09
20	¾	13.3	0.52	1.0	0.04	3.4	0.13
26	1	17.8	0.70	1.3	0.05	4.4	0.17
32	1¼	22.5	0.89	1.6	0.06	5.4	0.21
36	1⅜	25.1	0.99	1.8	0.07	6.1	0.24
46	1⅞	30.1	1.19	2.2	0.09	7.3	0.29
65	2½	44.5	1.75	2.9	0.11	9.7	0.38

^ACalculated from equation, min projected area = 0.75πd h/s

where:

d = nominal diameter,

h = minimum average height, and

s = maximum average spacing.

does not conform to the minimum requirements prescribed in Section 7. No rejection shall be made on the basis of measurements if fewer than ten adjacent deformations on each side of the bar are measured.

NOTE 2—The term “lot” shall mean all bars of the same nominal mass (weight) per metre (linear foot) contained in an individual shipping release or shipping order.

9. Permissible Variation in Size or Weight

9.1 For Type I bars, the permissible variation from the nominal diameter specified in Table 1 shall not exceed +0.75, -0.25 mm (+0.030, -0.010 in.).

9.2 For Type II bars, the permissible variation from the nominal weight specified in Table 2 shall not exceed +3 %, -2 %.

10. Finish

10.1 The bars shall be free of defects injurious to the mechanical properties and shall have a workmanlike finish.

11. Delivery

11.1 Unless otherwise specified in the contract or purchase order, bars shall be packed for delivery in accordance with the finished-bar manufacturer’s standard commercial practice.

11.2 When specified in the contract or purchase order, bars shall be packed in accordance with Practices A 700.

11.3 Marking:

11.3.1 Unless otherwise specified in the contract or purchase order, bars shall be sorted by size and each bundle or lift shall be properly tagged showing heat number, size, specification number (ASTM A 722), and the name of the finished-bar manufacturer in order to assure proper identification. The tags shall display the following statement: “High-Strength Prestressing Bars.” The tags shall be made of durable material and marked in a legible manner with waterproof markings; not less than one tag per bundle or lift, attached by wire (see Note 3). In addition, both ends of each bar shall be painted yellow.

NOTE 3—It should be recognized that the legibility of markings on tags has a finite life. When bundles or lifts of bars are stored outdoors for a long period of time, fading of the markings on non-metallic tags, or oxidation of the markings on metal tags, can be expected to occur.

11.3.2 When specified in the contract or purchase order, bars shall be marked in accordance with Practices A 700.

12. Inspection

12.1 The inspector representing the purchaser shall have free entry, at all times while work on the contract of the purchaser is being performed, to all parts of the manufacturer’s works that concern the manufacture of the material ordered. The manufacturer shall afford the inspector all reasonable facilities to satisfy him that the material is being furnished in

accordance with this specification. All tests (except product analysis) and inspection, shall be made at the place of manufacture prior to shipment, unless otherwise specified, and shall be so conducted as not to interfere unnecessarily with the operation of the works.

12.2 If specified in the purchase order, the purchaser shall reserve the right to perform any of the inspection set forth in the specification where such inspections are deemed necessary to assure that the material furnished conforms to prescribed requirements.

12.3 If outside inspection is waived, the finished-bar manufacturer’s certification that the material has been tested in accordance with, and meets the requirements of, this specification, shall be the basis of acceptance of the material.

13. Rejection

13.1 Unless otherwise specified, any rejection based on tests made in accordance with 5.2 shall be reported to the manufacturer within 5 working days from the receipt of samples by the purchaser.

13.2 Material that shows injurious defects subsequent to its acceptance at the manufacturer’s works shall be subject to rejection, and the manufacturer shall be notified.

14. Rehearing

14.1 Samples tested in accordance with 5.2 that represent rejected material shall be preserved for two weeks from the date rejection is reported to the manufacturer. In case of dissatisfaction with the results of the tests, the manufacturer shall be permitted to make claim for a rehearing within that time.

15. Certification

15.1 If outside inspection is waived, a manufacturer’s certification that the material has been tested in accordance with and meets the requirements of this specification shall be the basis of acceptance of the material. The certification shall include the specification number, year-date of issue, and revision letter, if any.

15.2 The manufacturer shall, when requested in the order, furnish a representative load-elongation curve for each size and grade of bar shipped.

15.3 A modulus of elasticity value of 205 GPa (29 700 000 psi) shall be used for the purpose of elongation calculation for Type II bars.

NOTE 4—Experience has shown that plotted load elongation curves from mill tests on Type II vary excessively and are not sufficiently reliable for use in calculating E-modulus values.

16. Keywords

16.1 high-strength steel bars; prestressed concrete; post-tensioning; deformed bars; plain bars

pci design handbook

Precast and Prestressed Concrete

FOURTH EDITION

MNL 120-92



PRECAST/PRESTRESSED CONCRETE INSTITUTE
175 WEST JACKSON BOULEVARD
CHICAGO, ILLINOIS 60604

312 786-0300 FAX 312 786-0353

Copyright© 1992
By Precast/Prestressed Concrete Institute
First edition, first printing, 1971
First edition, second printing, 1972
Second edition, first printing, 1978
Second edition, second printing, 1980
Third edition, first printing, 1985
Fourth edition, first printing, 1992


All rights reserved. This book or any part thereof may not
be reproduced in any form without the written permission
of the Precast/Prestressed Concrete Institute.

Library of Congress Catalog Card Number 92-61318

ISBN 0-937040-51-7

Printed in U.S.A.

Fig. 5.2.5 Moments developed in panels stripped flat



w = weight per unit area

(a) Two point pick-up

Maximum Moments (Approximate)

$$+M_x = -M_x = 0.0107 wa^2b$$

$$+M_y = -M_y = 0.0107 wab^2$$

M_x resisted by a section of width $15t$ or $b/2$, whichever is less.

M_y resisted by a section of width $a/2$.

(b) Four point pick-up

Maximum Moments (Approximate)

$$+M_x = -M_x = 0.0054 wa^2b$$

$$+M_y = -M_y = 0.0027 wab^2$$

M_x resisted by a section of width $15t$ or $b/4$, whichever is less.

M_y resisted by a section of width $a/2$.

mechanisms to increase the angle of lift. Any such special handling requirements should be clearly shown on the shop drawings.

In addition to longitudinal bending moments, a transverse bending moment may be caused by the orientation of the pick-up points with respect to the transverse dimension (Fig. 5.2.8). For the section shown, a critical moment could occur between the ribs because of the thin cross-section.

The design guidelines listed above apply to elements of constant cross-section. For elements of varying cross-section, the location of lift points is usually determined by trial and error. Rolling blocks can be used on long elements of varying section (Fig.

5.2.10), which makes the forces in the lifting lines equal. The member can then be analyzed as a beam with varying load supported by equal reactions.

The force in inclined lift lines can be determined from Fig. 5.2.7.

5.2.8 Handling Devices

The most common lifting devices are prestressing strand or cable loops projecting from the concrete, threaded inserts, or special proprietary devices.

Since lifting devices are subject to dynamic loads, ductility of the material is part of the design

Fig. 5.2.6 Stripping from a tilt table




Fig. 5.2.7 Determination of force in inclined lift lines




Fig. 5.2.8 Pick-up points for equal stresses of a ribbed member





Fig. 5.2.9 Moments caused by eccentric lifting





US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 19 of Pages


Subject Johnston, L.F.A.

Computed by E.A.A. Date 6/24/93

Computation UNIT 3 ANALYSIS TIE-BACK WALL

Checked by Date

BALANCE CONCRETE BEAM EQUATIONS



• FIND N.A. FROM STRAIN COMPATIBILITY:

$$\frac{\epsilon_c}{c} = \frac{\epsilon_s}{d-c} \quad c = \frac{d \epsilon_c}{\epsilon_c + \epsilon_s} \quad (1) \quad \text{FOR BALANCE STEEL CONDITION } (\rho_b):$$

$$\epsilon_c = f_y / E_c$$

$$\underline{\underline{c_b = \frac{d E_c}{E_c + f_y / E_c}}} \quad (2) \quad \text{BALANCED N.A.}$$

• FIND BALANCE STEEL CONDITION (ρ_b):

$$\sum M_x = 0 \quad T - C = 0 \quad A_s f_y = 0.85 f_c' b c \quad (3) \quad \text{LET } c = c_b = \frac{d E_c}{E_c + f_y / E_c}$$

$$\rho_b = \frac{A_c}{bd} = \frac{0.85 f_c' b c}{f_y} \left(\frac{E_c}{E_c + f_y / E_c} \right) \quad (4)$$

NOTE: FOR STEEL TO YIELD: $\rho(\text{ACTUAL}) \leq \rho_b$

• FIND REQUIRED DEPTH (d) & STEEL (A_c) FOR NOMINAL MOMENT (M_n): KNOW ρ

$$M_n = A_c f_y \left(d - \frac{a}{2} \right) \quad a = \beta_1 c = \frac{A_c f_c}{0.85 f_c' b} \quad (\text{see (4)})$$

$$= \rho b d f_y \left(d - \frac{A_c f_y}{1.7 E_c b} \right) \quad \rho = \frac{A_c}{bd}$$

$$\underline{\underline{M_n = \rho b d^2 f_y \left(1 - \frac{\rho f_y}{1.7 E_c} \right)}} \quad (5) \quad \text{KNOW } M_n, \rho, f_y, \frac{f_c}{E_c} \text{ & SOLVE FOR "d"}$$

$$M_n = A_c f_y \left(d - \frac{a}{2} \right) \quad a = A_c f_y / (0.85 f_c' b)$$


$$\frac{f_y^2}{1.7 E_c} A_c^2 - f_y d A_c + M_n = 0 \quad (6) \quad \text{KNOW } M_n, f_y, d, b \text{ & SOLVE FOR } A_c$$

Fastening Technology Manual

HILTI

Rebar Fastening Guide

HILTI MD2000



Test Arrangement

HILTI[®]

TODD PADEZANIN
Regional Field Engineer
Pennsylvania/Upstate New York
(800) 879-8000

Hilti Center: 1301 Beaver Avenue, Pittsburgh, PA
Mailing Address: P.O. Box 21148, Tulsa, OK 74121
Fax (800) 879-7000

ISO 9001 REGISTERED

Curing time

The curing time is dependent on temperature.

Base Material Temperature	Gel Time t_{gel}	Curing Time t_{cure}
23°F (-5 °C)	25 Minutes	6 Hours
32°F (0 °C)	18 Minutes	3 Hours
41°F (5 °C)	13 Minutes	1.5 Hours
68°F (20 °C)	5 Minutes	50 Minutes
86°F (30 °C)	4 Minutes	40 Minutes
104°F (40 °C)	2 Minutes	30 Minutes

Maintain foil pack temperature between 41°F and 104°F (5°C and 40°C).

Drill bit diameter

The correct drill bit diameter is important for the performance of the adhesive bond as well as for the economy of the application.

Nominal Rebar Diameter d_b	Maximum Recommended Hole Diameter* D
#3 (3/8")	1/2"
#4 (1/2")	3/4"
#5 (5/8")	7/8"
#6 (3/4")	1"
#7 (7/8")	1 1/8"
#8 (1")	1 1/4"


Injection volume

Nominal Rebar Diameter	Drill Bit Diameter* (in.)	Typical Adhesive Volume Required per inch of Embedment (in. ³)
#3 or 3/8"	1/2	0.105
#4 or 1/2"	5/8	0.131
#5 or 5/8"	3/4	0.176
#6 or 3/4"	7/8	0.218
#7 or 7/8"	1	0.236
#8 or 1"	1 1/8	0.284
#9 or 1 1/8"	1 5/16	0.466
#10 or 1 1/4"	1 3/8	0.433
#11 or 1 3/8"	1 9/16	0.820

NOTE: Useable volume of HIT HY 150 refill pack is 16.5 in.³ (270 ml)
 Useable volume of HIT HY 150 large cartridges is 61.0 in.³ (1000 ml)
 *Rebar diameter may vary. Use smallest drill bit which will accomodate rebar.

3.3.2 Bond to Rebar

The force, F_b , which can be transferred in bond between rebar and adhesive increases linearly with the development length, but only with the square root of the rebar diameter.




Adhesive bond failure

Design Strength of Adhesive:

$F_b =$	2260	•	l_d	•	$\sqrt{d_b}$
[lb]			[in.]		[in.]
$F_b =$	78	•	l_d	•	$\sqrt{d_b}$
[N]			[mm]		[mm]

The square root takes into consideration that small rebar diameters are typically used in groups, whereas larger diameters occur more often as single anchorage points.

This equation allows for the performance of the adhesive. It was developed by Professor Peter Marti of the Swiss Federal Institute of Technology (ETH), Zurich, based on a review of comprehensive test data.




This value controls when the installed development length is smaller than the basic development length and the compressive strength of concrete is greater than 3,000 psi (21 N/mm²).

3.3.3 Bond to Concrete

Concrete Bond Failure

The force, F_C , which can be transferred in the bond interface between adhesive and hole wall increases linearly with embedment depth, as well as in proportion to the square root of the compressive strength times the hole diameter.




Design value of bond strength between HIT-HY 150 and concrete:

$F_C =$	34	•	l_d	•	$\sqrt{f'_c \cdot D}$
[lb]	[in.]				[psi] [in.]
$F_C =$	14	•	l_d	•	$\sqrt{f'_c \cdot D}$
[N]	[mm]				[N/mm ²] [mm]

D=hole diameter. See 2.3.

This equation allows for the performance of the concrete bond interface. It was developed by Professor Peter Marti of the Swiss Federal Institute of Technology (ETH), Zurich, based on a review of comprehensive test data.



Test Arrangement

This value controls when the installed development length is less than the basic development length and the compressive strength of concrete does not exceed 3,000 psi (21 N/mm²).

3.3.4 Basic Development Length

The basic development length is derived by setting

$$F_y \leq F_b$$

(rebar strength \leq adhesive bond strength)

$$\frac{\pi d b^2}{4} \cdot f_y \leq 2260 \cdot l_d \sqrt{d_b}$$

[in.] [psi] [in.] [in.]

$$l_d \geq \frac{f_y d_b^{3/2}}{2880}$$

[in.] [psi] [in.]

$$\frac{\pi d b^2}{4} \cdot f_y \leq 78 \cdot l_d \sqrt{d_b}$$

[mm] [N/mm²] [mm] [mm]

$$l_d \geq \frac{f_y \cdot d_b^{3/2}}{100}$$

[mm] [N/mm²][mm]

and

$$F_y \leq F_c$$

(rebar strength \leq concrete bond strength)

$$\frac{\pi d b^2}{4} \cdot f_y \leq 34 \cdot l_d \sqrt{f'_c \cdot D}$$

[in.] [psi] [in.] [psi] [in.]

$$l_d \geq \frac{f_y \cdot d_b^2}{43 \cdot \sqrt{f'_c \cdot D}}$$

[in.] [psi] [in.]

$$\frac{\pi d b^2}{4} \cdot f_y \leq 14 \cdot l_d \sqrt{f'_c \cdot D}$$

[mm] [N/mm²] [mm] [N/mm²] [mm]

$$l_d \geq \frac{f_y \cdot d_b^2}{18 \cdot \sqrt{f'_c \cdot D}}$$

[mm] [N/mm²] [mm]

As a result, the conservative basic development length useable for all concrete strengths is obtained as the maximum value of the two limiting embedment depths:

Basic Development Length

$$l_{db} = \text{MAX} \left\{ \frac{f_y \cdot d_b^{3/2}}{2880} ; \frac{f_y \cdot d_b^2}{43 \cdot \sqrt{f'_c \cdot D}} \right\}$$

[in.] [psi] [in.] [psi] [in.]

$$l_{db} = \text{MAX} \left\{ \frac{f_y \cdot d_b^{3/2}}{100} ; \frac{f_y \cdot d_b^2}{18 \cdot \sqrt{f'_c \cdot D}} \right\}$$

[mm] [N/mm²] [mm] [N/mm²] [mm]

Appendix 4. – List of Demolition Contractors Contacted

List of Contractors

Bluegrass Concrete Cutting, Inc
107 Mildred Street
P.O. Box 367
Greenville, AL 36037
800-734-2935

P.C.S. Inc.
P.O. Box 959
Hobe Sound, FL 22475
561-223-7393

Cutting Edge Services Corp.
807 Eight Mile Road
Cincinnati, OH 45255
513-388-0199

Independence Excavating
5720 Schaaf Road
Independence, OH 44131
800 524-DIRT

Kokosing Construction Co., Inc.
17531 Waterford Road
Fredericktown, OH 43019
740-694-6315

Waterjet Tech, Inc.
1803 Beltway Drive
St. Louis, MO 63114
314-428-6900

Tramac
26 Eastmans Road
Parsippany, NJ 07054
800-526-3837

DTI Demolition Technologies Incorporated
P.O. Box 427, 107 Mildred Street
Greenville, AL 36037
800-282-4384

Appendix 5. – Cost Estimates

PROJECT: Panama Canal Miter Gate Study
LOCATION: Panama Canal
COST LEVEL: December 2001

Est By: crc
Checked: pgb
E:\PANAMA\sillsup.xls]Chain Fender Sills
Filename: (2)
Date: 4/10/2002

Precast Panel Sill Replacement (Precision Demo)

Remove 2'-0" of existing sill, replace w/ 9" thick precast panels bolted thru to existing concrete, under grout and grout joints.

Refer to Plate No. 9
Quantities are per Sill

Item Description	Eng Quantity	Eng Unit	SI Quantity	SI Unit	English Unit Price	SI Unit Price	Amount	Cont	Total Cost
1 Concrete Removal (Precision)	165	cy	126	m3	\$1,200.00	\$1,570.00	\$198,000.00	25%	\$247,500.00
2 Precast Concrete Panels									
2a Concrete	17	cy	13	m3	\$800.00	\$1,050.00	\$13,600.00	25%	\$17,000.00
2b Reinforcing Steel	6,861	lbs	3112	kg	\$1.00	\$2.20	\$6,861.00	25%	\$8,576.25
2c Base Grout	77	cf	2.18	m3	\$12.00	\$420.00	\$924.00	25%	\$1,155.00
2d Joints Grout	2	cf	0.06	m3	\$15.00	\$500.00	\$30.00	25%	\$37.50
3 Seal Steel (ss)	2,785	lbs	1263	kg	\$12.00	\$26.50	\$33,423.96	25%	\$41,779.95
4 Misc Steel							\$0.00	25%	\$0.00
4a 1" Dia Anchor Bolts w/ nuts (4'-1.5" Long)	84	ea			\$250.00		\$21,000.00	25%	\$26,250.00
4b 1" Dia Threaded Rods w/ nuts & washers (2'-0" long)	24	ea			\$130.00		\$3,120.00	25%	\$3,900.00
4c Plates etc.	1,351	lbs	613	kg	\$10.00	\$22.00	\$13,510.00	25%	\$16,887.50
1/4" Dia Headed Concrete Achors (2-11/16" long)	24	ea			\$15.00		\$360.00	25%	\$450.00
							Total/Sill		\$363,536.20
							Total/Sill Rounded		\$364,000.00
							12 Sills Total		\$4,368,000.00
Dewaterings	4	ea			\$30,000.00		\$120,000.00	25%	\$150,000.00
Mob/Demob inside Panama	4	ea			\$15,000.00		\$60,000.00	25%	\$75,000.00
							Total		\$4,593,000.00

Total Construction Cost, Rounded **\$4,590,000**

Construction Duration per Dewatering

Dewatering	2 days
Demolition	5 days
Steel/Concrete Placement	2 days
Cleanup/Flooding	1 day
Total	10 days

PROJECT: Panama Canal Miter Gate Study
 LOCATION: Panama Canal
 COST LEVEL: December 2001

Est By: crc
 Checked: pgb
 EVAPANAMA[sillsup.xls]
 ls]Chain Fender Sills
 Filename: (2)
 Date: 4/10/2002

Cast-In-Place Miter Sills (Precision Demo)

Remove 2'-0" of existing sill, install dowels, reinforcing, and seal steel, place 10.5" of 4000 psi concrete.

Refer to Plate No. 6
 Quantities are per Sill

Item Description	Eng Quantity	Eng Unit	SI Quantity	SI Unit	English Unit Price	SI Unit Price	Amount	Cont	Total Cost
1 Concrete Removal (Precision)	165	cy	126	m3	\$1,200.00	\$1,570.00	\$198,000.00	25%	\$247,500.00
2 CIP Concrete							\$0.00	25%	\$0.00
2a Concrete	20	cy	15	m3	\$500.00	\$670.00	\$10,000.00	25%	\$12,500.00
2b Reinforcing Steel	1,756	lbs	797	kg	\$1.00	\$2.20	\$1,756.00	25%	\$2,195.00
3 Dowels									
3a Drill 7/8" Dia Holes	412	lf	126	m	\$45.00	\$147.00	\$18,540.00	25%	\$23,175.00
3b Dowels (#6 bar)	1,031	lbs	468	kg	\$2.50	\$5.50	\$2,576.88	25%	\$3,221.09
4 Seal Steel (SS)	4,481	lbs	2033	kg	\$12.00	\$26.50	\$53,774.40	25%	\$67,218.00
5 Misc Steel							\$0.00	25%	\$0.00
5a 1" Dia Anchor Bolts; Drill and Epoxy Grout - (3'-0" Long)	64	ea			\$150.00		\$9,600.00	25%	\$12,000.00
5b 1" Hvy Hex Nuts & Washers	128	ea			\$5.00		\$640.00	25%	\$800.00
							Total/Sill		\$368,609.09
							Total/Sill Rounded		\$369,000.00
							12 Sills Total		\$4,428,000.00
Dewaterings	4	ea			\$30,000.00		\$120,000.00	25%	\$150,000.00
Mob/Demob inside Panama	4	ea			\$15,000.00		\$60,000.00	25%	\$75,000.00
							Total		\$4,653,000.00

Total Construction Cost, Rounded \$4,650,000

Construction Duration per Dewatering
 Dewatering 2 days
 Demolition 5 days
 Steel/Concrete Placement 2-3 days
 Cleanup/Flooding 1 day
 Total 10 - 11 days

PROJECT: Panama Canal Miter Gate Study
LOCATION: Panama Canal
COST LEVEL: December 2001

Est By: crc
Checked: pgb
E:\PANAMA\sillsup.xls)Chain Fender Sills
Filename: (2)
Date: 4/10/2002

Cast-In-Place Sills (Alternative "A") (Precision Demo)

Remove 1'-0" from existing sill, sawcut 2'-0" wide x 1'-0" deep across sealing edge of sill, remove concrete and embedded steel, place new steel and concrete.

Refer to Plate No. 7
Quantities are per Sill.

<u>Item Description</u>	<u>Eng Quantity</u>	<u>Eng Unit</u>	<u>SI Quantity</u>	<u>SI Unit</u>	<u>English Unit Price</u>	<u>SI Unit Price</u>	<u>Amount</u>	<u>Cont</u>	<u>Total Cost</u>
1 Concrete Removal (Precision)									
1a Precision Removal	88	cy	67	m3	\$1,800.00	\$2,370.00	\$158,760.00	25%	\$198,450.00
1b Concrete Demo	9	cy	7	m3	\$1,000.00	\$1,300.00	\$9,100.00	30%	\$11,830.00
2 CIP Concrete									
2a Concrete	8	cy	6.1	m3	\$500.00	\$660.00	\$4,000.00	25%	\$5,000.00
2b Reinforcing Steel	1,756	lbs	797	kg	\$1.00	\$2.20	\$1,756.00	25%	\$2,195.00
3 Dowels									
3a Drill 7/8" Dia Holes	135	lf	41	m	\$45.00	\$148.00	\$6,075.00	25%	\$7,593.75
3b Dowels (#6 bar)	347	lbs	157	kg	\$2.50	\$5.50	\$867.50	25%	\$1,084.38
4 Seal Steel (SS)	4,481	lbs	2033	kg	\$12.00	\$26.50	\$53,774.40	25%	\$67,218.00
5 Misc Steel							\$0.00	25%	\$0.00
5a 1" Dia Anchor Bolts; Drill and Epoxy Grout - (3'-0" Long)	64	ea			\$150.00		\$9,600.00	25%	\$12,000.00
5b 1" Hvy Hex Nuts & Washers	128	ea			\$5.00		\$640.00	25%	\$800.00
							Total/Sill		\$306,171.13
							Total/Sill Rounded		\$306,000.00
							12 Sills Total		\$3,672,000.00
Dewaterings	4	ea			\$30,000.00		\$120,000.00	25%	\$150,000.00
Mob/Demob inside Panama	4	ea			\$15,000.00		\$60,000.00	25%	\$75,000.00
							Total		\$3,897,000.00

Total Construction Cost, Rounded **\$3,900,000**

Construction Duration per Dewatering

Dewatering	2 days
Demolition	4 days
Steel/Concrete Placement	1-2 days
Cleanup/Flooding	1 day
Total	8-9 days

PROJECT: Panama Canal Miter Gate Study
 LOCATION: Panama Canal
 COST LEVEL: December 2001

Est By: crc
 Checked: pgb
 EV/PANAMA\{sillsup.xls}\Chain Fender Sills
 Filename: (2)
 Date: 4/10/2002

Cast-In-Place Sills (Alternative "B") (Precision Demo)

Remove from existing sill, sawcut 1'-2" wide x 1'-0" deep across sealing surface edge of sill, remove existing concrete & embedded metals, place new steel and concrete.

Refer to Plate No. 8

Quantities are per Sill.

Item Description	Eng Quantity	Eng Unit	SI Quantity	SI Unit	English Unit Price	SI Unit Price	Amount	Cont	Total Cost
1 Concrete Removal									
1a Precision Removal	88	cy	67	m3	\$1,800.00	\$2,370.00	\$158,760.00	25%	\$198,450.00
1b Concrete Demo	5	cy	4	m3	\$1,200.00	\$1,590.00	\$6,360.00	30%	\$8,268.00
2 Concrete	5	cy	4	m3	\$500.00	\$660.00	\$2,650.00	25%	\$3,312.50
3 Dowels									
3a Drill 1-1/8" Dia Holes	135	lf	41	m	\$50.00	\$165.00	\$6,750.00	25%	\$8,437.50
3b Drill 1-3/8" Dia Holes	210	lf	64	m	\$60.00	\$197.00	\$12,600.00	25%	\$15,750.00
3c Dowels (#8 bar)	641	lbs	291	kg	\$1.00	\$2.20	\$640.80	25%	\$801.00
3d Dowels (#10 bar)	1,291	lbs	586	kg	\$1.00	\$2.20	\$1,290.90	25%	\$1,613.63
4 Seal Steel (SS)	6,930	lbs	3143	kg	\$12.00	\$26.50	\$83,160.00	25%	\$103,950.00
5 Misc Steel							\$0.00	25%	\$0.00
5 3/4" Dia Anchor Bolts w/double nut and washers (3.25' ea)	120	ea			\$100.00		\$12,000.00	25%	\$15,000.00
5b 3/4" Dia x 6" Long splice bolts w/ nuts and washers	24	ea			\$30.00		\$720.00	25%	\$900.00
							Total/Sill		\$356,482.63
							Total/Sill Rounded		\$360,000.00
							12 Sills Total		\$4,320,000.00
Dewaterings	4	ea			\$30,000.00		\$120,000.00	25%	\$150,000.00
Mob/Demob inside Panama	4	ea			\$15,000.00		\$60,000.00	25%	\$75,000.00
							Total		\$4,545,000.00

Total Construction Cost, Rounded \$4,550,000

Construction Duration per Dewatering
 Dewatering 2 days
 Demolition 4 days
 Steel/Concrete
 Placement 1-2 days
 Cleanup/Flooding 1 day
 Total 8-9 days

PROJECT: Panama Canal Miter Gate Study
 LOCATION: Panama Canal
 COST LEVEL: December 2001

Est By: crc
 Checked: pgb
 EV\PANAMA\sillsup.xls]Chain Fender Sills
 Filename: (2)
 Date: 4/10/2002

Precast Panel Sill Replacement (Conventional Concrete Demo)

Remove 2'-0" of existing sill, replace w/ 9" thick precast panels bolted thru to existing concrete, under grout and grout joints.

Refer to Plate No. 9
 Quantities are per Sill

Item Description	Eng Quantity	Eng Unit	SI Quantity	SI Unit	English Unit Price	SI Unit Price	Amount	Cont.	Total Cost
1 Concrete Removal	165	cy	126	m3	\$850.00	\$1,110.00	\$140,250.00	30%	\$182,325.00
2 Precast Concrete Panels									
2a Concrete	17	cy	13	m3	\$800.00	\$1,050.00	\$13,600.00	25%	\$17,000.00
2b Reinforcing Steel	6,861	lbs	3112	kg	\$1.00	\$2.20	\$6,861.00	25%	\$8,576.25
2c Base Grout	77	cf	2.18	m3	\$12.00	\$420.00	\$924.00	25%	\$1,155.00
2d Joints Grout	2	cf	0.06	m3	\$15.00	\$500.00	\$30.00	25%	\$37.50
3 Seal Steel (ss)	2,785	lbs	1263	kg	\$12.00	\$26.00	\$33,423.96	25%	\$41,779.95
4 Misc Steel							\$0.00	25%	\$0.00
4a 1" Dia Anchor Bolts w/ nuts (4'-1.5" Long)	84	ea			\$250.00		\$21,000.00	25%	\$26,250.00
4b 1" Dia Threaded Rods w/ nuts & washers (2'-0" long)	24	ea			\$130.00		\$3,120.00	25%	\$3,900.00
4c Plates etc.	1,351	lbs	613	kg	\$10.00	\$22.00	\$13,510.00	25%	\$16,887.50
4d 1/4" Dia Headed Concrete Achors (2-11/16" long)	24	ea			\$15.00		\$360.00	25%	\$450.00
							Total/Sill		\$298,361.20
							Total/Sill Rounded		\$298,000.00
							12 Sills Total		\$3,576,000.00
Dewaterings	4	ea			\$30,000.00		\$120,000.00	25%	\$150,000.00
Mob/Demob inside Panama	4	ea			\$10,000.00		\$40,000.00	25%	\$50,000.00
							Total		\$3,776,000.00

Total Construction Cost, Rounded **\$3,780,000**

Construction Duration per Dewatering
 Dewatering 2 days
 Demolition 4 days
 Steel/Concrete Placement 2 days
 Cleanup/Flooding 1 day
 Total 9 days

PROJECT: Panama Canal Miter Gate Study
LOCATION: Panama Canal
COST LEVEL: December 2001

Est By: crc
 Checked: pgb
 EV\PANAMA\{sillsup
 xls}\Chain Fender Sills
 Filename: (2)
 Date: 4/10/2002

Cast-In-Place Miter Sills (Conventional Concrete Demo)

Remove 2'-0" of existing sill, install dowels, reinforcing, and seal steel, place 10.5" of 4000 psi concrete.

Refer to Plate No. 6
 Quantities are per Sill

<u>Item Description</u>	<u>Eng</u> <u>Quantity</u>	<u>Eng</u> <u>Unit</u>	<u>SI</u> <u>Quantity</u>	<u>SI</u> <u>Unit</u>	<u>English</u> <u>Unit Price</u>	<u>SI</u> <u>Unit Price</u>	<u>Amount</u>	<u>Cont</u>	<u>Total Cost</u>
1 Concrete Removal	165	cy	126	m3	\$850.00	\$1,110.00	\$140,250.00	30%	\$182,325.00
2 CIP Concrete							\$0.00	25%	\$0.00
2a Concrete	20	cy	15	m3	\$500.00	\$670.00	\$10,000.00	25%	\$12,500.00
2b Reinforcing Steel	1,756	lbs	797	kg	\$1.00	\$2.20	\$1,756.00	25%	\$2,195.00
3 Dowels									
3a Drill 7/8" Dia Holes	412	lf	126	m	\$45.00	\$147.00	\$18,540.00	25%	\$23,175.00
3b Dowels (#6 bar)	1,031	lbs	468	kg	\$2.50	\$5.50	\$2,576.88	25%	\$3,221.09
4 Seal Steel (SS)	4,481	lbs	2033	kg	\$12.00	\$26.50	\$53,774.40	25%	\$67,218.00
5 Misc Steel							\$0.00	25%	\$0.00
5a 1" Dia Anchor Bolts; Drill and Epoxy Grout - (3'-0" Long)	64	ea			\$150.00		\$9,600.00	25%	\$12,000.00
5b 1" Hvy Hex Nuts & Washers	128	ea			\$5.00		\$640.00	25%	\$800.00
							Total/Sill		\$303,434.09
							Total/Sill Rounded		\$303,000.00
							12 Sills Total		\$3,636,000.00
Dewaterings	4	ea			\$30,000.00		\$120,000.00	25%	\$150,000.00
Mob/Demob inside Panama	4	ea			\$10,000.00		\$40,000.00	25%	\$50,000.00
							Total		\$3,836,000.00

Total Construction Cost, Rounded **\$3,840,000**

Construction Duration per Dewatering
 Dewatering 2 days
 Demolition 4 days
 Steel/Concrete Placement 2-3 days
 Cleanup/Flooding 1 day
 Total 9-10 days

PROJECT: Panama Canal Miter Gate Study
 LOCATION: Panama Canal
 COST LEVEL: December 2001

Est By: crc
 Checked: pgb
 Filename: E:\PANAMA\sillsup.xls]Chain Fender Sills (2)
 Date: 4/10/2002

Cast-In-Place Sills (Alternative "A") (Conventional Concrete Demo)

Remove 1'-0" from existing sill, sawcut 2'-0" wide x 1'-0" deep across sealing edge of sill, remove concrete and embedded steel, place new steel and concrete.

Refer to Plate No. 7
 Quantities are per Sill.

Item Description	Eng Quantity	Eng Unit	SI Quantity	SI Unit	English Unit Price	SI Unit Price	Amount	Cont	Total Cost
1 Concrete Removal									
1a Concrete Demo	88	cy	67	m3	\$850.00	\$1,120.00	\$74,970.00	35%	\$101,209.50
1b Concrete Demo	9	cy	7	m3	\$1,000.00	\$1,300.00	\$9,100.00	35%	\$12,285.00
2 CIP Concrete									
2a Concrete	8	cy	6.1	m3	\$500.00	\$660.00	\$4,000.00	25%	\$5,000.00
2b Reinforcing Steel	1,756	lbs	797	kg	\$1.00	\$2.20	\$1,756.00	25%	\$2,195.00
3 Dowels									
3a Drill 7/8" Dia Holes	135	lf	41	m	\$45.00	\$148.00	\$6,075.00	25%	\$7,593.75
3b Dowels (#6 bar)	347	lbs	157	kg	\$1.00	\$2.20	\$347.00	25%	\$433.75
4 Seal Steel (SS)	4,481	lbs	2033	kg	\$12.00	\$26.50	\$53,774.40	25%	\$67,218.00
5 Misc Steel							\$0.00	25%	\$0.00
5a 1" Dia Anchor Bolts; Drill and Epoxy Grout - (3'-0" Long)	64	ea			\$150.00		\$9,600.00	25%	\$12,000.00
5b 1" Hvy Hex Nuts & Washers	128	ea			\$5.00		\$640.00	25%	\$800.00
							Total/Sill		\$208,735.00
							Total/Sill Rounded		\$209,000.00
							12 Sills Total		\$2,508,000.00
Dewaterings	4	ea			\$30,000.00		\$120,000.00	25%	\$150,000.00
Mob/Demob inside Panama	4	ea			\$10,000.00		\$40,000.00	25%	\$50,000.00
							Total		\$2,708,000.00

Total Construction Cost, Rounded

\$2,710,000

Construction Duration per Dewatering

Dewatering	2 days
Demolition	3 days
Steel/Concrete Placement	2 days
Cleanup/Flooding	1 day
Total	8 days

PROJECT: Panama Canal Miter Gate Study
 LOCATION: Panama Canal
 COST LEVEL: December 2001

Est By: crc
 Checked: pgb
 EVAPANAMA\{sillsup.xls}\Chain Fender Sills
 Filename: (2)
 Date: 4/10/2002

Cast-In-Place Sills (Alternative "B") (Conventional Concrete Demo)

Remove 1'-0" from existing sill, sawcut 1'-2" wide x 1'-0" deep across sealing surface edge of sill, remove existing concrete & embedded metals, place new steel and concrete.

Refer to Plate No. 8
 Quantities are per Sill.

Item Description	Eng Quantity	Eng Unit	SI Quantity	SI Unit	English Unit Price	SI Unit Price	Amount	Cont	Total Cost
1 Concrete Removal									
1a Concrete Demo	88	cy	67	m3	\$850.00	\$1,120.00	\$74,970.00	35%	\$101,209.50
1b Concrete Demo	5	cy	4	m3	\$1,200.00	\$1,590.00	\$6,360.00	35%	\$8,586.00
2 Concrete	5	cy	4	m3	\$500.00	\$660.00	\$2,650.00	25%	\$3,312.50
3 Dowels									
3a Drill 1-1/8" Dia Holes	135	lf	41	m	\$50.00	\$165.00	\$6,750.00	25%	\$8,437.50
3b Drill 1-3/8" Dia Holes	210	lf	64	m	\$60.00	\$197.00	\$12,600.00	25%	\$15,750.00
3c Dowels (#8 bar)	641	lbs	291	kg	\$1.00	\$2.20	\$640.80	25%	\$801.00
3d Dowels (#10 bar)	1,291	lbs	586	kg	\$1.00	\$2.20	\$1,290.90	25%	\$1,613.63
4 Seal Steel (SS)	6,930	lbs	3143	kg	\$12.00	\$26.50	\$83,160.00	25%	\$103,950.00
5 Misc Steel							\$0.00	25%	\$0.00
5a 3/4" Dia Anchor Bolts w/double nut and washers (3.25' ea)	120	ea			\$100.00		\$12,000.00	25%	\$15,000.00
5b 3/4" Dia x 6" Long splice bolts w/ nuts and washers	24	ea			\$30.00		\$720.00	25%	\$900.00
							Total/Sill		\$259,560.13
							Total/Sill Rounded		\$260,000.00
							12 Sills Total		\$3,120,000.00
Dewaterings	4	ea			\$30,000.00		\$120,000.00	25%	\$150,000.00
Mob/Demob inside Panama	4	ea			\$10,000.00		\$40,000.00	25%	\$50,000.00
							Total		\$3,320,000.00

Total Construction Cost, Rounded **\$3,320,000**

Construction Duration per Dewatering
 Dewatering 2 days
 Demolition 3 days
 Steel/Concrete Placement 2 days
 Cleanup/Flooding 1 day
 Total 8 days

PROJECT: Panama Canal Miter Gate Study
 LOCATION: Panama Canal
 COST LEVEL: December 2001

Est By: crc
 Checked: pgb
 O:\ED\EC-
 EV\PANAMA\sillsu
 p.xls]Chain Fender
 Filename: Sills (2)
 Date: 4/10/2002

Miter Gate Bottom Extension

Refer to Plate No. 10
 Quantities are per set of gate leaves.

Item Description	Eng Quantity	Eng Unit	SI Quantity	SI Unit	English Unit Price	SI Unit Price	Amount	Cont	Total Cost
1 Mob/Demob	1	ls			\$3,000.00		\$3,000.00	25%	\$3,750.00
2 Edge Bulb Seal	123	lf	37	m	\$25.00	\$83.00	\$3,075.00	25%	\$3,843.75
3 2-3/4" x 3/4" St Stl Clamping Bar	864	lbs	392	kg	\$7.00	\$15.40	\$6,044.50	25%	\$7,555.63
4 Angle (5x3.5x.5)	1,673	lbs	759	kg	\$4.00	\$8.80	\$6,692.00	25%	\$8,365.00
5 3/4" Dia x 6" long St. Stl Bolts w/ nuts and washers	60	ea			\$25.00		\$1,500.00	25%	\$1,875.00
6 11/16" Single V-Groove (Field Weld)	123	lf	37	m	\$50.00	\$166.00	\$6,150.00	25%	\$7,687.50
7 11/16" Single V-Groove (Shop Weld	123	lf	37	m	\$35.00	\$116.00	\$4,305.00	25%	\$5,381.25
Bar Stock (2-3/4" x 11/16")	791	lbs	359	kg	\$4.00	\$8.80	\$3,164.00	25%	\$3,955.00
9 Bar Stock (3" x 3/4")	942	lbs	427	kg	\$4.00	\$8.80	\$3,768.00	25%	\$4,710.00
10 11/16" Plate (.5 SF/plate)	815	lbs	370	kg	\$6.00	\$13.20	\$4,890.00	25%	\$6,112.50
11 1/4" Fillet Weld (Field Weld)	84	lbs	38	kg	\$12.00	\$26.50	\$1,008.00	25%	\$1,260.00
12 1/4" Fillet Weld (Shop Weld)	24	lbs	11	kg	\$8.00	\$17.50	\$192.00	25%	\$240.00
13 2" x 1/2" Bar	247	lbs	112	kg	\$4.00	\$8.80	\$986.00	25%	\$1,232.50
14 Metalize	1	ls			\$5,000.00		\$5,000.00	25%	\$6,250.00
15 Misc Field Work (handling/assembling)	1	ls			\$8,000.00		\$8,000.00	25%	\$10,000.00
							Total/Set of leaves		\$72,218.13
							Total/Set Rounded		\$72,000.00
							12 Sets Total		\$864,000.00
							Total		\$864,000.00

Total Construction Cost, Rounded

\$865,000

PROJECT: Panama Canal Miter Gate Study
LOCATION: Panama Canal
COST LEVEL: December 2001

Est By: crc
 Checked: pgb
 O:\ED\EC-
 EV\PANAMA[sillsu
 p.xls]Chain Fender
 Filename: Sills (2)
 Date: 4/10/2002

Emergency Dam Sill Demolition

Miraflores Locks

Quantities are per sill. Total of two sills, one per lane.
 A separate dewatering will have to be done to allow this work.

<u>Item Description</u>	<u>Eng Quantity</u>	<u>Eng Unit</u>	<u>SI Quantity</u>	<u>SI Unit</u>	<u>English Unit Price</u>	<u>SI Unit Price</u>	<u>Amount</u>	<u>Cont</u>	<u>Total Cost</u>
1 Mob/Demob	1	ls			\$5,000.00		\$5,000.00	25%	\$6,250.00
2 Dewater	1	Job			\$30,000.00		\$30,000.00	25%	\$37,500.00
3 Concrete Demolition	178	cy	136	m3	\$850.00	\$1,110.00	\$151,470.00	25%	\$189,337.50
							Total per sill		\$233,087.50
							Total per sill rounded		\$233,000.00
							2 sills total		\$466,000.00
							Total		\$466,000.00

Total Construction Cost, Rounded

\$470,000

PROJECT: Panama Canal Miter Gate Study
LOCATION: Panama Canal
COST LEVEL: December 2001

Est By: crc
 Checked: pgb
 O:\ED\EC-
 EVAPANAMA\sillsu
 p.xls]Chain Fender
 Filename: Sills (2)
 Date: 4/10/2002

Chain Fender Sills

Pedro Miguel - Miraflores Lake Side
 Quantities are per sill. Total of two sills, one per lane.
 This work will be done in the wet.

	<u>Item Description</u>	<u>Eng</u> <u>Quantity</u>	<u>Eng</u> <u>Unit</u>	<u>SI</u> <u>Quantity</u>	<u>SI</u> <u>Unit</u>	<u>English</u> <u>Unit Price</u>	<u>SI</u> <u>Unit Price</u>	<u>Amount</u>	<u>Cont</u>	<u>Total Cost</u>
1	Mob/Demob	1	ls			\$15,000.00		\$15,000.00	25%	\$18,750.00
2	Concrete Demolition (In the wet)	51	cy	39	m3	\$2,200.00	\$2,880.00	\$112,200.00	25%	\$140,250.00

Total per sill \$159,000.00
 Total per sill rounded \$159,000.00
 2 sills total \$318,000.00

Total \$318,000.00

Total Construction Cost, Rounded \$320,000

PROJECT: Panama Canal Miter Gate Study
LOCATION: Panama Canal
COST LEVEL: December 2001

Est By: crc
 Checked: pgb
 O:\ED\EC-
 EV\PANAMA\sillsu
 p.xls]Chain Fender
 Filename: Sills (2)
 Date: 4/10/2002

Chain Fender Sills: Between Miter Gates

Pedro Miguel - Between Miter Gates 54 - 57 and 58 - 61
 Quantities are per sill. Total of two sills, one per lane.
 Concrete Demolition to be concurrent with other work.
 Chamber dewatering covered in the cost of this other lock work.

<u>Item Description</u>	<u>Eng</u> <u>Quantity</u>	<u>Eng</u> <u>Unit</u>	<u>SI</u> <u>Quantity</u>	<u>SI</u> <u>Unit</u>	<u>English</u> <u>Unit Price</u>	<u>SI</u> <u>Unit Price</u>	<u>Amount</u>	<u>Cont</u>	<u>Total Cost</u>
1 Mob/Demob	1	ls			\$5,000.00		\$5,000.00	25%	\$6,250.00
2 Concrete Demolition	43	cy	33	m3	\$850.00	\$1,100.00	\$36,380.00	25%	\$45,475.00

Total per sill \$51,725.00
 Total per sill rounded \$52,000.00
 2 sills total \$104,000.00

Total \$104,000.00

Total Construction Cost, Rounded \$105,000

Appendix 6. – Quantities



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 1 of 1 Pages

Computed by JET Date 12-9-01

Subject PALAMA MITER GATE STUDY

Checked by Date

Computation MITER GATE EXTENSION (PER SET OF GATE LEAF)

EDGE BULB SEAL (SIMILAR OR EQUAL TO BUCKHORN RUBBER PRODUCTS, INC.,
MOLD # 2990)

$$61.5 \text{ LF PER GATE LEAF} \times 2 \text{ LEAFS} = \underline{123 \text{ LF}}$$

$$2\frac{3}{4}'' \times \frac{3}{4}'' \text{ ST. STL. CLAMPING BAR} \rightarrow 123 \text{ LF} \times 7.02 \frac{\text{#}}{\text{LF}} = \underline{863.5 \text{ LBS}}$$

$$\text{ANGLE} \rightarrow L 5 \times 3\frac{1}{2} \times \frac{1}{2}'' \Rightarrow 123 \text{ LF} \times 13.6 \frac{\text{#}}{\text{LF}} = \underline{1,673 \text{ LBS}}$$

60 - $\frac{3}{4}'' \phi \times 6''$ LONG ST. STL. BOLTS w/ NUTS & WASHERS

123 LF OF $\frac{1}{16}''$ SINGLE V-GROOVE \rightarrow FIELD WELD

123 LF " " " " " \rightarrow SHOP WELD

$$123 \text{ LF OF } 2\frac{3}{4}'' \times \frac{1}{16}'' \text{ BAR STOCK} \Rightarrow 123 \times 6.43 \frac{\text{#}}{\text{LF}} = \underline{791 \text{ LBS}}$$

$$123 \text{ LF OF } 3'' \times \frac{3}{4}'' \text{ " " " " " } \rightarrow 123 \times 7.66 \frac{\text{#}}{\text{LF}} = \underline{942 \text{ LBS}}$$


$$\frac{1}{16}'' \text{ PLATE} \Rightarrow .5 \text{ SF/PL} \times 58 \text{ EA (29/LEAF)} = 29 \text{ SF} \times 28.1 \frac{\text{#}}{\text{SF}} = \underline{815 \text{ LBS}}$$

$$\frac{1}{4}'' \text{ FILLET WELD} \Rightarrow 3.2 \text{ LF (SHOP) PER PL} \times 58 \text{ EA} = \underline{186 \text{ LF}}$$

$$3.2 \text{ LF (FIELD) PER PL} \times 58 \text{ EA} = \underline{186 \text{ LF}}$$

$$2'' \times \frac{1}{2}'' \text{ BAR} \Rightarrow 1.25 \text{ LF/PL} \times 58 \text{ PL'S} = 72.5 \text{ LF} \times 3.4 \frac{\text{#}}{\text{LF}} = \underline{246.5 \text{ LBS}}$$

* METALIZE ALL EXPOSED SURFACES (EXCLUDING ST. ST. & BULB SEAL)



DETAIL 1
 SCALE: 3"=1'-0"



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 1 of 2 Pages

Computed by GET Date 11-29-01

Checked by Date

Subject PANAMA CANAL - MITER GATE STUDY

Computation LAST-IN-PLACE MITER SILL (PER SILL QUANTITIES)

PROCEDURE = REMOVE 2'-0" OF EXISTING SILL, INSTALL DOWELS, REINFORCING, AND SEAL STEEL, PLACE 10 1/2" ± (4,000 PSI) CONCRETE.



REMOVAL = $\frac{\pi}{4} \times (\text{SEE REMOVAL DRAWINGS @ BACK OF PACKAGE})$

$$2346.5131 \text{ SF (EXISTING)} \times 2'-0" = 4,693 \text{ SF OR}$$

$$\text{ACTUAL} \Rightarrow 2346.5131 \text{ SF} \times 1'-10\frac{1}{2}" = 4400 \text{ CF OR } 179 \text{ CF/SILL}$$

DOWELS: #6 BENT BARS - 183 REQUIRED, EPOXY GROUT-IN

$$\text{DRILL } 183 - \frac{7}{8}" \phi \text{ HOLES @ } 2.25 \text{ LF EACH} = 411.75 \text{ LF/SILL}$$

$$183 - \#6 \text{ DOWELS @ } 5.6325 \text{ \# / DOWEL} = 1,030.75 \text{ LBS/SILL}$$

REINFORCING: #6 STEEL @ 1'-0" C-C

2 BARS @ 3.4'	=	6.8'
2 " @ 4.2'	=	8.4'
10 " @ 60.9'	=	609.0'
2 " @ 4.3'	=	8.6'
2 " @ 2.2'	=	4.4'
2 " @ 5.0'	=	10.0'
116 " @ 4.5'	=	522.0'

$$1,169.2 \text{ LF @ } 1.502 \text{ \# / LF} = 1,756 \text{ LBS/SILL}$$

SILL SEAL STEEL =

64 - 1" φ BOLTS → DRILL & EPOXY GROUT (3'-0" x 1 1/8" φ) x 64

$$128 - 1" \text{ HWY. HEX NUTS \& WASHERS} = 192 \text{ LF}$$

122.5 LF - 8" x 1/2" THICK PL (ST. STL.) } SHOP WELD TOGETHER TO
 122.5 LF - 12" x 1/2" THICK PL (ST. STL.) } FORM 8" x 12" ANGLE - 1/2" SINGLE BEVEL WELD

$$122.5 \text{ LF} \times 13.6 \text{ \# / LF} = 1,666 \text{ LBS.}$$

$$122.5 \text{ LF} \times 20.4 \text{ \# / LF} = 2,499 \text{ LBS.}$$



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 2 of 2 Pages

Computed by GET Date 11-29-01

Checked by _____ Date _____

Subject PANAMA CANAL MITER GATE STUDY

Computation CAST-IN-PLACE MITER SILL

SILL SEAL (CONT'D)

(ST. STL)

62 - 6" x 6" x 1/2" THICK GUSSET PL^S (1241 SF EACH)

WELD GUSSET PL^S TO 8" x 12" ANGLE = 2 LF/PL x 62 GUSSET PL^S

→ 312 LF of 6" x 1/2" PL

= 124 LF of 5/16" FILLET WELD


312 LF x 10.2 #/LF = 3162 LBS

CONCRETE =

612 x 1294 SF x 10.5" = 535.61 CF or 19.84 cy


612 x 1294 SF x 1'-0" = 612.1294 CF or 22.67 cy

+ 25 cy TOTAL/SILL



TYPICAL SECTION

C.I.P. SILL REPLACEMENT



12-10-01

RET

REMOVALS (EA SILL)

<u>' CATION</u>	<u>SF</u>	<u>2'-0"</u>	<u>ALT "A" (+9)</u>	<u>ALT "B" (+5)</u>
2. ATUNE 13-16	2346.5	174 cy	96 cy	92 cy
17-20	2346.5	174 cy	96 cy	92 cy
P.M. S ^{SA} 57	1470.17	109 cy	64 cy	60 cy
58-61	1971.73	146 cy	82 cy	78 cy
2-65 68-69	2616.14	194 cy	106 cy	102 cy
66-69	2524.5	187 cy	94 cy	90 cy
	<u>13,278.54</u>	<u>984 cy</u>	<u>538 cy</u>	<u>514 cy</u>
<u>AVG'S</u>	2,212.6 sf	164 cy	90 cy	86 cy



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 1 of 2 Pages

Computed by JET Date 12-3-01

Subject PANAMA MITEN GATE STUDY

Checked by Date

Computation CAST-IN-PLACE SILL - ALTERNATIVE "A"

PROCEDURE = DIAMOND-WIRE SAWCUT 1'-0" FROM EXISTING SILL,
SAWCUT 2'-0" WIDE x 1'-0" DEEP ALONG SEALING EDGES OF
SILL, REMOVE CONCRETE & EMBEDDED STEEL, PLACE BACK
STEEL & CONCRETE

REMOVAL = $2381.14 \text{ SF} \times 1'-0" = 2381.14 \text{ CF} \text{ OR } 88.2 \text{ CY}$

$2'-0" \text{ WIDE} \times 1'-0" \text{ DEEP} \times 123.0 \text{ LF} = 246 \text{ CF} = 9.1 \text{ CY}$

* (SEE REMOVAL BROKDOWN @ BACK OF PACKAGE) 97.3 CY

DOWNERS:

60 - #6 BENT BARS @ 3.85 LF EA. x 1.502 #/LF = 347 LBS

DRILL 60 - 1/8" ϕ HOLES, GROUT/EPoxy IN

REINFORCEMENT = #6 @ 12" C-C

124 - 1.5' BARS =
4 @ 61.21' =

SILL SEAL STEEL

64 - 1" ϕ BOLTS \rightarrow DRILL & EPOXY GROUT (3'-0" x 1 1/2" ϕ) x LF = 192 LF

128 - 1" Hvy. Hex NUTS & WASHERS

122.5 LF - 8" x 1/2" THICK PL (ST. STL.) } SHOP WELD TO FORM 8" x 12" ANGLES
122.5 LF - 12" x 1/2" THICK PL (" ") } USE 1/2" SINGLE BEVEL

$\rightarrow 122.5 \times 13.6 \text{ #/LF} = 1,666 \text{ LBS.}$

$\rightarrow 122.5 \times 20.4 \text{ #/LF} = 2,499 \text{ LBS.}$

62 - 6" x 6" x 1/2" GUSSET PL (ST. STL.) - 0.1241 SF EA.
31 LF OF 6" x 1/2" PL $\Rightarrow 31 \times 10.12 \text{ #/LF} = 316.2 \text{ LBS.}$

WELD GUSSET PL TO 8" x 12" ANGLES = 2 LF/PL x 62 PL = 124 LF
OF 5/16" FILLER WELD



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 2 of 2 Pages

Computed by JET Date 12-4-51


Checked by _____ Date _____

Subject PANAMA MITEN GATE STUDY

Computation CAST-IN-PLACE SILL - ALTERNATIVE "A"

CONCRETE

$$245,967.5 \text{ SF} \times 16\frac{1}{2}'' \text{ THICK} = 215,72 \text{ CF} \text{ OR } \underline{\underline{8 \text{ CY}}}$$



TYPICAL SECTION
C.I.P. SILL REPLACEMENT,
ALTERNATIVE "A"

12-10-01

RET

REMOVALS (EA SILL)

<u>STATION</u>	<u>SF</u>	<u>2'-0"</u>	<u>ALT "A" (+9)</u>	<u>ALT "B" (+5)</u>
STATION 13-16	2346.5	174 cy	96 cy	92 cy
17-20	2346.5	174 cy	96 cy	92 cy
P.M. 54 54-57	1470.17	109 cy	64 cy	60 cy
58-61	1971.73	146 cy	82 cy	78 cy
62-65 68	2616.14	194 cy	106 cy	102 cy
66-69	2524.5	187 cy	94 cy	90 cy
	<u>13,275.54</u>	984 cy	538 cy	514 cy
<u>AVG' =</u>	2,212.6 sf	164 cy	90 cy	86 cy



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 1 of 2 Pages

Subject PANAMA CANAL - MITER GATE STUDY

Computed by GET Date 12-05-01

Computation CAST-IN-PLACE MITER SILL - ALTERNATIVE "B"

Checked by Date

PROCEDURE: DIAMOND-WIRE SAWCUT 1'-0" FROM EXISTING SILL, SAWCUT 1'-2" WIDE x 1'-0" DEEP ACROSS SEALING SURFACE EDGE OF SILL, REMOVE EXISTING CONCRETE & EMBEDDED METALS, PLACE BACK STEEL & CONCRETE

REMOVAL: $2381.14 SF \times 1'-0" = 2381.14 CF$ on 88.2 cy
 $1'-2" \text{ WIDE} \times 1'-0" \text{ DEEP} \times 123 LF = 143.5 CF$ on 5.3 cy
 * (500 REMOVAL BURIED DOWN @ BACK OF PACKAGES) = 94 cy

DOWELS: 60 - #8 DOWELS @ 4'-0" = 240 LF @ 267 #/FT = 6408 #
 60 - #10 DOWELS @ 5'-0" = 300 LF @ 4303 #/FT = 12909 #
1932 LBS.

DRILL & GROUT:
 } 60 - 1 1/8" ϕ x 2.25 FT = 135 LF
 } 60 - 1 3/8" ϕ x 3.5 FT = 210 LF

REINFORCING: NONE - DOWELS & ANCHORS ONLY

SILL SERIAL STEEL

ANGLE: $(8 \times 6 \times 3/4") \times 33.8 \#/FT \times 123 LF = 4,157 LBS$

$(6 \times 4 \times 7/16") \times 14.3 \#/FT \times 4 1/2" \times 60 = 321.75 \#$

$(5 \times 3 1/2 \times 7/16") \times 12.0 \#/FT \times 4 1/2" \times 60 = 270.0 \#$

ST. STEEL: $(5 9/8" \times 3/8") \times 123 LF \times 7.18 \#/FT = 883.14 LBS$

11 11 " $(7 3/8" \times 3/8") \times 123 LF \times 9.75 \#/FT = 1199.25 LBS.$

GUSSET @ SPICES \Rightarrow DEPENDS ON HOW MANY SPICES;
 ASSUMES EVERY 10' SPICE = 12 SPICES

4 1/2" x 6 1/2" x 1/2" PL x 24 PLATES =

$(4 1/2" \times 1/2") (7.66 \#/FT) (.5417 CF) \times 24 = 99.6 LBS$



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 2 of 2 Pages

Computed by *JET* Date 12-5-01

Subject *PANAMA MITER GATE STUDY*

Checked by _____ Date _____

Computation *CAST-IN-PLACE SILLS - ALTERNATIVE "B"*

SILL SEAL STEEL CONT'D

WELD → 123 LF × 3 of $\frac{3}{8}$ " ST. STL. WELD = 369 LF
 12 SPICES @ 1.3 LF/SPICE × $\frac{1}{4}$ " = 15.6 LF of $\frac{1}{4}$ " V-GROOVE ST. STL. WELD

12 - $\frac{1}{4}$ " FILLET @ 11" EA = 11 LF

12 - $\frac{1}{4}$ " SINGLE BEVEL @ 11" EA = 11 LF

$\frac{1}{4}$ " FILLET WELD (7018 ROD) FOR ADJUSTING ANGLES TO SEAL ANGLE



5 × $3\frac{1}{2}$ " × = 16" EA × 60 = 80 LF

6" × 4" × = 18" EA × 60 = 90 LF

120 - $\frac{3}{4}$ " ϕ ANCHOR BOLTS w/ DOUBLE NUT & WASHERS, 3.25' EA


24 - $\frac{3}{16}$ " ϕ × 6" LONG SPICER BOLTS w/ NUTS & WASHERS

CONCRETE 143.4 SF × 1'-0" DEEP = 143.4 CF = 5.3 CY



ELEVATION

SCALE: 1/2" = 1'-0"





7/8" SLOTTED
HOLES (TYP)

2'-0"

PLAN

SCALE: 1/2" = 1'-0"



12-10-01

FET

REMOVALS (EA SILL)

<u>LOCATION</u>	<u>SF</u>	<u>2'-0"</u>	<u>ALT "A" (+9)</u>	<u>ALT "B" (+5)</u>
STATION 13-16	2346.5	174 cy	96 cy	92 cy
17-20	2346.5	174 cy	96 cy	92 cy
O.M. S ^S 51-57	1470.17	109 cy	64 cy	60 cy
58-61	1971.73	146 cy	82 cy	78 cy
2-65 62-69	2616.14	194 cy	106 cy	102 cy
66-69	2524.5	187 cy	94 cy	90 cy
	<u>13,275.54</u>	<u>984 cy</u>	<u>538 cy</u>	<u>514 cy</u>
<u>AVG'z</u>	2,212.6 SF	164 cy	90 cy	86 cy



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 1 of 3 Pages
Computed by JET Date 12-3-01
Checked by - Date

Subject PANAMA CANAL MITEN GATE STUDY
Computation PRECAST PANEL SILL REPLACEMENT (PER SILL QUANTITIES)

PROCEDURE: REMOVE 2'-0" OF EXISTING SILL, REPLACE W/ 9" THICK PRECAST PANELS BOLTED THRU TO EXISTING CONCRETE, UNDER GROUT & GROUT JOINTS.

REMOVAL: $2386.14 \text{ SF/SILL} \times 2'-0" = 4,772.28 \text{ CF OR } 176 \text{ CY}$

OPTION: DIAMOND WIRE SAW THAN 3" COARS

$2386.14 \text{ SF/SILL} \times 1'-10\frac{1}{2}" = 4,464.64 \text{ CF OR } 165 \text{ CY}$

* (SEE REMOVAL BREAKDOWN @ BACK OF PACKAGE)

PRECAST PANELS: DOUBLE-MAT OF #6 REINFORCING, LEVELING DEVICES, 1" ϕ ANCHORS, 9" THICK CONCRETE W/KEYS @ ENDS, ST. STEEL CHANNEL SEAL SURFACE

4 - 20'-0" PANELS } PER SILL
2 - 21'-4" PANELS }

REINFORCEMENT

20'-0" PANELS

10 BARS @ 19.441' = 194.41 FT x 1.502 #/FT = 292 LBS
36 BARS @ 5.0312' = 181.12 FT x 1.502 #/FT = 272 LBS

376 FT/PANEL 564 LBS/PANEL

x 4 PANELS x 4 PANELS

1,504 FT 2,256 LBS

21'-4" PANELS

10 BARS @ 20.7696' = 207.70 FT x 1.502 #/FT = 312 LBS
38 BARS @ 5.0312' = 191.19 FT x 1.502 #/FT = 287 LBS

398.89 FT 599 LBS

x 2 PANELS x 2 PANELS

798 FT 1,198 LBS

2,302 FT/SILL

3,454 LBS/SILL

12-10-10
FEET

400 REINFORCING @
W/ ANCHORS - 6'-4'-0"
ANCHORS
274 x 34 ANCHORS x 1.502 #/FT
= 3406.54 LBS
= 3,407 LBS



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page **2** of **3** Pages
 Computed by **GET** Date **12-3-01**
 Checked by _____ Date _____

Subject **PANAMA CANAL MITEN GATE STUDY**
 Computation **PRECAST PANEL SILL REPLACEMENT (PER SILL QUANTITIES)**

SEAL STEEL = **C9x20 STAINLESS STEEL, 3/8" THICK STRAPS**

CHANNEL
122'-8" of C9x20 ST. STL @ 20#/LF = 2,453.33 #/SILL

Anchor STRAPS

2" WIDE x 3/8" THICK x 1'-8" LONG

78 STRAPS x 2.55 LBS/LF x 1.667 FT = 332 LBS/SILL

46 LF of 1/4" FILLET WELD

MISC. STEEL : **1" φ ANCHORS, 1" φ THREADED BARN, 1/2" THICK PLATE, 1" I.P., THREADED PIPE SLEEVES, 1/4" FILLET WELD, NELSON STUDS**

84 - 1" φ ANCHOR BOLTS w/ NUTS & WASHERS (4'-1 1/2" LONG EACH)

24 - 1" φ THREADED ROD w/ NUTS & WASHERS (2'-0" LONG EACH)

11 LF of 1 1/4" ID THREADED PIPE (X-STRINGS) = 33 LBS

4" φ PLATE x 1/2" x 24 OR = 163 LBS

12" SQUARE A x 1/2" x 24 OR = 490 LBS

~~6 3/4" SQUARE A x 1/2" x 24 OR = 966 LBS~~

3593 x 4 = 1,4372 LF

2916 x 4 = 1,1664 LF

2083 x 4 = 8332 LF

3.4365 say 3.5 LF/emb/67 LBS of 1/2" A (GRADE 50)

294 LF x 20.4 #/LF = 5998 LBS

TOTAL = 6651 L

24 - 1/4" φ HEADED C.W. ANCHORS (NELSON STUDS), 2'-1/16" LONG EA.

125 LF of 1/4" FILLET WELD

12-10-01
GET
Anchor
EMBED
DETAIL ①



US Army Corps
of Engineers
Ohio River Division

COMPUTATION SHEET

Page 3 of 3 Pages

Computed by GET Date 12-3-01

Checked by _____ Date _____

Subject PALAMA MITON GATE STUDY

Computation PRECAST PANEL SILL REPLACEMENT

CONCRETE & GROUT

CONCRETE

$$4 \text{ PANELS @ } 20' \times 5' \times 9" \text{ THICK} = 300 \text{ CF} = 11.11 \text{ CY}$$

$$2 \text{ PANELS @ } 21'4" \times 5' \times 9" \text{ THICK} = 160 \text{ CF} = 5.93 \text{ CY}$$

$$\underline{\underline{17 \text{ CY} / \text{SILL}}}$$

BASE GROUT

$$614.92 \text{ SF} \times 1\frac{1}{2}" \text{ THICK} = 77 \text{ CF}$$

JOINTS

$$4 \text{ JOINTS @ } .0729 \text{ SF} \times 5.5625 = 1.62 \text{ CF}$$

$$2 \text{ JOINTS @ } .03645 \text{ SF} \times 5.5625 = \underline{.40 \text{ CF}}$$

$$\underline{\underline{2.0 \text{ CF}}}$$

FILL RECESSES ⇒

LEVELING/PICKING ⇒ 4'1/2" φ TO 6'3/4" φ, 3" DEPTH


$$\left(\frac{.11045 + .2485}{2} \right) \cdot 25 = .04 \text{ CF SA} \times 2400 = \underline{\underline{1 \text{ CF}}}$$

ANCHOR RECESSES ⇒ 4'1/2" SQ. TO 6'3/4" SQ, 3" DEPTH


$$\left(\frac{.14063 + .31691}{2} \right) \cdot 25 = .06 \text{ CF SA} \times 8400 = \underline{\underline{5 \text{ CF}}}$$


DRILL & GROUT ANCHORS 84 - 1 1/2" φ HOLES × (3' LONG)

$$84 \cdot (.00690) \cdot (3) = 1.74 \text{ CF} = \underline{\underline{2 \text{ CF}}}$$




TYPICAL 20' PANEL





SECTION
TYPICAL PRECAST




ANCHOR BOLT

1

DETAIL

SCALE: 1"=1'-0"





LEVELING/PICKING DEVICE

2

DETAIL

SCALE: 1"=1'-0"

12-10-01




ANCHOR BOLT

1

DETAIL


SCALE: 1"=1'-0"



2" x 3/8" x 1'-8" Anchor Straps

13 per panel

78 total



12-10-01

RET

REMOVALS (EA SILL)

LOCATION	SF	2'-0"	ALT "A" (+9)	ALT "B" (+5)
2-17-16	2346.5	174 cy	96 cy	92 cy
17-20	2346.5	174 cy	96 cy	92 cy
2.M. 54 57	1470.17	109 cy	64 cy	60 cy
58-61	1971.73	146 cy	82 cy	78 cy
2-65 68-69	2616.14	194 cy	106 cy	102 cy
66-69	2524.5	187 cy	94 cy	90 cy
	<u>13,275.54</u>	<u>984 cy</u>	<u>538 cy</u>	<u>514 cy</u>
<u>AVG'S</u>	2,212.6 sf	164 cy	90 cy	86 cy

Minatitlan Locks

R. Allier

10 MAR 2002

1) Emergency Dam Sill

a) Width - Escalated from Aug 2000

$$\frac{117}{117} = \frac{x}{145} \quad x = 25' 6"$$

b) Length - 110' 0"

c) Propose to lower sill 1'-9", since the Emergency Dam is not used.

d) The Emergency Dam Sill will be lowered 1'-9" using steel raising and pneumatic hammers within the dewatered chamber.

e) Vol of concrete removal: $Vol = (110')(1.75')(25') / (27 ft^3/yd^3)$

$$Vol = 175.2 yd^3$$

$$Wt = 361 tons$$

2) Chain Fender Sills

a) Pedro Miguel - Minatitlan Lake Side

(Aug 2000)

1) The 1/2 chain fender sill must be lowered in-the-wet. No bulkheads are installed 1/2 in which to dewater this portion of the chamber.

a) Dimensions: width

$$\text{Scaled: } \frac{110'}{198.5'} = \frac{x}{22}$$

$$x = 12.57'$$

$$\text{Say } x = \underline{\underline{12' 6''}}$$

a) Propose to lower sill 1'-0"

4) Vol of concrete removal: $Vol = (110')(1')(12.5') / (27 ft^3/yd^3)$

$$Vol = 51 yd^3$$

$$Wt = 102 tons$$

5) In-the-wet removal

a) Saw cut & pneumatic hammer w/ hydraulic excavator

b) drill holes & Briston

3) Pedro Miguel - Between MG 57+55 - 58+61 (Aug 6/27)
1) 500 width - 2-sided

$$\frac{182.5}{94.5} = \frac{x}{6.5} \quad K = 10.6'$$

2) The wall will be lowered with the chamber dewatered

3) Vol of concrete removed:

$$\text{Vol} = (110') (1') (10.5') / (27 \text{ ft}^3 / \text{yd}^3)$$

$$\text{Vol} = \underline{\underline{42.8 \text{ yd}^3}}$$

$$\text{WT} = \underline{\underline{86.6 \text{ TONS}}}$$

4) Removal - saw cut & pneumatic hammer in-the-dry

Appendix 7. – Scope of Work

**MEMORANDUM OF AGREEMENT (MOA)
BETWEEN
THE PANAMA CANAL COMMISSION (PCC)
AND
THE DEPARTMENT OF THE ARMY
OF THE UNITED STATES OF AMERICA**

CONTROL No. 97-003

WORK ORDER No. _____

1. Reference enclosed scope of work statement to study and provide a preliminary design to raise miter gate heights and lower the critical miter gate sills to increase allowable vessel draft in the Panama Canal, which shall be performed under this Work Order and MOA 97-003.
2. Schedule: See Scope of Work.
3. The total effort will require \$ _____ (_____ thousand dollars with 00/100). The budget estimate is attached. The Panama Canal Commission (PCC) will provide an Interagency Service Support Agreement (ISSA) indicating the funding level that the U.S. Army Corps of Engineers (USACE) can bill against. Account No. _____.
4. All funds shall be provided to the USACE Mobile District for distribution as required. Mail funding documents to the Commander, U.S. Army Corps of Engineers, Mobile District.
5. The principal representatives for the MOA and Work Order are as listed below:
 - 5.a. The administrative principal representatives for the MOA and Work Order are:
 - 5.a.1. For the USACE Mobile District:
Mr. Billy Brown;
Phone no. (334) 694-4253; facsimile no. (334) 690-2327;
E-mail address: Billy.R.Brown@sam02.usace.army.mil;
Mailing address: U.S. Army Corps of Engineers, Mobile District,
P.O. Box 2288, Attn.: PM-LA
Mobile, AL 36628.
 - 5.a.2. For the PCC Contracting Division:
Ms. Gloria Gibson;
Phone no. (507) 272-4075; facsimile (507) 272-3253;
E-mail address: FMCO-____@pancanal.com;
Mailing address: Panama Canal Commission,

Unit 2300 (FMCO)
APO AA 34011-2300.

5.b. The technical principal representatives for the Work Order are:

5.b.1. For the USACE Pittsburgh District

Mr. Allen Remaly;

Phone no. (412) 395-7257; facsimile no. (412) 644-6815;

E-mail address: Allen.T.Remaly@lrp02.usace.army.mil;

Mailing address: USACE, Pittsburgh District;

1000 Liberty Avenue

Pittsburgh, PA 15222

5.b.2. For the PCC Canal Capacity Projects Office:

Mr. Juan Wong H.;

Phone no. (507) 272-5843; facsimile no. (507) 272-6137;

E-mail address: juanwong@pancanal.com;

Mailing address: Panama Canal Commission, CCL,

Unit 2300 (CCL-JW)

APO AA 34011-2300.

6. All communications which may change the terms of this Work Order shall be routed through the USACE Mobile District administrative principal representative (these are generally matters dealing with budget, schedule or additional effort). The communications dealing with the technical aspects of the project shall be addressed to the USACE-Pittsburgh District technical principal representative.
7. The work/services provided under this Work Order shall be provided by the USACE Pittsburgh District in-house labor unless otherwise approved.
8. The USACE Pittsburgh District shall provide the following reports in triplicate to the PCC administrative principal with a copy furnished to the USACE Mobile District administrative principal:
 - 8.a. Monthly progress report.
 - 8.b. Monthly billing with funds status.
9. Intellectual property rights: All information, findings and reports resulting from the execution of this contract shall become property of the Panama Canal Commission. No use nor reproductions of this information is permitted without the previous written authorization from the PCC.

10. Amending or modifying this Work Order: The PCC and USACE Mobile and Pittsburgh Districts shall mutually agree to any change to this Work Order before beginning work. No work shall be executed until the PCC and USACE Mobile District have signed the modification/amendment to the Work Order.
11. Additional coordination of details and responsibilities will be noted in the Scope of Work.

For the Panama Canal Commission:

Contracting Officer
Contracting Division
Department of Financial Management

Date

For the Department of the Army:

J. David Norwood
Colonel, Corps of Engineers
District Engineer, Mobile District

Date

**PANAMA CANAL COMMISSION (PCC)
CONTRACTING DIVISION**

**DETERMINATION AND FINDINGS
UNDER ECONOMY ACT**

ISSA No. 97-003 (WORK ORDER No. ____)

This determination is made under the authority of the Economy Act, 31, U.S.C. 1535, as implemented by FAR subpart 17.5 and pursuant to FAR 17.504 (a).

1. BACKGROUND INFORMATION

The Panama Canal operates its locks systems continuously on a 24-hour, 365 days a year, passage of deep draft oceangoing vessels. The Panama Canal operates with a series of locks to raise the vessels from the Pacific to the Atlantic Ocean and vice-versa. The vessels are raised to Gatun Lake to a nominal height of 85 feet above sea level by water locks. The locks are twin lane with a total of three lift at Gatun Locks in the Atlantic terminal; at the Pacific terminal, Miraflores Locks provides for two lifts to an intermediate Miraflores Lake, 54 feet above sea level, and Pedro Miguel Locks for a single lift to Gatun Lake.

The lock chambers are 110 feet wide by 1,000 feet long. The maximum allowable vessel draft is of 39.5 feet. The minimum depth over the locks sills is 41 feet and of 45 feet at the navigational channels. The locks operates with eighty (80) miter gates (MGs), double skinned, horizontally braced, riveted design, of different sizes ranging in heights of 54 to 82 feet and approximate weights of 500 to 790 tons.

The Canal Capacity Projects Office was formed in 1998 to develop a long-term strategy for different scenarios for the next 50 years to provide support facilities with the purpose of designing long-range master plan to augment Canal capacity and capability to meet future traffic demand and customer service in a reliable, efficient and competitive way.

These studies include the upgrading of current Canal infrastructure; incorporate modern lock technology and water saving methods to existing facilities; construction of new locks; study alternate systems for raising and lowering vessels; additional sources of water supply, storage and hydropower; making navigational channel improvements; insuring environmental concerns at all phases of study.

The proposals to increase Canal throughput by augmenting vessel draft beyond the existing 39.5 feet limitation by means of raising Gatun Lake level, by increasing lake miter gate heights and by reducing critical sill elevations, require an in-depth study to define the structural modifications, preliminary designs and extent of work involved in order to assess a cost/benefit analysis of the alternative solutions.

2. FINDINGS

The PCC proposes to issue Work Order No. _____, under the subject Interagency Service Support Agreement (ISSA No. 97-003) with the USACE to study and provide preliminary design of proposal to raise the lake miter gates and to reduce the critical miter gate sill elevations to provide for additional vessel draft. The study would provide analysis, preliminary designs, conclusions and recommendations on the results of the gathered information for improvements in structures and operations of existing and future facilities.

This action complies with FAR 6.002, in that it is not being entered into with another agency for the purpose of avoiding competition requirements. Neither the servicing agency or any contractor has commenced work on this acquisition.

This action is considered to be in the best interest of the Government because:

- (a) The PCC has not evaluated the structural requirements to increase the height of lake miter gates, nor the structural requirements to lower the critical miter gate sills, in order to increase vessel draft. A limited in-house experience in the structural modification of riveted double skin miter gates requires contracted support. Due to the high impact of the locks structures and equipment in the operating efficiency of the Canal, the PCC requires this critical information based on expert opinion to insure extended and reliable equipment service life.
- (b) This contract requires engineers and technicians with experience in structural engineering design. The U.S. Army Corps of Engineers (USACE) Pittsburgh District has performed structural design, modifications, specifications and finite element analysis on a varied range of miter gates, including those with riveted and with double skin designs in continental locks and waterways with similar head and load characteristics.
- (c) The USACE Pittsburgh District Structural Design Group and its engineers and technicians are considered highly knowledgeable and with safe and consistent design practices for locks and dams by its peers and other District engineers in the Corps.
- (d) The USACE Pittsburgh engineers/technicians are knowledgeable of the PCC mission, structures and operating conditions. They were also involved in different studies for the PCC such as the 1995 USACE Structures Conditions Assessment Report which prompted many actions and projects to upgrade facilities, and the 1999 Water Pressures in Locks Chamber Studies.
- (e) The locks miter gates and valves are one of the most critical equipment for the lockages and transit of vessels through the Panama Canal. A delay or failure in its operations affects the throughput capacity of the entire Canal. The efficient operation, reliability, maintenance, repair, and control of the locks miter gates are thus essential for the expeditious and safe operation of the Canal.

- (f) The present studies to improve on existing facilities and to consider future capacity expansion requires the consideration of increased permissible draft for Panamax vessels. The alternative to increase water level in Gatun Lake requires to make structural changes to lake miter gates at Gatun and Pedro Miguel Locks. The alternative to lower the critical miter gate sills at Pedro Miguel Locks requires structural modifications to the sills and the miter gates. Proper design and evaluation of modifications at the onset of the contract is critical to successfully comply with all the design, reliability, cost, time and safety parameters.
- (g) The PCC will provide plans and information on existing facilities to facilitate study, information and discussions as required. The study by an expert, senior structural engineer in the area of structural designs for miter gates and concrete sills is necessary to insure that the best system and value is obtained as it is in the best interest of the PCC.
- (h) The cost of the proposed work order is considered to be fair and reasonable because the USACE Pittsburgh prices are based on GS-9 through GS-13 pay levels, plus overhead, supervisory, office automation, administrative and costs for supplies.

3. DETERMINATION

Based on the above, and in accordance with FAR 17.503, Determination and Findings requirements, I hereby determine that the services described in the Work Order No. _____ cannot be obtained as conveniently and expeditiously by contracting directly with a private source. It is in the best interest of the PCC to issue this work order to the USACE Pittsburgh District.

Manager
Contracting Officer
Contracting Division
Financial Management Department

Date

PANAMA CANAL COMMISSION (PCC)

ISSA No. 97-003 (WORK ORDER No. ___)

**SCOPE OF WORK FOR THE STUDY AND PRELIMINARY DESIGN
TO RAISE MITER GATE HEIGHTS AND LOWER MITER GATE SILLS
TO INCREASE ALLOWABLE VESSEL DRAFT**

1. BACKGROUND INFORMATION

The Panama Canal operates its locks systems continuously on a 24-hour, 365 days a year, passage of ocean going vessels of up to a maximum allowable draft of 39.5 feet. The Panama Canal operates with a series of locks to raise the vessels from the Pacific to the Atlantic Ocean and vice-versa. The vessels are raised to Gatun Lake at a nominal height of 85 feet above sea level by water locks. The lock chambers are 110 feet wide by 1,000 feet long. The minimum depth is 41 feet over the locks sills and 45 feet in the navigational channels.

The locks operates with eighty (80) miter gates (MGs) of different sizes ranging in heights of 54 to 82 feet and approximate weights of 500 to 790 tons. The miter gates are double skinned, horizontally framed structures with floatation chambers. The miter gates presently operate with an electro-mechanical system consisting of a 40 hp electrical motor going through a series of gear reducers, up to a final bullgear which connects to the miter gate via a strut arm to open/close the gates under 2 minutes.

The lock chambers are fed by one lateral culvert 18 feet in diameter and a shared centerwall culvert of same cross-sectional area. Water from the main culverts is fed to the chamber by 10 lateral culverts with 5 openings each, evenly distributed along the locks chamber floors.

Water movement into and out of the chambers is controlled by rising stem valves (RSVs). The RSVs work in pairs and are 10 ft. wide and 18 ft high and weigh 12 tons. The RSVs are positioned at the beginning and the end of each chamber. There are a total of 116 RSVs in all three locks. Their construction is of welded steel running on sliding bearings.

The centerwall culvert can move water from either the east or west chambers. These are regulated by cast iron 7-foot diameter cylindrical valves (CVs) at the lateral culverts. There are a total of 120 CVs in all three locks.

Present projects to widen the Gaillard Cut are expected to increase the Canal throughput from 38 vessels a day to a sustainable capacity of 43 vessels per day. Work is expected to be completed by the year 2002. Additional capital investment projects to procure additional tugs, towing locomotives, hydraulic miter gate and valve operators, centralized

locks control system, rehabilitate locomotive track, and a modern vessel positioning will complement the cut widening project.

Market studies indicate that by the year 2010 the capacity of the Canal will be saturated. The average Canal Waters Times (CWT), an internal efficiency measure, will exceed 24-hours, deteriorating customer service. Restrictions during locks outages for maintenance and upgrading will further add to transit times.

The Canal Capacity Projects Office was formed in 1998 to develop a long-term strategy for different scenarios for the next 50 years to provide support facilities with the purpose of designing long-range master plan to augment Canal capacity and capability to meet future traffic demand and customer service in a reliable, efficient and competitive way.

These studies include the upgrading of current Canal infrastructure; incorporating modern lock technology and water saving methods to existing facilities; studying alternate systems for raising and lowering vessels; constructing new locks; finding additional sources of water supply, storage and hydropower; and making navigational channel improvements.

The proposals to increase Canal throughput by augmenting vessel draft beyond the existing 39.5 feet limitation by means of raising Gatun Lake level, by increasing lake miter gate heights and by reducing critical sill elevations, require an in-depth study to define the structural modifications, preliminary designs and extent of work involved in order to assess a cost/benefit analysis of the alternative solutions.

2. GENERAL INFORMATION

Data analysis and recommendations to improve existing facilities and to consider future capacity expansion requires experienced and accurate structural design calculations to insure structural and equipment reliability and integrity through its expected operating life cycle.

The objectives of this study are for the USACE Pittsburgh District to study and provide preliminary designs to alternatives for raising lake miter gates and to lower critical miter gate sills to allow for increased vessel draft beyond the maximum allowable of 39.5 feet. Design work on effects and means to reduce impact to locks structures and equipment affected by increase of vessel draft is also required.

All information, data, findings, recommendations, conclusions, and reports generated from the execution of this contract shall become sole property of the Panama Canal Commission. No use nor reproductions of this information is permitted without the previous written authorization from the PCC. All major equipment purchased under this contract shall also become property of the PCC.

3. DESCRIPTION OF WORK TO BE PERFORMED

The USACE Pittsburgh District shall provide all labor, materials and services to perform the studies, analysis and preliminary designs to increase allowable draft in the Panama Canal beyond the present vessel limitation of 39.5 feet maximum for the plans described below. The study will consider four major alternatives to be analyzed and evaluated. See attached sketches for miter gate locations and existing sill heights:

- a- Increase Height of Gatun Lake Miter Gates: In order to allow increased permissible draft, one option proposed is to raise the height of Gatun Lake over its nominal 85 feet to the extent possible. In order to contain the water, the MGs nos. 21 through 40 at Gatun Locks and MGs 50 through 69 at Pedro Miguel Locks must be raised accordingly. The Contractor shall provide structural calculations and preliminary design on modifications to the miter gates as required. Assessment of impact and proposed solutions to miter gate machinery recess, other openings at the locks, and locks walls shall be considered. 88.5
- b- Increase Height of Miraflores Lake Miter Gates: In order to allow increased permissible draft, one option proposed is to raise the height of Miraflores Lake over its nominal 54 feet to the extent possible. In order to contain the water, the MGs nos. 100 through 119 at Miraflores Locks must be raised accordingly. The Contractor shall provide structural calculations and preliminary design on modifications to the miter gates as required. Assessment of impact and proposed solutions to miter gate machinery recess, other openings at the locks, and locks walls shall be considered.
- c- Lower Gatun Lake Miter Gate Sills: To allow for increased vessel draft, the lake MGs nos. 37 through 40 at Gatun Locks and MGs nos. 50 through 53 at Pedro Miguel Locks sills and upstream emergency dam and caisson seat sills may be lowered accordingly to the extent possible. The Contractor shall provide structural and civil calculations and preliminary designs on modifications to lower miter gate sills and to extend the miter gate seals. The Contractor shall also perform an assessment of the impact and proposed solutions to adjacent underwater structures and operating machinery.
- d- Lower Critical Miter Gate Sills: To permit increased draft in transiting vessels, the critical downstream sills of miter gate nos. 54 through 69 may be lowered accordingly to the extent possible. The Contractor shall provide structural and civil calculations and preliminary designs on modifications to lower miter gate sills and to extend the miter gate seals. The Contractor shall also perform an assessment of the impact and proposed solutions to adjacent underwater structures

The USACE Pittsburgh District shall provide knowledgeable senior and junior engineers and technicians for the analysis and preliminary design of study to include assessment of existing structures, consider alternative solutions, evaluate and select best option, prepare preliminary designs, estimate quantities of labor, materials and performance times for

modifications, general project guidance, monthly progress, final reports and presentations.

The USACE Pittsburgh District will study existing conditions and infrastructures in the locks, miter gate machinery operating machinery, gate weight, height, construction, repairs, overhauls, and maintenance, different operating modes, varied vessel configurations, different water level as it effects to transit operations.

The USACE Pittsburgh District will provide for effective technology transfer to PCC Canal Capacity Projects Office personnel to create in-house capabilities for future modification of studies. The completed study shall also address and recommend areas that require further consideration and analysis.

The proposed modifications and designs shall minimize the effect in Canal operations, requiring a minimum number and duration of outages to accomplish the modifications. Ease of installation and maintenance of proposed solutions is very important in this project. The study will also suggest further studies and considerations in the event that the PCC decides to proceed with these modification projects.

An on-site familiarization and recognizance 3-day trip of existing field conditions at the PCC locks and surrounding areas by three performing team members is required and to discuss needs, gather information, view lockage and transit operations, and define design limitations. A second 2-day trip by two performing team members is required to inspect the sill area during the Miraflores Locks MGs 100-101 dry chamber scheduled for August 16-27, 1999.

4. PCC SUPPORT

The PCC will provide plans, drawings, field conditions, operating procedures, mean and range of water levels, and general information to facilitate studies and discussions.

All traveling from Pittsburgh, PA to Panama should have previous approval by the PCC Contracting Officer (CO). The PCC will reimburse to the USACE personnel all air travel, lodging, per diem, and ground transportation according to approved Federal Travel Regulations, prescribed by the General Services Administration, in effect on the dates of performance of this contract and/or any delivery order.

Estimated costs for all travel to be performed under this contract/delivery order must be included in the total cost of services to be performed. Reimbursement of travel expenses will be made separately from the cost of services performed on the basis of each travel occurrence. Reimbursement will be made on the basis of the following:

- a- Per diem: Reimbursed based on the established rates (\$59 daily in Panama includes meals and incidentals).

- b- Lodging: Reimbursed for actual cost incurred up to the stated limits. Lodging will be arranged in PCC quarters to the extent possible.
- c- Airfare and Rental Car/Taxi: Reimbursement will be made on the basis of actual costs incurred. Airfare will be reimbursed for coach class, 30-day, non-restricted airline tickets.
- d- Miscellaneous expenses: Reimbursement will be made on the basis of actual costs incurred as permissible in accordance with the established guidelines.

Prior to each travel occurrence, PCC will request the official travel order for the Contractor by completing Form No. 504 "Request and Authorization for Official Travel" (pink form) and obtaining the necessary approvals and forward the form to the Contractor.

Upon completion of travel, the Contractor shall complete the reverse side of the "Travel Expenses Report" form and return it to the PCC Contracting Division (FMC) with the original copies of air tickets, receipts and necessary supporting documents on actual expenses incurred. No allowable expenses will be reimbursed proper documentation and verification of costs incurred.

5. SCHEDULE

Within two weeks of contract award, the USACE Pittsburgh District shall provide to the PCC CO for his review and acceptance, a detailed plan with activities, resources, scheduling, time table, and cost estimates for the study and preliminary design of proposed work.

The completed study including plans, design, calculations, reference material, methodology, data gathering and final report presentation shall be completed within four (4) months from date of contract award.

The USACE Pittsburgh District shall provide written monthly reports in triplicate by the fifth day of each month. The USACE Pittsburgh District shall submit five (5) copies of the final report, studies, preliminary design and recommendations with attachments, drawings, calculations, and supporting documents. Additionally, a copy shall also be submitted in electronic form on disc in Word, AutoCAD, Microstation, Excel, Access, and PowerPoint formats, as applicable.

Panama Canal Authority

Contract No. , Delivery Order No. 1

SCOPE OF WORK TO COMPLETE THE STUDY AND PRELIMINARY DESIGN TO RAISE MITER GATE HEIGHTS AND LOWER MITER GATE SILLS TO INCREASE ALLOWABLE VESSEL DRAFT

1. BACKGROUND INFORMATION

The Panama Canal operates its locks systems continuously on a 24-hour, 365 days a year, passage of ocean going vessels of up to a maximum allowable draft of 12.0 m. The Panama Canal operates with a series of locks to raise the vessels from the Pacific to the Atlantic Ocean and vice-versa. The vessels are raised to Gatun Lake at a nominal height of 25.9 m above sea level by water locks. The lock chambers are 33.6 m wide by 305 m long. The minimum depth is 12.5 m over the locks sills and 13.7 m in the navigational channels.

The locks operates with eighty (80) miter gates (MGs) of different sizes ranging in heights of 16.5 to 25.0 m and approximate weights of 230 to 360 metric tons. The miter gates are double skinned, horizontally framed structures with floatation chambers. The miter gates presently operate with an electro-mechanical system consisting of a 40 hp electrical motor going through a series of gear reducers, up to a final bullgear which connects to the miter gate via a strut arm to open/close the gates under 2 minutes.

The lock chambers are fed by one lateral culvert 5.5 m in diameter and a shared centerwall culvert of same cross-sectional area. Water from the main culverts is fed to the chamber by 10 lateral culverts with 5 openings each, evenly distributed along the lock chamber floors.

Water movement into and out of the chambers is controlled by rising stem valves (RSVs). The RSVs work in pairs and are 3.1 m wide and 5.5 m and weigh 5.5 metric tons. The RSV2 are positioned at the beginning and the end of each chamber. There are a total of 116

RSVs in all three locks. Their construction is of welded steel running on sliding bearings.

The centerwall culvert can move water from either the east or west chambers. These are regulated by cast iron 2.1 m diameter cylindrical valves (CVs) at the lateral culverts. There are a total of 120 CVs in all three locks.

Present projects to widen the Gaillard Cut are expected to increase the Canal throughput from 38 vessels a day to a sustainable capacity of 43 vessels per day. Work is expected to be completed by the year 2002. Additional capital investment projects to procure additional tugs, towing locomotives, hydraulic miter gate and valve operators, centralized locks control system, rehabilitate locomotive track, and a modern vessel positioning will complement the cut widening project.

Market studies indicate that by the year 2010 the capacity of the Canal will be saturated. The average Canal Waters Times (CWT), an internal efficiency measure, will exceed 24-hours, deteriorating customer service. Restrictions during locks outages for maintenance and upgrading will further add to transit times.

The Canal Capacity Projects Office was formed in 1998 to develop a long-term strategy for different scenarios for the next 50 years to provide support facilities with the purpose of designing long-range master plan to augment Canal Capacity and capability to meet future traffic demand and customer service in a reliable, efficient and competitive way.

These studies include the upgrading of current Canal infrastructure; incorporating modern lock technology and water saving methods to existing facilities; studying alternate systems for raising and lowering vessels; constructing new locks; finding additional sources of water supply, storage and hydropower; and making navigational channel improvements.

The proposals to increase Canal throughput by augmenting vessel draft the existing 12.0 m limitation by means of raising Gatun Lake level, by increasing lake miter gate heights and by reducing critical sill elevations, require an in-depth study to define the structural

modifications, preliminary designs and extent of work involved in order to assess a cost/benefit analysis of the alternative solutions.

2. GENERAL INFORMATION

Data analysis and recommendations to improve existing facilities and to consider future capacity expansion requires experienced and accurate structural design calculations to insure structural and equipment reliability and integrity through its expected operating life cycle.

The objectives of this study are for the Contractor to study and provide preliminary designs and cost estimates for alternatives for raising the locks lake miter gates and to lower critical miter gate sills to allow for increased vessel draft beyond the maximum allowable of 12.0 m. Design work on effects and means to reduce impacts to locks structures and equipment affected by increase of vessel draft is also required. Work under this Scope of Work was initiated in September 1999 under a previous contract but only partially completed. The work under this contract is for the full completion of the work and submission off the required reports.

All information, data, findings, recommendations, conclusions, and reports generated from the execution of this contract shall become sole property of the Panama Canal Authority (ACP). No use or reproductions of this information is permitted without the previous written authorization from the ACP. All major equipment purchased under this contract shall also become property of the ACP.

3. DESCRIPTION OF WORK TO BE PERFORMED

The Contractor shall provide all labor, materials and services to perform the studies, analysis, preliminary designs and cost estimates to increase allowable draft in the Panama Canal beyond the present vessel limitation of 12.0 m maximum for the plans described below. The study will consider four major alternatives to be analyzed and evaluated. The work was originally started under ISSA No. 97-003, Work Order No. 24, and has been completed to about a 50% level of completion. The work required under this Delivery Order shall be for

the full completion of the work required for the study and preliminary design with presentation of the required draft and final reports. See sketches previously provided for miter gate locations and existing sill heights:

- a- Increase Height of Gatun Lake Miter Gates: In order to allow increased permissible draft, one option proposed is to raise the height of Gatun Lake over its nominal 25.9 m to the extent possible. In order to contain the water, the MGs nos. 21 through 40 at Gatun Locks and MGs nos. 50 through 69 at Pedro Miguel Locks must be raised accordingly. The Contractor shall provide structural calculations and preliminary design on modifications to the miter gates as required. Assessment of impact and proposed solutions to miter gate machinery recess, other openings at the locks, and locks walls shall be considered.
- b- Increase Height of Miraflores Lake Miter Gates: In order to allow increased permissible draft, one option proposed is to raise the height of Miraflores Lake over its nominal 16.5 m to the extent possible. In order to contain the water, the MGs nos. 100 through 119 at Miraflores Locks must be raised accordingly. The contractor shall provide structural calculations and preliminary design on modifications to the miter gates as required. Assessment of impact and proposed solutions to miter gate machinery recess, other openings at the locks, and locks walls shall be considered.
- c- Lower Gatun Lake Miter Gate Sills: To allow for increased vessel draft, the lake MGs nos. 37 through 40 at Gatun Locks and MGs nos. 50 through 53 at Pedro Miguel Locks sills and upstream emergency dam and caisson seat sills may be lowered accordingly to the extent possible. The contractor shall provide structural and civil calculations and preliminary designs on modifications to lower miter gate sills and to extend the miter gate seals. The contractor shall also perform an assessment of the impact and proposed solutions to adjacent underwater structures and operating machinery.
- d- Lower Critical Miter Gate Sills: To permit increased draft in transiting vessels, the critical downstream sills of miter gate nos.

54 through 69 may be lowered accordingly to the extent possible. The Contractor shall provide structural and civil calculations and preliminary designs on modifications to lower miter gate sills and to extend the miter gate seals. The Contractor shall also perform an assessment of the impact and proposed solutions to adjacent underwater structures.

The USACE (Pittsburgh District) shall provide knowledgeable senior and junior engineers and technicians for the analysis and preliminary design of study to include assessment of existing structures, consider alternative solutions, evaluate and select best option, prepare preliminary designs, estimate quantities and costs of labor and materials and estimate performance times for modifications, develop general project guidance, and prepare monthly progress and the final reports and presentations as required.

The Contractor will study existing conditions and infrastructures in the locks, miter gate machinery operating machinery, gate weight, height, construction, repairs, overhauls, and maintenance, different operating modes, varied vessel configurations, different water level as it effects to transit operations.

The Contractor will continue to provide continuous and effective technology transfer to ACP Canal Capacity Projects Office personnel through day-to-day contact to create in-house capabilities for future modifications of studies. The completed study shall also address and recommend areas that require further consideration and analysis.

The proposed modifications and designs shall minimize the effect in Canal operations, requiring a minimum number and duration of outage to accomplish the modifications. Ease of installation and maintenance of proposed solutions is very important in this project. The study will also suggest further studies and considerations in the event that the ACP decides to proceed with these modification projects.

An on-site familiarization and recognizance 3-day trip of existing field conditions at the ACP locks and surrounding areas by three performing team members was performed under the previous contract and no further visits to Panama are required to discuss

needs, gather information, view lockage and transit operations, and define design limitations.

3. ACP SUPPORT

The ACP will provide plans, drawings, field conditions, operating procedures, mean and range of water levels, and general information to facilitate studies and discussions.

4. SCHEDULE

Within two weeks of contractor award, the Contractor shall provide to the ACP CO for his review and acceptance, a detailed plan with activities, resources, scheduling, time table, and cost estimates for the completion of the study and preliminary design and cost estimates of proposed work. In accordance with the requirements of the Agreement, no travel to Panama will be needed or accomplished to complete the requirements of this Scope of work.

The submission of the draft report including plans, design, calculations, reference material, methodology and data gathering shall be submitted for review within 10 weeks of receiving the notice to proceed. The final report presentation shall be completed within four (4) weeks from the date of receiving the ACP comments on the draft report. The ACP will furnish comments on the draft report within 30 days of receipt.

The Contractor shall provide written monthly reports in triplicate by the fifth day of each month. The Contractor shall submit five (5) copies of the draft and final report to include studies, preliminary design and recommendations with attachments, drawings, calculations, and supporting documents. Additionally, a copy of the final report shall also be submitted in electronic form on disc in Microsoft Office 2000, AutoCAD, and Microstation, as applicable. All work shall be prepared in the SI units of measure.



AUTORIDAD DEL CANAL DE PANAMA
PANAMA CANAL AUTHORITY
ORDEN DE COMPRA/PURCHASE ORDER

CONTRATISTA/CONTRACTOR
 US ARMY CORPS OF ENGINEERS
 ROOM 630 WANNAMAKER BLD
 100 PENNS SQ EAST
 PHILADELPHIA, PA 17307

REVENAR AV BLD 710
 AUTORIDAD DEL CANAL DE PANAMA
 PROY CAPACIDAD CANAL
 BUILDING 714, EL PRADO STREET, BALBOA
 PANAMA,
 Republica de Panama
 FACTUMAR A BLD 710
 AUTORIDAD DEL CANAL DE PANAMA
 ACP - CC 010003
 P.O. BOX 025413
 MIAMI, FL 33102-5413

CODIGO DE CONTRATISTA/VEENDOR NO.
 0060930725

TERMINOS DE PAGO/PAYMENTS TERMS
 Neto 30 días

TERMINOS DE ENTREGA/DELIVERY TERMS
 Pagado por Contrato

TERMINOS DE RECEPCION/RECEIPT TERMS
 DDU PANAMA

ORDER NO. 0060930725
 ORDER DATE 05/17/05
 ORDER TIME 13:25
 ORDER BY: [Blank]
 ORDER FOR: [Blank]
 ORDER VALUE: [Blank]
 ORDER TYPE: [Blank]
 ORDER STATUS: [Blank]
 ORDER COMMENTS: [Blank]

LINEA LINE	NO. DE ARTICULO / DESCRIPCION ITEM NO./DESCRIPTION	FECHA DE ENTREGA DELIVERY DATE	CANTIDAD QUANTITY	UNIDAD UNIT	PRECIO UNITARIO UNIT PRICE	MONTO EXTENDED AMOUNT
	<p>- Aducción: Leo Cain Tel: 334-690-3440 Fax: 334-690-3734</p> <p>- ACUSE DE RECIBO Y ACEPTACION DE LA ORDEN:</p> <p>Mediante fecha y firma de Persona Autorizada en el espacio abajo provisto, (Artículo 49) Numeral 6 del Reglamento de Contratación de La ACP, la Contratación tendrá un plazo de hasta tres días una vez recibida la orden, para comunicar su aceptación. Favor remitirlo vía Fax al (507) 272-7661</p> <p>Personas autorizada (aceptación) _____ Fecha: _____</p>					
<p>"CLAVES/CLAS DEL CONTRATO"</p> <p>- Son todos los artículos aplicables del Reglamento de Contrataciones de la Autoridad del Canal de Panamá, específicamente: 10, 17, 18, 19, 43, 44, 45, 46, 47, 48, 49, 55, 64, 69, 71, 73, 76, 77, 78, 81, 82, 90, 91, 92, 95, 99, 100, 101, 102, 123, 124, 125, 126, 127, 130, 131, 32, 133, 134, 135, 136, 137, 138, 139, 140, 144, 152, 153, 154, 155, 156, 158, 162, 165, 166, 169, 170, 172, 173, 175, 176, 214, 217, 218, 219, 220, 221, 222, 223, 225, 226. Para obtener el texto completo, sírvase dirigirse de Internet: - http://www.panama.com/procadsp/procadsplegal.html</p> <p>- TRIBUTOS, IMPUESTOS, DERECHOS TASAS, CARGOS, O CONTRIBUCIONES DEL PAIS DE ORIGEN: El proveedor o contratista certifica que el precio propuesto incluye todo tributo, impuesto, derecho, tasa cargo o contribución, de carácter nacional, estatal o municipal del país de origen. En virtud de esta certificación no cabe ninguna reclamación.</p> <p>- CONTROVERSIAS RELACIONADAS CON LOS CONTRATOS: En referencia a los artículos No. 100 y 101, los procesos administrativos para la resolución de controversias serán los siguientes en el orden que se establezca: -a. Mediación o Conciliación -b. Arbitraje de Derecho La instancia administrativa que se establece para la resolución de controversias será el Centro de Conciliación y Arbitraje de Panamá. Todo arbitraje será de Derecho.</p> <p>- RESOLUCION ADMINISTRATIVA DEL CONTRATO POR CAUSA IMPUTABLE AL CONTRATISTA.</p>						
<p>FIRMA DEL OFICIAL BR CONTRATACIONES / SIGNATURE OF CONTRACTING OFFICER</p>						
<p>TERMINOS Y CONDICIONES: Se lea a las condiciones y condiciones detalladas en los artículos del Reglamento de Contrataciones y procedimientos por referencia en esta orden. Terms and Conditions: See terms and conditions detailed in the clauses referenced in this order.</p>						
<p>TOTAL</p>						<p>Continued ...</p>



ACIP - Autoridad del Canal de Panamá
 PANAMA CANAL AUTHORITY
ORDEN DE COMPRA/PURCHASE ORDER

CONTRATISTA/CONTRACTOR
 US ARMY CORPS OF ENGINEERS
 ROOM 630 WANNAMAKER BLD
 100 PENNS SQ EAST
 PHILADELPHIA, PA 17107

ENVIAR AL SEPTO
 AUTORIDAD DEL CANAL DE PANAMA
 PROJ CAPACIDAD CANAL
 BUILDING 714, EL PRADO STREET, BALBOA
 PANAMA,
 Republica de Panama
 FACTURAR AL/BILL TO
 AUTORIDAD DEL CANAL DE PANAMA
 ACP - CC 010003
 P.O. BOX 025413
 MIAMI, FL 33102-5413

COMUNICACIONES DE CONTRATISTA/VEHICULO NO. (MM09)30725

TERMINOS DE PAGO/PAYMENT TERMS
 No. 30 días

TERMINOS DE ENTREGA/DELIVERY TERMS
 Pagado por Contratación

TERMINOS DE ENTREGA/DELIVERY TERMS
 DDU/PANAMA
 SUBCANTON NEGOCIOS BARBARRA A. ROSARIO M

BARBARRA QUE YU SOBWA

ORDEN DE COMPRA NO. (PURCHASE ORDER NO.)	REVISION NO. (REVISION NO.)	PAGINA (PAGE)
SAAC20000310	0	2
PARA IDENTIFICAR LOS ITEMS, INCREMENTOS Y FACTURAS CON EL NUMERO DE ORDEN DE COMPRA Y LA DESCRIPCION DEBE SER EN "SERIES A". A TODOS LOS ENVIOS CON LAS LETRAS SOBWA QUE.		
FECHA DE PAGO DE 20 DIAS DESPUES DE RECIBIR LA INVOICE. INCREMENTOS Y FACTURAS DEBE SER EN "SERIES A". A TODOS LOS ENVIOS CON LAS LETRAS SOBWA QUE.		
FECHA DE ORDEN (ORDER DATE)	FECHA DE ENTREGA (DELIVERY DATE)	FECHA DE CANCELACION (CANCELLATION DATE)
26-APR-2001	L. TOALA	
EL CARGO DE REVISIONES OFICIAL DE CONTRATACIONES DEBE SER REVISADO POR EL CARGO DE REVISIONES OFICIAL DE CONTRATACIONES		

LINEA LINE	NO. DE ARTICULO / DESCRIPCION ITEM NO / DESCRIPTION	FECHA DE ENTREGA DELIVERY DATE	CANTIDAD QUANTITY	UNIDAD UNIT	PRECIO UNITARIO UNIT PRICE	MONTO EXTENDED AMOUNT
1	ESTUDIOS PARA EL RYABATABAR LAS ALTURAS DE LAS COMPUTERTAS Y LAS ELIVACIONES DE LOS QUICIOS, VER DOCUMENTOS ADJUNTO.	06-JUL-2001	1	Patch	36,844.3400	36,844.34
TOTAL						36,844.34

FIRMA DEL OFICIAL DE CONTRATACIONES / SIGNATURE OF CONTRACTING OFFICER

TERMINOS Y CONDICIONES: Sujeto a los términos y condiciones detalladas en los artículos del Reglamento de Contratación e instrucciones por referir en este orden
 Terms and Conditions: Subject to the terms and conditions detailed in the clauses referred in this order.

FACTURA: Enviar factura original y copia a la dirección descrita en "FACTURAR AL"
 La Autoridad del Canal de Panamá está exenta de todo impuesto aduanal o municipal.
 Invoice: Send invoice original and copy to the "BILL TO" Address shown above. Tax/Panama Canal Authority is exempt from all duties and municipal taxes.

Appendix 8. – Design Manuals and USACE Engineering Manuals

Design Manuals and USACE Manuals

<u>Ref.</u>	<u>Description</u>	<u>Date</u>
AISC ASD	Manual of Steel Construction, 9 th Ed.	1989
EM 1110-2-2104	Strength Design for Reinforced-Concrete Hydraulic Structures	30 June 1992
ACI 318-99/ 318R-99	Building Code Requirements for Structural Concrete (318-99)/and Commentary (318R-99)	June 1999
EM 1110-2-2703	Lock Gates and Operating Equipment	29 Feb. 1984
EM 1110-2-2105	Design of Hydraulic Steel Structures	31 Mar. 1993
MNL 120-92	PCI Design Handbook, Precast and Prestressed Concrete	1992
	PCI Design Handbook, Precast and Prestressed Concrete	1971

Appendix 9. – Correspondence

Allwes, Rich LRP

From: Allwes, Rich LRP
Sent: Wednesday, November 21, 2001 4:19 PM
To: 'jgribar@pancanal.com'
Cc: Remaly, Allen T LRP; Zovack, Frank LRP; Harkness, Andy LRP
Subject: MG Sill and Seal Modification
Importance: High

Tracking:	Recipient	Delivery	Read
	'jgribar@pancanal.com'		
	Remaly, Allen T LRP	Delivered: 11/21/2001 4:20 PM	Read: 11/26/2001 8:56 AM
	Zovack, Frank LRP	Delivered: 11/21/2001 4:20 PM	
	Harkness, Andy LRP	Delivered: 11/21/2001 4:20 PM	Read: 11/23/2001 8:45 AM

John:

I would appreciate if you or your staff would review the attached document and drawing. I believe that some of the miter gate sills do not need to be modified as originally proposed. I would appreciate if you could provide a reply via email or conference call by close of business 27 November. The drawing is in MicroStation format. If you need the drawing in AutoCad format, I can convert it but some information may not port properly.

Respectfully,

Rich Allwes
Structural Engineer
USACE-CELRP-ED-DS
412-395-7294

Panama Canal

Study and Preliminary Design to Raise Miter Gate Heights and Lower Miter Gate Sills To Increase Allowable Vessel Draft

Richard A. Allwes, USACE-CELRP-ED-DS
21 November 2001

- A. The Scope of Work is to consider the following four (4) alternatives to increase draft:
1. Increase Height of Gatun Lake Miter Gates:
 - a. Gatun Locks: raise MGs Nos. 21-40
 - b. Pedro Miguel Locks: raise MGs Nos. 50-69
 2. Increase Height of Miraflores Lake Miter Gates:
 - a. Miraflores Locks: raise MGs Nos. 100-119
 3. Lower Gatun Lake Miter Gate Sills:
 - a. Gatun Locks: lower MG Sills Nos. 37-40
 - b. Pedro Miguel Locks: lower MG Sills Nos. 50-53
lower upstream emergency dam sill
lower upstream caisson seat sill
 4. Lower Critical Miter Gate Sills:
 - a. Pedro Miguel Locks: lower MG Sills Nos. 54-69
- B. USACE Current Progress and Request for Clarification:
1. The present plan proposed by the Pittsburgh District is to raise the heights of Gatun Lake and Miraflores Lake by a height of 3 in and not to increase any of the heights of the miter gates in the three (3) locks as proposed in Items 1 and 2 (a. and b. in the Scope of Work). In order to raise the lake elevations by 3 in and not increase the heights of the miter gates, the entrance velocity of the vessels will have to be decreased to prevent overtopping of the miter gates. The reduced vessel velocity study is completed. Boots are required for the direct-connect cylinders to prevent floating lake debris and water from entering the machinery recess areas. In addition, bulkheads are required for the machinery access areas to protect the galleries from flooding.
 2. ACP is requested to review the attached Pittsburgh District's Minimum Draft Drawing for concurrence. It was compiled from as-built drawings and plates

Panama Canal

Study and Preliminary Design to Raise
Miter Gate Heights and Lower Miter Gate Sills
To Increase Allowable Vessel Draft
21 November 2001

provided by ACP. The Minimum Draft Drawing serves as the basis for modifying miter gates sills and seals. The following discrepancy is noted for the record.

- a. The upstream emergency dam sill of Miraflores Locks was removed according to Isthmian Canal Commission Dwg 7065 M-28 (revised 2-5-68) and provides a sill elevation EL +11.3. The Panama Canal Elevations Diagram Plate (NIVELES.DGN) provides a sill elevation EL +13.0 for the upstream emergency dam. ACP is requested to verify that the emergency sill elevation is EL +11.3.
3. ACP proposed miter gate sills to be lowered for all three (3) locks. However, a review of the Pittsburgh District's Minimum Draft Drawing reveals that a majority of the proposed sills do not need to be lowered, specifically:

Gatun Locks:	MG Sills Nos. 37-40
Pedro Miguel Locks:	MG Sills Nos. 50-53
	Upstream emergency dam sill
	Upstream caisson seat sill

A review of the Minimum Draft Drawing reveals that drafts above the sills are equal to or greater than 42.2 ft.

4. The miter gate sills planned to be lowered by the Pittsburgh District are MG Sills Nos. 54-69 of Pedro Miguel Locks. The current draft at minimum Gatun Lake Elevation (L.W. EL +81.5) is 40.5 ft. The sills will be lowered 1.0 ft. Accordingly, the miter gate seals of MGs Nos. 54-69 of Pedro Miguel Locks will be extended 1.0 ft.
5. The MG Sills Nos. 13-20 of Gatun Locks should be lowered 1.0 ft since they restrict draft to 40.58 ft at the lowest chamber pool (EL +27.0). ACP is requested to provide concurrence to lower these MG sills 1.0 ft and extend the MG seals 1.0 ft.
6. The current proposal is to remove approximately 2.0 ft of each sill and then raise a nominal portion of the sills 1.0 ft. Two methods of concrete removal are being investigated – hydroblasting and diamond wire concrete cutting.

Panama Canal

Study and Preliminary Design to Raise Miter Gate Heights and Lower Miter Gate Sills To Increase Allowable Vessel Draft 21 November 2001

7. Three MG sill preliminary designs (steel frame, precast panel, and cast-in-place) are being investigated and the preliminary designs will be evaluated in terms of cost and construction time.
8. A mix design is being investigated to achieve a design strength of 4,000 psi within 8 hours to minimize construction time. The time to demobilize and flood the chambers may be incorporated into the cure time of 8 hours to reduce total chamber outage time.
9. Since the miter gates are horizontally framed, the sill extensions will be designed to resist the maximum hydrostatic pressure corresponding to maximum lake or chamber pool elevation.

Allwes, Rich LRP

From: Allwes, Rich LRP
Sent: Wednesday, November 28, 2001 4:17 PM
To: 'jgribar@pancanal.com'
Cc: Zovack, Frank LRP; Harkness, Andy LRP
Subject: USACE Miter Gate Sill Modifications

Tracking:	Recipient	Delivery	Read
	'jgribar@pancanal.com'		
	Zovack, Frank LRP	Delivered: 11/28/2001 4:17 PM	
	Harkness, Andy LRP	Delivered: 11/28/2001 4:17 PM	Read: 11/28/2001 4:23 PM

Dear John:

I sent an email to you on 21 Nov requesting clarification concerning the sills to be modified. I plan on calling you tomorrow morning, 29 Nov at 7:30 am to discuss the email that I sent. Frank Zovack and I tried to call you by phone but you were out of the office.

In addition, I have been speaking with demolition contractors and the following questions have been raised that require input from ACP. I would appreciate if you or someone on your staff could provide a response to the following questions by Monday, 3 Dec:

1. Concrete:
 - a. Availability of logs of any concrete cores taken through the years.
 - b. Availability of concrete strength data.
 - c. Any information on the type of aggregate used at the different sites. We are of the opinion that the basalt was used as aggregate on the Pacific side, the Atlantic side used natural gravel, and we are not sure what type of aggregate was used for the middle locks.
 - d. Any information on the original concrete mix designs or any info on the original concrete.
2. Steel reinforcement in the miter gate sills. For Pedro Miguel MG Sills Nos. 54-69, is the steel reinforcement shown in Mitering Lock Gates, Dwg. 5169 present in the sills? When I was there in Sept 1999 at Miraflores Locks dewatering, it appeared that the sills had been modified and the massive steel reinforcement was removed. We need to know if the steel exists at Pedro Miguel since this would have an impact on the method, size, and speed of concrete removal.
3. Cuttings and slurry: are there special requirements (environmental) for collection and/or disposal?
4. Availability of equipment (cranes and sizes) to handle large slabs of concrete? Or must demolition contractor arrange for all equipment?
5. Source of power - from lock, generator, or contractor supplied?
6. Bonding requirements for contractor.
7. Anticipated number of weeks/months for lead time for start of work by contractor - it will take time to schedule equipment, personnel, and arrange for shipping of equipment from Miami, Fl to Panama - this will affect cost.

8. The contractor will work 2 12-hr shifts/day - is this a problem?
9. Housing - supplied by ACP or must contractor arrange for housing.
10. Chamber outage:
 - a. What is the chamber outage cost per day?
 - b. What is the maximum acceptable time for the chamber closure for the miter sill work?
 - i. It is assumed that the period is for dewatering, sill modification, and flooding chamber.
 - c. What is the length of time to dewater the Pedro Miguel chambers to have access to MG Sills Nos. 54-69?
 - d. What is the length of time to flood the chambers?
10. Water quality - are sulphates a problem for concrete mix?

Respectfully,

Rich Allwes
Structural engineer
USACE - Pittsburgh District 412-395-7294

Allwes, Rich LRP

From: Allwes, Rich LRP
Sent: Thursday, January 24, 2002 11:32 AM
To: 'jgribar@pancanal.com'; 'fhdelgado@pancanal.com'
Cc: Zovack, Frank LRP; Remaly, Allen T LRP; Tankosh, John E LRP
Subject: Panama Canal Study to Increase Draft

Dear John and Rigoberto:

The subject report was sent to your office on 13 Dec 01 for review and was most likely received on 17 Dec 01. I would appreciate if you would let me know when we will receive your comments. In addition, I sent emails to John on 21 Nov 01 and 28 Nov 01 requesting information on the sills and clarification for the study. I appreciate the information provided by Rigoberto on his visit to the Pittsburgh District. However, a majority of the information requested was not received to date. I would appreciate receiving the information, if it is available.

Rigoberto indicated to John Tankosh that the sill elevations are incorrectly shown on the drawing entitled, "Miter Gate Study – Minimum Draft" for the D/S portion of Pedro Miguel Lock. However, on review, the sills elevations are correctly shown (according to PCA Dwg 7046), except that the Chain Fender Sill was not included in the drawing. The Chain Fender Sill was not included in the Scope of Work. Specifically, the sill, sill elevations, and minimum drafts are:

Sill Description	Elevation (ft)	Minimum Draft (ft)
MG 62-65 Sills (Safety)	+13	40.5
MG 66-69	+13	40.5
MG 70-73 (Lower Guard)	+11 $\frac{1}{3}$	42.2
Caisson Sill	+11 $\frac{1}{3}$	42.2
Chain Fender	+13	40.5

As a result, we are currently investigating lowering the Chain Fender Sill by 1.0 ft using in-the-wet demolition (hydraulic excavator and a rotary rock cutting head). However, we need to know if the emergency chain is in use or will be used in the future and the impact of lowering the sill by 1 ft on the structure.

Respectfully,

Rich Allwes
 Structural Engineer

Appendix 10. – ACP Comments and USACE Responses

Comments on
Panama Canal Study to Increase Draft
Draft Report by USACE, Pittsburgh District

13 December 2001

Cesar Kiamco, Locks Team
March 14, 2002

USACE Responses
10 April 2002

General Response: The Corps appreciates the comments and insight provided by the ACP. Mr. Rigoberto Delgado was particularly helpful in providing concrete material properties and informing us of our omission of the lower chain fender sill during his visit to the Pittsburgh District in December 2001. This information was important and his efforts were appreciated. It should be noted, however, that for several aspects of the project our requests for additional information or clarifications were not addressed (see Appendix 9). In those areas we used the best information we had available and engineering judgment to develop assumptions necessary to complete the study. Some of the comments made concerning the Draft Report are issues originally raised by the Corps and our responses to those comments reflect our belief that the assumptions made are sound and result in an accurate evaluation of the alternatives. Richard Allwes, EC-DS

Page 1

1. Third line: Use caisson instead of bulkhead.

Response: Revision was made to the report. Richard Allwes, EC-DS

2. Last line of first paragraph: Use ACP instead of PCA.

Response: Revision was made to the report. Richard Allwes, EC-DS

3. Third line from the bottom: ACP does not have drawings 5158-9 and 5161-5. Are you referring to drawings 5158 and 5161 of the mitering gates?

Response: Yes, the miter gate drawings are referenced and revisions were made to the report. Miter gate drawing No.s 5158 and 5161 are referenced. Richard Allwes, EC-DS

Page 2

4. Third paragraph: The statement “Gatun Lake is held at EL +87.5 ft when sufficient water is available” is somewhat simplistic. Elevation +87.5 is only a nominal figure used for purposes of communication. Actual elevations may exceed the nominal maximum elevation; they are variable and are not controlled to the millimeter.

Response: Gatun Lake is held at the nominal elevation EL + 26.67 m (+87.5 ft) when sufficient water is available, although actual lake elevations may exceed this nominal level. Richard Allwes, EC-DS

5. Gatun Lake has a Ruling Curve that varies seasonally between elevations 25.75m (84.5’) to 26.7m (87.5’). Gatun Lake elevation exceeds 87.5 feet just 5% of the time. Without additional water regulation (new lakes), it will be very difficult to maintain the lake elevation at 87.75 feet.

Response: The operational feasibility of raising and maintaining Gatun Lake to EL +26.75 m (+87.75) is beyond the Scope of Work. Richard Allwes, EC-DS

6. Miraflores Lake is not held at EL +54.5 ft. This elevation is only a nominal figure used for purposes of communication. Actual elevations vary greatly about the nominal elevation and are not controlled to the millimeter. Lake regulation is based on visual observation, experience and judgment. The elevation of the lake varies as a function of lockages at Pedro Miguel (one lift lock) and Miraflores (two lift lock). Every Pedro Miguel chamber spilled to Miraflores Lake increases the Miraflores lake level about 0.15 ft; while, every chamber taken from Miraflores locks from the lake decreases the lake level about 0.11 ft.

Response: The nominal elevation for Miraflores Lake is EL +16.61 (+54.5 ft). It is recognized that the lake elevation is affected by the operation of both Pedro Miguel and Miraflores Locks. However, the operational feasibility of raising and maintaining Miraflores Lake to EL +16.69 m (+54.75) is beyond the Scope of Work. Richard Allwes, EC-DS

Page 3

7. Raising Miraflores Lake 3 inches is something that happens several times every day. For deep draft ships, we let the lake rise to the maximum elevation.

Response: The Corps recommends raising and maintaining Miraflores Lake level to EL +16.61 (+54.75). This will permit Vessels to draft up to 40.75 ft, provided that the critical sills are lowered. Based on this comment, it appears that the recommendation is feasible, provided from an operations standpoint that the level may be maintained or an intermediate lake level may be maintained. Richard Allwes, EC-DS

8. To increase the elevation of Miraflores Lake, we must check Miraflores Dam and the bulkheads used for dewatering.

Response: A statement will be included in the report that ACP needs to assess the impact of raising Miraflores and Gatun Lakes by 76 mm (3 in) on the dams, shoreline structures, miter gates, and other structures. Richard Allwes, EC-DS

9. Raising Miraflores Lake 3 inches seems to entail a high cost since it requires a reduction in the entrance velocity of the ships. This decrease in velocity will result in an increase in the lockage time.

Response: The following points should be considered: 1) while the entrance velocity for the vessels is decreased, it occurs for only two lake chambers per transit, 2) the increase in transit time is very small in comparison o the CWT (24-30 hrs), 3) there is a small cost in terms of the small increase in lockage time for two lake chambers per transit, and 4) there is significant savings associated with the increased tonnage due to the increase in draft and this will more than compensate for the small increase in lockage costs. Richard Allwes, EC-DS

10. The report cites one of the objectives of lowering the miter gate sills as reducing transit times. How is this obtained? Does the reduction in transit time compensate for the increase in lockage time?

Response: The statement made in the report (Sec. 3.2.1) was "...reducing transit times during periods of low lake levels". The transit time during normal periods will slightly increase due to the reduced entrance velocity for a vessel for two lake chambers per transit. The overall transit cost will decrease due to the increase in tonnage. Richard Allwes, EC-DS

Page 4

11. Bottom of first paragraph: The report recommends that entrance velocity from the lakes to the upper chambers be reduced by 0.16 ft/sec at Miraflores and 0.36 ft/sec at Pedro Miguel and Gatún. Although they might be provided with velocity indicators, panamax ships are not this responsive. It is unrealistic to expect that such exact reductions in velocity will be made in practice.

Response: The lake levels may be raised 76 mm and the entrance velocities of the vessels need to be decreased to the theoretical velocities provided in the report to prevent overtopping of the miter gates for a vessel drafting 12.42 (40.75 ft). The velocity recommendations are based on theoretical values established in the 1996 report. Experience will provide the practical data in establishing achievable velocities of vessels and the associated surcharges. The theoretical velocities provide the basis for establishing vessel velocity. It should also be noted that vessels that draft 12.04 m (39.5 ft) may increase their entrance velocity since the surcharge is less due to the increase in draft in the lock chambers if the lakes are

raised and the critical sills are lowered. This will decrease the transit time (CWT) since the entrance velocities may be increased. Richard Allwes, EC-ED

12. Second paragraph: This year ACP will build two prototypes of rubber boots around the hydraulic pistons to fully watertight these openings. Depending on the results, ACP will implement this change at all gates.

Response: Acknowledged. Richard Allwes, EC-DS

13. Third paragraph: Your comment is based on the 1996 report. The condition was subsequently investigated. Our findings are different: Overloading due to sliding friction when the valve is lifted under head did not cause problems at some Rising Stem Valves (RSV). The problem occurred in two RSV's at Gatun Locks. Of interest, these valves were not subjected to the greatest operating head.

Response: Of the representative sampling that was tested in the June 1996 report, all RSV motors were overloading, except for the remaining valve at Miraflores Locks that had the original roller trains. As a result, it is believed that the friction was increased with the new sliding surface and is causing the overloading condition. The additional friction load is proportional to head and is ultimately carried by the H castings. The increased friction load may also contribute to a fatigue loading condition. Frank Zovack, EC-DE & Richard Allwes, EC-DS

14. Plate 1 needs to be modified to reflect chain fender sills elevations at lower Pedro Miguel lock at +13'. These sills are located between miter gates (MG) 58, 59, 60, and 61; and MG's 62, 63, 64, and 65. The other two sills are located downstream of the South caisson sill (East and West).

Response: This change was made to Plate 1 and is discussed in the report. Richard Allwes, EC-DS.

Page 5

15. First line: Change Table 2 to Table 3.

Response: Revision was made to the report. Richard Allwes, EC-DS

16. Table 3: Change Meguel to Miguel.

Response: Revision was made to the report. Richard Allwes, EC-DS

17. Paragraph 3.2.2: USACE recommends lowering the miter gate sills. If the sill is lowered, we must consider the possibility of having the edges rounded (as recommended by the Texas A&M University study) to improve water flow under

deep draft ships. A quarter round of a pipe 10, schedule 80 anchored to the edges would work.

Response: The embedded quarter round of pipe may be incorporated into the sill modification if and when the plans and specifications are developed. However, the Corps is skeptical that the minimal rounding/streamlining will have any beneficial affect to improve the flow of water beneath deep-draft vessels. Richard Allwes, EC-DS

Page 6

18. Change Meguel to Miguel in Tables 5 and 6.

Response: Revisions were made to the report. Richard Allwes, EC-DS

Page 10

19. Bottom of second paragraph: ACP has equipment and trained personnel to do this job.

Response: The costs were changed to reflect that ACP or a contractor is Panama will conduct the work. Richard Allwes, EC-DS

Page 12

20. 3.2.7.1b: Why is a water stop required between existing and new concrete?

Response: A waterstop was initially considered for the cast-in-place sections, but is not necessary and is not provided in any of the details and drawings. The last sentence of the paragraph states that water stops will not be used unless they are absolutely necessary. Waterstop are not necessary. No Revision was made to the report. Richard Allwes, EC-DS

Page 13

21. Construction Scheme for Precast Option: Add a short description of the leveling the precast units.

Response: A short description was provided and the combination lifting/leveling lugs provided in Plate 9, detail 2 was referenced. Richard Allwes, EC-DS

Page 16

22. Bottom of page: The estimate is based on having a contractor from outside of Panamá performing the demolition. Please note, however, that there is expertise within Panama. ACP owns 14 complete units for concrete wire cutting and 2

complete units of hydro-rehabilitation. Trained personnel have removed up to 10,000 tons of concrete in one year

Response: Estimates are changed to reflect the utilization of local contractors, fabricators, as well as the ACP wire saw units. Craig Carney, EC-EV

Page 17

23. Bottom of page: 3” raise of Miraflores pool: see “Page 3” comments above.

Response: The response to Comments No.s 7 through 10 are applicable. Richard Allwes, EC-DS

24. ACP is constructing a prototype with flexible rubber boots to make the strut arm connection to the MG watertight.

Response: Acknowledged. Richard Allwes, EC-DS

Page 18

25. Modification to Miter Gates: “, the additional loading on the girder is insignificant”. A finite element modeling (FEM) study should back this statement.

Response: This statement was made for two reasons. The first is that the miter gates at Panama are horizontally framed, not vertically framed. The loads transferred by a vertically-framed miter gate to a sill are significantly higher than the loads transferred by a horizontally-framed miter gate. The second, is that the additional loading on the miter gate is minor when Detail 1 of Plate 10 is closely reviewed. Full hydrostatic pressure acts on both sides of the miter gate extension and a portion of the existing miter gate skin plate. The net load is essentially the same as with the omega-type seal. There is a torsional load applied to the miter gate due to the contact pressure (miter gate deflection) and the offset of the edge-bulb seal, with respect to the centerline of the bottom girder. The bottom girder will not be solely required to carry the torsional load. The torsional load will be distributed through the miter gate by the diaphragms, since the extension stiffeners match the miter gate stiffeners (diaphragms) between the girders. A finite element study is beyond the scope of this study. The purpose of the study was to investigate the feasibility of extending the miter gates and to provide a preliminary design. A finite element study may be used during the final design of the miter gate extension to verify loadings and deflections. The report will be revised to state that the additional loading on the miter gate is minor. Richard Allwes, EC-DS

26. The assumption that the rubber seal does not transmit load to the sill is not correct:

Response: It was not assumed that the miter gate seal does not apply a load to the miter gate sill as a result of miter gate deflection. This issue was discussed with John Gribar on 29 November 2001. The lateral load applied to the sills was made equal to the hydrostatic pressure applied to the tributary area of the lowest girder with the chamber dewatered. This is an extreme loading condition. Richard Allwes, EC-DS

27. Physical evidence in the field shows signs that the sill receives load from the MG seal. There are imprints in concrete made by the seal.

Response: See comment No.s 26 and 26. Richard Allwes, EC-DS

28. A FEM analysis of the MG would show that the miter point deflects under load after the gates are mitered. At this point, the sill limits the deflection of the seal. The seal deforms, and picks up loads.

Response: See comment No.s 26 and 26. Richard Allwes, EC-DS

29. Construction and operational variations can cause unintended contact between concrete and seal and, hence, additional loading on the sill.

Response: The construction and operational variations may be addressed during final design. Richard Allwes, EC-DS

30. Welding of an 11/16" bracket plate to the all riveted, watertight bottom girder of the MG should be recommended with caution. The area is densely populated with rivets. Heat will cause nearby rivets to loosen. Water tightness will be lost.

Response: The rivets may be ring sealed with weldment or the rivets may also be replaced with structural bolts to eliminate this potential problem. Richard Allwes, EC-DS

31. At the quoin end, you need to provide a detail showing how you will prevent leaks through the intersection of reduced sill and seal of the miter gate extension.

Response: During the dewatering of the Miraflores Locks, the miter gates, seals, and quoin areas were inspected. It was determined that lowering the sill 1 ft would not interfere nor adversely affect the quoin seal. As a result, no modification is proposed for the quoin seal. Richard Allwes, EC-DS

Page 19

32. Second paragraph: For the purpose of the estimate, it is assumed that fabrication is done in the United States. Please note that the fabrication could be performed in Panama. The estimate would be different.

Response: Cost estimates are amended to reflect that the fabrication along with a majority of the other will be performed by local fabricators, contractors, or the ACP. Craig Carney, EC-EV

33. Third bullet from the bottom: Gates 54 through 69 are located at Pedro Miguel, not at Miraflores.

Response: Change was made to the report. Richard Allwes, EC-DS

Appendix 5

34. An estimate based on costs and construction practices in Panama would be more useful. We cannot make decisions based on estimates based on US costs. As examples of differences, we provide following comparison of US costs to those witnessed in Panama:

Response: Changes are made to the cost estimates to reflect the cost data information furnished through these comments. Craig Carney, EC-EV

35. Page 1/9: \$1,300.00/yd³ of concrete is too high. \$500.00/yd³ would be a better figure.

Response: The unit cost for concrete has been changed in the cost estimates. The new values are lower than the original furnished estimate, however, the Corps feels that \$500/cy is too low for precast concrete. Craig Carney, EC-EV

36. \$2/lb for reinforcing steel is also high, \$0.90/lb is better.

Response: Unit cost of reinforcing steel was lowered to \$1.00/lb. Craig Carney, EC-EV

37. Floating plant is not required, we pump concrete from the sidewalls.

Response: Floating plant eliminated from the cost estimates except for the lowering of the Chain Fender Sills for Pedro Miguel Locks (D/S side adjacent to Miraflores Lake). Craig Carney, EC-EV

Page 3/9

38. \$3,600.00/yd³ is too high. Considering that ACP has equipment and personnel, \$1,200.00/yd³ is a better estimate.

Response: Precision Demolition unit costs have been lowered. Note that \$1,200/cy has been used for the larger quantity demolition, but a higher unit cost was used for the smaller quantities for precision demolition. This accounts for

the setup and wire cutting, which is essentially the same for the differing quantities. Craig Carney, EC-EV

Page 4/9

39. \$150.00 per bolt can be reduced to half, as ACP can manufacture them.

Response: Estimate is changed to \$100 per bolt. Craig Carney, EV-EC

Appendix 6

40. Detail 1: Change 3 ¼", as it is difficult to measure to the middle of plate.

Response: This is a preliminary design drawing, and the dimension provided is with respect to the centerline of the girder. A shop drawing may provide a different dimension. Richard Allwes, EC-DS

Appendix 7

41. Bottom of page 6 asks for SI units for all work. ACP is an international organization. We have agreed to review the draft report in the English system. For the final report, you must use SI for all work.

Response: The original Scope of Work did not require metric units for all work (page 11). This requirement was added to the resubmitted Scope of Work (page 6). The report was changed to provide both SI and English units. The drawings were changed to SI units. The calculations will be provided in English units. Richard Allwes, EC-DS

42. **Plate No. 6:** Demolish 24" thick concrete to rebuild 12" seems unnecessary.

Response: This was one option that was explored but was not proposed as the final concept for the study. Richard Allwes, EC-DS

43. Plate No. 10: The existing seals have to be replaced periodically due to damage. Edge-Bulb Seal proposed looks weaker than the existing 'Ω'-shaped seal. Sometimes debris is caught under the gate or between the gate and sill. How will the extension, the seal and the bottom girder behave?

Response: The edge-bulb seal (pork chop seal) is commonly used for the horizontally-framed miter gates. The seal is durable, robust, and rarely needs to be replaced according to Operations. If there is a problem with deflection of the miter gates (ACP did not state any problems with excessive deflection of the miter gates during the visit to the locks on 22 September 1999, the edge-bulb seal may be mounted horizontally with respect to the gate and the miter gate sill may be extended so that the edge-bulb seals on the top of the miter gate sill. This was not

explored since ACP did not indicate any problems with deflection of the miter gates. Richard Allwes, EC-DS

44. What is the expected replacement time for the proposed seal? The proposed seals do not appear to be as strong as the existing seals.

Response: The Corps experience is that they get stiff with age but have lasted more than 50 years. According to Operations, the Corps rarely replaces these seals. Richard Allwes, EC-DS

45. Today, if a trapped log damages the omega seal, a diver unbolts the damaged piece and inserts a new one. If the extension were to be damaged, the miter gate would have to be removed and taken to the Industrial Division for repairs.

Response: The edge-bulb seal may be unbolted and replaced. Richard Allwes, EC-DS